LOCKWOOD'S TECHNICAL MANUALS

THE DRAWING & DESIGN OF JIGS, TOOLS & FIXTURES

PHILIP GATES

Digitized by the Internet Archive
in 2026

https://archive.org/details/jigstoolsfixture0000phil

THE DRAWING & DESIGN
OF
JIGS, TOOLS & FIXTURES

LOCKWOOD'S MANUALS

TRADE		
Gasfitting and Appliances.	Briggs.	6/–
Brick and Tile Manufacture.	Searle.	7/6
Clock Repairing and Making.	Garrard.	6/–
Watch Repairing and Cleaning.	Garrard.	6/–
Mechanical Dentistry.	Hunter.	6/–
Electro-plating.	Watt.	5/–
House Painting, Graining, &c.	Davidson.	7/6
Carpentry and Joinery.	Tredgold.	6/–
Roof Carpentry.	Collings.	2/6
Upholstering and Cutting Out.	Bitmead.	2/6
Cabinet Maker's Guide.	Bitmead.	3/6
Metal Plate Work.	Barrett.	3/6
Builders' Accounts.	Keen.	5/–
Superficial Measurement.	Hawkins.	4/–
TECHNICAL		
Engineering Drawing.	Malden.	8/6
Engineers' Screw Cutting	Pull.	2/6
Engineers' Measuring Tools.	Pull.	4/6
Slide Rule.	Hoare.	4/–
CRAFT-WORK		
Goldsmith's Handbook.	Gee.	6/–
Modern Fretcutting.	Makinson.	2/6
ART-WORK		
Illuminating and Missal Painting.	Whithard.	6/–
Letter Painting Made Easy.	Badenock.	2/–
EDUCATIONAL		
Portuguese Dictionary.	Elwes.	8/6
Hebrew and English Dictionary.	Breslau.	7/6
English and Hebrew Dictionary.	Breslau.	3/6
BUSINESS		
Foreign Commercial Correspondent.	Baker.	7/6
FARM		
Commercial Poultry Farming.	Toovey.	6/–
Stockowner's Veterinary Aid.	Archer.	7/6
GARDEN		
Bees for Pleasure and Profit.	Samson.	3/6

The above prices are net (postage extra).

LONDON: CROSBY LOCKWOOD & SON

JIGS, TOOLS AND FIXTURES

THEIR DRAWING AND DESIGN

(COVERING EQUIPMENT FOR PRACTICALLY ALL MODERN MACHINE TOOLS, WITH CHAPTERS ON SPECIAL EQUIPMENT AND DRAWING OFFICE PROCEDURE; ALSO GIVING NUMEROUS EXAMPLES FROM PRACTICE)

WITH

165 ILLUSTRATIONS AND DIAGRAMS AND 17 TABLES.

BY

PHILIP GATES

Production Engineer; Lecturer in Machine Construction and Drawing, Aylesbury Technical School; Author of "Tool and Machine Setting," "Capstan and Automatic Lathes."

LONDON

CROSBY LOCKWOOD AND SON

7 STATIONERS' HALL COURT, LUDGATE HILL, E.C. 4

1922

PREFACE

In preparing this work the author has endeavoured to deal with the subject in a simple manner, at the same time covering as wide a field as possible.

It is hoped that the fully qualified draughtsman will not look askance at it because the beginner, apprentice, as well as the man in the shop has been specially considered. To the latter a knowledge of just what happens behind the drawing-office doors, as herein given, should be of considerable use. The ambitious one, also, who seeks to forsake the spanner for the pencil, it is hoped, will not peruse it in vain.

The author desires to remind the reader that among tool and jig designers there exists such a diversity of opinion on some points that any method or design discussed in this work is not necessarily the only way out.

As it is possible this work may pass into the hands of one who is not already conversant with the ordinary rules of machine drawing, no apology is offered for including this in Chapter I.

In these days of high production the design of the necessary equipment is of vast importance, and it is doubtful whether any other occupation affords such splendid opportunities for the exercise of ingenuity, so that the inventive one is advised to push forward, and may great success attend his efforts.

The Writer desires to express his thanks to Messrs. Cubitt Engineering Co., Aylesbury, for permission to take the photographs for Figs. 20, 23, 122 and 33; to the National Automatic Tool Co., Indiana, U.S.A., for the illustrations for Figs. 25 and 155; to Mr. George Hay, A.M.I.Mech.E., M.I.A.E., Managing Director of "Jigs" Ltd., for the photograph of Fig. 47; to Messrs. Brown & Sharp, Providence, R.I., U.S.A., for Table No. 13; to Messrs. Newall Engineering Co., for Table No. 9; and lastly, to Messrs. E. W. Bliss Co., Brooklyn, U.S.A., for Table No. 12.

UNIFORM WITH THIS VOLUME

JUST PUBLISHED

255 *pp., with over* 300 *Illustrations and Six Plates*

Price 8s. 6d. *net*

MAXTON'S MANUAL OF ENGINEERING DRAWING

New Edition revised, with Additional Matter

By

LIEUT.-COMMANDER G. C. MALDEN, R.N.,

INSTRUCTOR IN METALLURGY, ROYAL NAVAL ENG. COLLEGE, KEYHAM

LONDON: CROSBY LOCKWOOD & SON

CONTENTS

CHAPTER I

PAGE

MECHANICAL DRAWING 1

Drawing Equipment—Representation of Materials—Lines—Dimensioning—Lettering—Bolts, Nuts and Screw Threads—Abbreviations—Selecting Views—Centre Lines—A Working Drawing.

CHAPTER II

SKETCHING. 10

The Value of Sketching—Proportion—Duplicates—Tabular Drawings—Oblique Projection.

CHAPTER III

FIRST CONSIDERATIONS IN THE DESIGN OF JIGS, TOOLS AND FIXTURES 14

Difference between Jigs and Fixtures—Their Value—Looking Ahead—Cost of Equipment—Quality of Product—Class of Labour—Single or Multiple Equipment—Remember the Tool Room—Elaboration—Co-operation—Properties of First-class Equipment.

CHAPTER IV

DRILL JIGS 23

Holes through Diameters—Location—Self-Centring Mechanisms—Locating Rough Components—Adjustable Supports—Clamping—A Simple Drill Jig—Drill Jig for Pistons—Jig for Use on Double Spindle Machine—"U" Washers—Jig Feet, "Jigging" a Component—Multiple Drill Head—Simplicity of Design—An Indexing Jig—A Jig Indexing in Four Planes—Continuous Drilling.

CHAPTER V

MILLING FIXTURES 52

Choice of Machine—Setting Spots—A Simple Fixture—String Fixtures—Continuous Milling—Indexing Fixtures—Clamps and Location (see Chaper IV).

CHAPTER VI

PAGE

CHUCKS AND TURNING EQUIPMENT 67

Mandrels—Expanding Mandrels—Special Purpose Expanding Mandrel—Spring Collets—Thread Chucks—Turning Fixtures—Indexing Fixtures—Cross Slide Tool Holders—Circular and Dovetail Form Tool Holders—End Working Tool Holders—Plain Holders—Bushes for Holders—"Floating" Holders—Tap Holders and Die Adapters—Turning Tools—Cutters for Box Tools—Flat Form Tools—Circular and Dovetail Form Tools—Shaving Tools.

CHAPTER VII

CUTTERS 95

Roller Milling Cutters—Inserted Tooth Cutters—Relieved Form Cutters—Hollow Mills—Running Stops—Cheap Type of Hollow Mill—Reamers—Expanding Reamers—Special Purpose Reamers—Boring Tools and Holders—Boring Cutters of Special Form—Flat Bits—Counter Bores and Spot-Facing Cutters—Countersink Cutters—Spot-Facing Cutters—Trepanning or Spirally Relieved End-Working Tools—Broaches.

CHAPTER VIII

SCREWING EQUIPMENT 119

Dies—Hinged Button Dies—Spring Dies—Taps—Double Taps—Chasing Tools—Thread Milling Cutters.

CHAPTER IX

GAUGES 128

Limits—Plug Gauges—Caliper Gauges—Scissor Gauges—Depth Gauges—Screw Thread Gauges—Profile Gauges—Combination Gauges—Variety—Materials.

CHAPTER X

PRESS TOOLS 142

Simple Blanking Tools—Multiple or Gang Tools—Holding Punches—Bolsters—Strippers—Stops—"Follow" Dies—Piloted Punches—Drawing Tools—Re-drawing—Combination Tools—Bending Tools—Special Forming Die—Sub-Presses—Materials.

CHAPTER XI

BROWN & SHARP CAMS 158

Feeds and Speeds—Direction of Spindle Rotation—Total Revolutions per Piece—Correcting the Revolutions—Selecting Gears—List of Operations—Determining Cam Surface—Plotting the Cam—Back Slide Cam—Front Slide Cam.

CHAPTER XII

PAGE
SPECIAL EQUIPMENT. 169

Truck Jig—Friction Screwdriver—Special Cut-Off and Forming Tool—Watertight Inlet Gland.

CHAPTER XIII

JIG AND TOOL OFFICE PROCEDURE 175

Personnel of a Jig and Tool Office—Duties of Jig and Tool Office —Method of Working—Detailing—Checking—Tracing—Filing and Recording—Alterations—Operation Sheets.

CHAPTER XIV

STANDARDIZATION 184

INDEX 191

ILLUSTRATIONS

CHAPTER I

FIG.		PAGE
1.	A.—METHOD OF SHARPENING PENCILS	2
	B.—CONVENIENT FORM OF SCALE	2
2.	A.—REPRESENTATION OF MATERIALS	3
	B.—SAMPLE LINES.	3
3.	A.—CORRECT DIMENSIONING	5
	B.—CORRECT DIMENSIONING	5
4.	A.—REPRESENTATION OF SCREW THREADS	6
	B.—HEXAGON NUTS	6
5.	ARRANGEMENT OF VIEWS	9

CHAPTER II

6.	A.—SKETCHING IN PROPORTION	11
	B.—TABULAR DRAWINGS	11
7.	OBLIQUE PROJECTION	12

CHAPTER III

8.	ALTERATION OF DESIGN TO FACILITATE MACHINING	19
9.	ALTERATION OF DESIGN TO FACILITATE MACHINING	22

CHAPTER IV

10.	LOCATING FOR DIAMETER DRILLING	24
11.	SELF-CENTRING MECHANISMS	26
12.	LOCATING METHODS	28
13.	ADJUSTABLE SUPPORTS	30
14.	CLAMPS	32
15.	CLAMPS	34
16.	SIMPLE DRILL JIG	36
17.	DRILL JIG FOR PISTONS	37
18.	DRILL JIG FOR DOUBLE SPINDLE MACHINE	39
19.	MULTI SPINDLE HEAD	42
20.	GROUP OF SIMPLE JIGS	44
21.	COMPONENT FOR JIGS IN FIG. 20	45
22.	INDEXING JIG	46

FIG. PAGE
23. JIG INDEXING IN FOUR PLANES 48
24. SPECIAL GUIDE PLATE FOR SUPPORTING DRILL . . 49
25. CONTINUOUS DRILLING 50

CHAPTER V

26. MILLING METHODS 53
27. MILLING METHODS 54
28. SETTING SPOTS 56
29. SIMPLE MILLING FIXTURE 58
30. FIXTURE FOR MILLING IN TWO PLANES 59
31. STRING FIXTURE 60
32. STRING FIXTURE 61
33. STRING FIXTURE 63
34. CONTINUOUS MILLING 64
35. INDEXING FIXTURES 66

CHAPTER VI

36. MANDREL HOLDING TWO COMPONENTS 67
37. MANDREL FOR ROUGH CORED COMPONENT . . . 68
38. MANDREL FOR SPLINED GEAR BLANKS 69
39. MANDREL FOR SPLIT PISTON RINGS 70
40. EXPANDING MANDREL 71
41. EXPANDING MANDREL 72
42. EXPANDING MANDREL FOR PISTONS 73
43. SPECIAL SPRING COLLET AND NOSE-PIECE . . . 75
44. THREAD CHUCKS. DRAW BACK 77
45. THREAD CHUCKS. PUSH OUT 77
46. TURNING FIXTURE 79
47. INDEXING FIXTURE FOR AERO ENGINE CRANK CASE . 80
48. TOOL POST DESIGN 82
49. CIRCULAR AND DOVETAIL TOOL HOLDERS. . . . 83
50. PLAIN HOLDERS 85
51. COLLET TYPE HOLDER 85
52. BUSHES FOR HOLDERS 86
53. "FLOATING" HOLDERS 87
54. TAP HOLDERS 88
55. TAP HOLDERS 88
56. DIE ADAPTERS 88
57. CUTTER FOR BOX TOOL HOLDER 91
58. FLAT FORM TOOL 91
59. CIRCULAR FORM TOOLS 91
60. DOVETAIL FORM TOOLS. 91
61. SHAVING TOOL 94

CHAPTER VII

FIG.		PAGE
62.	ROLLER MILLING CUTTERS	95
63.	INSERTED TOOTH CUTTERS	97
64.	RELIEVED FORM CUTTERS	99
65.	HOLLOW MILLS	101
66.	LARGE HOLLOW MILLS	101
67.	RUNNING STOPS	101
68.	CHEAP TYPE OF HOLLOW MILL	101
69.	REAMERS, PLAIN SOLID	103
70.	EXPANDING REAMERS	103
71.	SPECIAL PURPOSE REAMERS.	103
72.	SPECIAL PURPOSE REAMERS.	106
73.	SHELL REAMER ON BORING BAR	106
74.	BORING TOOLS	107
75.	BORING TOOLS	107
76.	BORING TOOLS	107
77.	BORING TOOLS	107
78.	BORING TOOLS	107
79.	BORING CUTTERS	109
80.	BAR CONSTRUCTION FOR LONG LIFE	109
81.	FORM BORING CUTTER	110
82.	STEPPED FORM CUTTERS	110
83.	FLAT BITS	112
84.	FLAT BITS, SIDE CLEARANCE	112
85.	SPOT-FACING AND COUNTERBORING	112
86.	COUNTERBORES WITH REMOVABLE PIN AND CUTTER	112
87.	COUNTERBORE WITH REMOVABLE CUTTER	112
88.	COUNTERSINK CUTTERS (SMALL WORK)	114
89.	COUNTERSINK CUTTERS (LARGE WORK)	114
90.	SPOT-FACING CUTTERS	114
91.	TREPANNING TOOLS	114
92.	SPOT-FACING TOOL FOR LARGE WORK	116
93.	FIXTURE FOR SPOT-FACING	116
94.	BROACHES	117
95.	KEYWAY BROACHES	117

CHAPTER VIII

96.	BUTTON DIE	120
97.	BUTTON DIE HINGED	120
98.	SPRING DIE	120
99.	RELIEF	123
100.	TAP DRAWING	123

FIG. PAGE
101. "SHELL" SIZING TAP 124
102. DOUBLE TAP 124
103. CHASING TOOLS, SINGLE POINT 126
104. CHASING TOOLS, WITH CREST RADIUS 126
105. THREAD MILLING CUTTER 126

CHAPTER IX

106. PLUG GAUGE 131
107. PLUG GAUGE, RENEWABLE ENDS 131
108. PLATE PLUG GAUGE 131
109. PIN PLUG GAUGE 131
110. CALIPER GAUGE 133
111. DECIDING WIDTH OF GAUGE 133
112. ADVANTAGE OF WIDTH 133
113. SCISSOR GAUGE 134
114. DEPTH GAUGES 134
115. DEPTH PLUG 134
116. MALE SCREW GAUGES 136
117. FEMALE SCREW GAUGES 136
118. PROFILE GAUGE 137
119. PROFILE AND POSITION GAUGE 137
120. COMBINATION GAUGE 138
121. COMPONENT FOR FIG. 120 138
122. GROUP OF GAUGES 139

CHAPTER X

123. SIMPLE BLANKING TOOL 142
124. MULTIPLE OR GANG TOOL 142
125. ARRANGEMENT OF PUNCHES FOR IRREGULAR BLANKS . 142
126. METHODS OF HOLDING PUNCHES 145
127. METHODS OF HOLDING PUNCHES 145
128. METHODS OF HOLDING PUNCHES 145
129. METHODS OF HOLDING PUNCHES 145
130. BOLSTERS 145
131. PUNCH WITH STRIPPER. 146
132. PRESSURE RINGS AS STRIPPERS 146
133. PRESSURE RINGS AS STRIPPERS 146
134. "KNOCKOUTS" 146
135. STOPS 148
136. DANGER OF FIXED STOPS 148
137. SPRING STOPS 148
138. TRIGGER STOPS 148

FIG.		PAGE
139.	FOLLOW DIES	149
140.	ADJUSTABLE GUIDES	149
141.	PILOTED PUNCHES	149
142.	STRAIGHT-THROUGH DRAWING DIES	151
143.	RE-DRAWING DIES	151
144.	DRAWING WITH PRESSURE RING	151
145.	COMBINATION TOOLS	153
146.	SIMPLE BENDING TOOLS	154
147.	BENDING WITH SPRING PAD	154
148.	ALLOWING FOR FOREIGN SUBSTANCES IN THE GUIDE PLATE	154
149.	SPECIAL FORMING OPERATION	155
150.	SUB-PRESSES	156

CHAPTER XI

151.	COMPONENT FOR B. & S. CAMS, FIGS. 152 AND 153	165
152.	LEAD CAM	165
153.	CROSS-SLIDE CAMS	168
154.	DIAGRAM SHOWING RELATION OF TOOLS TO TURRET AND MACHINE NOSE	165

CHAPTER XII

155.	TRUCK JIG UNDER M.S. DRILL	170
156.	FRICTION SCREW DRIVER	171
157.	SPECIAL CUT-OFF AND FORMING TOOLS	171
158.	COMPONENT PRODUCED BY FIG. 157	171
159.	WATERTIGHT INLET GLAND	173

CHAPTER XIII

160.	DRAWING RECORD FRAMES	177
161.	SYMBOL FOR INDICATING HEAT TREATMENT	179
162.	TOOL INDEX CARD	182
163.	OPERATION SHEET	183
164.	DRILL BUSHES	185
165.	REAMER BUSHES	185

TABLES

TABLE		PAGE
1.	PROPORTIONS FOR MILLING CUTTERS	96
2.	PROPORTIONS FOR INSERTED TOOTH CUTTERS	98
3.	PROPORTIONS FOR HOLLOW MILLS	100
4.	NUMBER OF REAMER TEETH	105
5.	PROPORTIONS FOR COUNTERBORES	113
6.	PROPORTIONS FOR SPOT-FACING CUTTERS	115
7.	PROPORTIONS FOR BUTTON DIES	119
8.	PROPORTIONS FOR SPRING DIES	122
9.	NEWALL LIMITS	129
10.	PROPORTIONS FOR PLUG GAUGES	130
11.	PROPORTIONS FOR RING SCREW GAUGES	135
12.	PUNCH AND DIE CLEARANCE	143
13.	NUMBER "00" BROWN AND SHARP CAM TABLE	163
14.	PROPORTIONS FOR DRILL BUSHES	186
15.	PROPORTIONS FOR REAMER BUSHES	186
16.	SOME MACHINE CAPACITIES	187
16A.	SOME MACHINE CAPACITIES	189

JIGS, TOOLS AND FIXTURES
THEIR DRAWING & DESIGN

CHAPTER I

MECHANICAL DRAWING

Drawing Equipment—Representation of Materials—Lines—Dimensioning—Lettering—Bolts, Nuts and Screw Threads—Abbreviations—Selecting Views—Centre Lines—A Working Drawing.

It is not intended in the short space of one chapter to attempt to deal in detail with the subject of mechanical drawing, but enough is given to assist the casual reader to a better understanding of drawings in general, and in particular those that follow.

Drawing Equipment.—Like the tools used in most trades and professions, those of the draughtsman have been improved, and so facilitate the production of drawings, and this with greater convenience.

The drawing-board and table has been replaced by the more elaborate stand and board fitted with sliding rule, and in some offices the drafting machine has been introduced. The ordinary equipment, however, remains much as before, but a word here on this may help.

With regard to the proper grade of pencil, different people will often get varying results with the same pencil; but for general work a good-class HB is very useful, though a H is often preferred, especially for centre lines, etc. For large work, especially lettering, a B will give excellent results.

The correct sharpening of a pencil is a great help to neat and accurate drawings, and the usual shape is that shown at A, Fig. 1, the flat side of the lead being used against the rule edge, by which means a line of unvarying thickness is obtained.

To assist in maintaining the point a 4″ or 6″ flat smooth file is a very useful addition to one's kit, though there are

now on the market some small pads, about 4″ × 1″, consisting of layers of fine glass-paper, which are stripped off as they become worn.

There is a wide choice of scales, but in the writer's opinion nothing can surpass the pattern as shown in section at B, Fig. 1, the round rib at the top forming a very quick and convenient means of handling.

For tool and jig work, graduations in one-tenth of an inch, as well as the usual divisions, will be found most suitable. For the purpose of taking measurements of existing machinery



FIG. 1.

A.—MOST SATISFACTORY FORM OF SHARPENED PENCIL.
B.—MOST CONVENIENT SECTION OF SCALE.

a 12″ or 6″ flexible rule, together with slide-gauge or calipers, will prove of much value.

With regard to drawing papers, it will be found that practice varies in different offices, but there are three that can be mentioned as being of general use : they are Cartridge Paper, Detail Paper and Tracing Paper.

The former is generally used where the drawing will be subjected to a lot of handling, or where a lot of erasing and redrawing may be necessary.

Detail paper is a finer and cheaper paper much used for small drawings, also for roughing out ideas generally, though good-class detail paper is often used for all drawings.

Tracing paper is employed occasionally where blue prints

are wanted quickly from an experimental drawing, and if the lines are put in with a good pencil the prints are quite good.

It may appear superfluous to mention drawing pins, but there are on the market a type where the pin is just lightly forced into the head, which is very dangerous when pressure is put on the head.

Representation of Materials.—Though in tool drawing



FIG. 2.

A.—METHOD OF INDICATING MATERIAL.
B.—LINES EMPLOYED IN MECHANICAL DRAWING.

it is not usual to rely too much on the indication of material by the style of line, there being such a great variety of steels, etc., used, it is necessary to be acquainted with their meanings.

Colours are even less employed, but for reference purposes they are given here.

Sections of various metals, insulating compositions, etc., are indicated by different methods of lining, as shown at A, Fig. 2. Others are added by firms according to the materials called for.

In making use of the colours some little skill or practice is necessary before neat results can be obtained. For large surfaces the colour is best washed on, that is, the surface of the paper is first damped with a brush containing clear water, and before it is dry the colour, a small amount at a time, is added at the top of the space and carefully brushed downwards, any surplus being removed by means of blotting-paper.

The colours in general use are as follows :

Prussian blue	for	Wrought iron.
Payenes grey	,,	Cast iron.
Purple	,,	Steel.
Crimson lake	,,	Copper.
Chrome yellow	,,	Brass or gunmetal.

Lines.—As the reader may be aware, the style of line used throughout the drawing is also of importance. At B, Fig. 2, will be seen sample lines, that as shown at No. 1 being used for the roughing-in of a drawing, construction lines, etc. No. 2 would be about correct for the finished outline ; while No. 3, consisting of alternate dots and dashes, is employed for centre lines, though very often No. 1 is used for this. There should be a distinct difference between Nos. 3 and 4, the latter being put in for edges not seen in the particular view being drawn yet are known to exist.

For indicating dimensions, a line made up of a series of dashes, as at No. 5, is often used, though many draughtsmen prefer the continuous line for this purpose.

Dimensioning.—The correct dimensioning of a drawing is of considerable importance, and pays for thought, both from the point of view of assisting the workman and the neatness of the finished drawing. The necessity for a lengthy search for a dimension should be avoided, and this can be done by their careful arrangement.

One dimension should lead up to another, and after a number of steps have been dimensioned an overall size should be added, as at A, Fig. 3, where the different shoulders are indicated, allowing the eye to almost automatically follow from one to the other ; and in close proximity is the overall size, providing a check on the drawing and also assisting the mechanic or store-keeper who may be responsible

for getting out the material. In the latter connection it is often the duty of a clerk or other non-technical person to make out a list of material required from drawings and then to hand this to whoever has charge of the cutting-off machines, so that it will be obviously an advantage to avoid the necessity for any calculating and very little thinking.

The dimensions should, as far as possible, be kept off the



FIG. 3.

CORRECT DIMENSIONING.

actual figure, especially where the latter is complicated, thereby avoiding confusion.

In the case of several diameters, as at B, Fig. 3, these are sometimes given by dimensioning on the plan view, with several lines passing through the centre at different angles; but where there are two or more diameters it is not good practice, and the method adopted at B should be followed, which leaves no possibility of doubt. The absence of figuring

as far as possible on the figure also helps the mechanic to visualize the object more quickly.

The extremities of the dimension lines should always touch another line, and the arrow must be put in so as to make it quite clear which lines are indicated.

In printing the figures or other remarks on drawings, they should always be written in one plane, so that they are immediately readable from one position. Some drawings have their lettering running in various directions, which is unsightly, inconvenient and unnecessary.

Lettering.—To print neatly and quickly requires con-



FIG 4

A.—METHOD OF REPRESENTING SCREW THREADS.
B.—METHOD OF DRAWING HEXAGON HEADS AND NUTS.

siderable practice, and in most cases, until skill is acquired, it will be necessary to draw parallel lines between which the letters are drawn. A common fault with printing is to mix capitals with small letters in the same word or words, another is to put in several types of lettering on the same sheet.

The various drawings throughout this work will give the reader an idea of lettering and the proportion of the letter or figure to the object itself.

Bolts, Nuts, Screw Threads.—When representing these

it is never necessary to give dimensions unless it is intended to depart from the standard (see Chapter XIV), it being quite sufficient to indicate the size and form in the case of the thread, as shown at A, Fig. 4. Hexagon heads or nuts are put in as shown at B, Fig. 4, where, for drawing purposes, the proportions are based on the diameter of the bolt portion.

The actual form of thread is not shown, but the methods usually adopted are shown at A, Fig. 3, the first being the neatest and the simplest.

Abbreviations.—Apart from actual dimensions, it is necessary in places to add brief instructions, and to accomplish this simply yet intelligibly a number of abbreviations have become more or less standardized and are here given :

C.I.	Cast iron.	f.	Machine or finish.
M.S.	Mild steel or machinery steel.	C/L.	Centre line.
		B.S.F.	British standard fine.
Ph.B.	Phosphor bronze.		
T.S.	Tool steel.	B.S.P.	British standard pipe.
H.S.S.	High-speed steel.		
Sq.	Square.	U.S.S.	United States standard.
B.P.	Blue print.		
Std.	Standard.	B.A.	British Association.
In.	Inch.	Whit.	Whitworth.
R.H.	Right hand.	Thd.	Thread.
G.A.	General arrangement.	Hex.	Hexagon.
		Hd.	Head.
L.H.	Left hand.	C/Bore.	Counterbore.
Deg.	Degree.	C/Sink.	Countersink.
Rad.	Radius.	C/Hnd.	Case-hardened.
MC.	Machine.	H. & G.	Harden and Grind.

Selecting Views.—As the essential point of a mechanical drawing is that it should convey the ideas of the draughtsman to the mechanic as clearly as possible, the selection of the correct view or number of views becomes important.

To draw an unnecessary view is wasteful and misleading ; to give insufficient views will give rise to innumerable queries.

As to the correct method of showing plans and elevations there exists some difference of opinion, American draughtsmen adhering to what is known as third-angle drawing and English to first angle.

While the practice of a particular office should be followed, it matters not what arrangement of views is given as long as what is intended is made perfectly clear.

Where the ordinary plans and elevations are not sufficient to convey the idea, section or part section drawings are added. In some cases there may be a plan, side elevation, end elevation and a sectional view, whereas in others the sectional view can be combined with, say, the end elevation, thus avoiding a view. Fig. 5 is an example of this. This is almost always done where the object is symmetrical about a centre line, one complete half being in section.

In cases where detail drawings (see Fig. 16) are drawn on the same sheet as the General Arrangement, views of the detail should be arranged as near to the original as possible, so that its exact shape and method of assembly can be immediately seen.

Centre Lines.—Both in the drawing office and the machine shop it is necessary to have some central point from which to work, and for this reason the insertion of centre lines is essential. They do not necessarily pass through the centre of the object, but through its most important point.

Take, for example, an automobile cylinder, the centre line would certainly pass through the cylinder bores, and another through the bore for the cam shaft, and others through as many more points of importance. The centre lines are generally put in first, and the object as it were built round it.

A Working Drawing.—To assist the reader to a clearer understanding of the various points mentioned it will be best to give a working drawing, and, ignoring questions of design for a moment, to point out the method of procedure.

The drawing (Fig. 5) represents a simple milling fixture for milling two flats on the component A. The part to be machined is marked in the usual way by placing a *f* thereon.

In this fixture the component is held by inserting its long stem into the hole B till the shoulder F rests on the top of the fixture, then by tightening up the nut C the pad D is drawn slightly, which causes it to grip the stem of the component, the pad being prevented from turning by a small key E.

The slot H, which is cast, and therefore saves a mechanic's time necessary to cut it out if left solid, is for holding down purposes.

To proceed with the drawing then. Having decided on the scale of the drawing, which, for jig and tool work, is generally full size, the centre lines for the plan and side elevation are drawn. The circles for the pad, screw and nut are next put in, drawing very lightly in case of an error, and then the circle for the hole B.

Having thus put in the most important part of the fixture,



FIG. 5.

SELECTION AND ARRANGEMENT OF VIEWS.

the size of the surrounding casting, which is not important, can be decided upon and drawn.

The end elevation and part section can now be put in, and after settling upon the material to be used the section can be correctly indicated.

The dimensions are now inserted, together with any necessary notes and detail numbers.

CHAPTER II

SKETCHING

The Value of Sketching—Proportion—Duplicates—Tabular Drawings—Oblique Projection.

The Value of Sketching.—Ability to make rapid and fairly accurate sketches is essential to the successful draughtsman, in fact it has been truly described as an auxiliary language.

Often it may be necessary to go into the machine shops, which may not be near at hand, to take details of a machine or tool, and to do this the machine may have to be stopped, obviously then the draftsman must not only be quick but reliable, for the forgetting of a point would entail another visit and stoppage which would not be viewed with pleasure.

It is also of great value when discussing the pros and cons of equipment, a few rapid sketches making one's ideas immediately clear. It might be mentioned that sketching is one of the finest ways of learning and remembering the construction of machine tools and details, many people would be surprised to find how weak is their detailed knowledge of various constructions, having looked at, passed by, and perhaps used a certain mechanism, quite certain that it has been understood, yet when called upon to put the idea on paper, difficulty is experienced.

On the machine bed with chalk, on the wall, on the palm of one's hand, many are the arguments settled by means of a few telling sketches.

Proportion.—There is one point that should be carefully observed, and that is that the various parts should be in correct proportion. In attempting to make a neat sketch this is often overlooked, and while it might be said that if the dimensions thereon are stated right, that is sufficient, it is very deceiving and often leads to a misunderstanding.

When turning a job in the lathe or working on the shaper the mechanic gets into the habit of allowing the machine slide to travel till the piece looks something like the drawing, and then applying the rule or other instrument.

A, Fig. 6, is an example of this where the shortest length is marked 4″ and a part considerably longer 2″, the diameters also being deceiving.

It will also be noticed that only one view is given, this is permissible when no error can possibly occur, which certainly is so in this case, the word or abbreviation for diameter being distinctly written after the figure.

Sketching pads made up of paper ruled in tenth of an inch



A	B	C	D	E		
10	4	2	3/4			6 off
7	3	2	3/4			10 off
6	2 1/2	1 1/2	5/8			32 off
4	1 1/2	1	1/2			18 off

FIG. 6.

A.—IMPORTANCE OF SKETCHING IN PROPORTION.
B.—TABULAR DRAWINGS.

squares are exceedingly useful, but the draughtsman should practise so as to be able to draw under any circumstances.

Duplicates.—Where rough sketches are called for in cases of great urgency the draughtsman will be well advised to lay a sheet of carbon paper between the sheets of his pad, so as to secure a duplicate, because such sketches, in their passage through the shops, generally become unreadable and in the

event of a mistake occurring due to this, the value of the duplicate is obvious.

Tabular Drawings.—It is often necessary to call for a number of parts very similar in form but differing perhaps in one or two dimensions. This is overcome by making one sketch of the part, but instead of putting the usual dimensions, letters are added as at B, Fig. 6. Below or near the sketch is then made out a tabular statement of the sizes required.

This is particularly useful where a number of parts of varying



FIG. 7.

OBLIQUE PROJECTION.

size are called for quickly, it being only necessary to fill in the figures.

Oblique Projection.—The method of laying out an object showing views in a certain relation as in Fig. 5 is termed orthographic projection, and while it is the usual method adopted, it is sometimes necessary, particularly when sketching an awkward piece, to make its general form obvious at once.

To do this, what is known as Oblique Projection is employed as shown in Fig. 7. The reader will observe that it has the appearance of perspective drawing except that lines going in the same direction are parallel.

With this style of drawing it is possible to explain a point

to anyone unacquainted with mechanical drawing and it also enables three dimensions to be given in one view.

To become skilled in the rapid sketching of objects thus projected, should not be difficult with practice.

The best results are obtained by placing the longest side of the piece horizontal, this prevents a distorted appearance, then draw one of the edges upright, following with a side at 30 degrees to the horizontal.

After this, if *all the lines running in the same direction are made parallel,* there should not be the slightest difficulty in producing quite lifelike sketches.

To appreciate fully the value of this projection one has but to attempt to show by ordinary methods a complicated piece of pipe work with branches in different planes, or any rather elaborate piece of smith work.

CHAPTER III

FIRST CONSIDERATIONS IN THE DESIGN OF JIGS, TOOLS AND FIXTURES

Difference between Jigs and Fixtures—Their Value—Looking Ahead—Cost of Equipment—Quality of Product—Class of Labour—Single or Multiple Equipment—Remember the Tool Room—Elaboration—Co-operation—Properties of First-class Equipment.

Jigs and Fixtures, the Difference.—Clarity of expression and description is as important in the world of engineering production as in any other trade or profession, so that a few words on the relation between jigs and fixtures will be helpful.

One would be safe in saying that a jig is a device having suitable guides through which are passed the necessary tools to operate on the particular component held in that jig. The latter, as in the case of a drill jig, might have guide holes or drill bushes through its various faces, thus making it impossible to clamp it on the machine in any one position.

In the case of a fixture, however, as the name suggests, it could be described as a device clamped to a machine table, into which the component to be dealt with is locked. In the latter case a certain amount of skill may be necessary to set the tools in relation to the fixture, whereas with a jig it is correct to assume that very little skilled attention is called for.

Their Value.—The use of jigs and fixtures is extending and developing daily, having had its beginning in the production of small and medium-sized articles; to-day, however, one sees large engine and machine tool builders employing them, and the economies effected thereby are unquestionable.

To mention a few points in their favour, there is :—

(1) Quicker production, due to the removal of measuring operations, etc.

(2) Cheaper production, it being then possible to employ unskilled labour.

(3) Interchangeability, thus facilitating assembly and also helping future upkeep.

The old mechanic who laboriously marked off each part has gone, to be replaced by the tool maker responsible for the manufacture of jigs and fixtures. It must not be assumed, however, that the system of employing jigs, etc., is infallible, because, in the case of castings which vary considerably in form, much trouble often occurs.

A compromise is sometimes effected in such cases by centre lining or roughly marking out the important points of the casting and then locating them in the fixture. The latter remark applies particularly to heavier work such as automobile components, cylinders, etc.

Looking Ahead.—The successful designer is not only an ingenious person, but one who has developed the habit of looking well ahead, and the field that he should scan before making any decisions will be indicated.

In these days of "Payment by Results" there might not always appear the necessity for giving special attention to rapidity of production but as it has been found that sometimes an operator or clique of operators will "nurse" a certain job with a view to maintaining or increasing its price, the design of what might be called "compelling" jigs and fixtures is necessary.

By "compelling" the writer means equipment, that by watching points in its general design such as method of loading, cleaning, clamping, etc., the opportunity for any such form of slacking is removed.

By attention to the points mentioned an indirect increase of production is obtained, for without entering the field of "Motion Study" it is obvious that the operator can work continuously, or at least with less fatigue, when the number of his movements are limited. It is a fatal mistake for the designer to complete the design of jigs, tools, etc., for one operation on a component, without giving a thorough consideration to the operations to follow. The order, "layout," or sequence of operations for a certain part may be handed to the designer by his chief, but even then he should mentally follow the operations in order to make quite sure that there

exists no hidden "snags," because it has often been found that, paradoxical as it may sound, to add one or two extra operations on a component has, in the end, reduced the total time of production very considerably.

To give an example, a casting may be varying in form, or be very roughly cast at an important locating spot. To work from this point under these circumstances would probably result in many being spoilt entirely, a great number being doubtful, and others would require an expenditure of labour to save them from the scrap bin, whereas by introducing an extra operation to clean or true up this locating spot, in the first instance the work would have passed through successfully with satisfaction to the people concerned, and without interrupting "progress,"[1] a very important point in a well-organized factory.

Cost of Equipment.—The scale on which production is to be carried out, or the number of a certain article called for, will naturally decide the expense to be incurred in producing the necessary equipment. When dealing with turned work it would be necessary to decide between arranging for the tooling of an automatic as against a capstan lathe, or between the tooling of a capstan with cheap labour, and avoiding special tools altogether by putting the job in question on a centre lathe and employing skilled labour.

Where the material is of thin section, the question of press or drilling machine would arise, but whatever method is adopted, if the quantity to be produced is small, the tools, etc., should be made with as little expense as possible. With press tools the hardening process might, in some cases, be avoided, with the drilling operation the body of another jig might be utilized temporarily by adding the necessary extra parts. The main point to bear in mind, then, is that any profits accruing from a small job must not be consumed by the cost of the equipment.

Quality of Product.—Quality of the finished product, by which, as far as the tool draughtsman is concerned, is meant accuracy and finish, comes next for consideration.

[1] It is necessary to explain to the beginner that "Progress" occasionally referred to is the systematic control of components, etc., from the rough stores till they reach the shipping department, in a finished state, by which means waste time is avoided and the efficiency of the works increased.

The greater degree of accuracy called for, the more care must be expended both in the designing and making of the jig or fixture.

The machine available for the particular operation must be selected, and assuming that this machine has defects, which cannot be, or possibly it may not be convenient to have remedied, the equipment must be so designed as to produce accurate work, and at the same time to remove any danger introduced by these defects in the machine tool itself. It may sound somewhat unfair to thrust the responsibility of overcoming machine faults on to the designer, but he must regard it as excellent practice and remember that unusually successful results often bring their reward; on the other hand, when connected with a firm whose plant is very doubtful, to ignore this would certainly end disastrously.

The finish of a product is often affected, indirectly, by the method of machining which, in turn, is controlled by the design of the jigs or fixtures.

If the various operations are so arranged that burrs or "rags" are thrown up excessively, or surfaces are not finished sufficiently fine, extra expense is entailed in correcting this, and the final finish is sometimes affected. The removal of burrs often provides the designer with an interesting though difficult problem, the cost of their removal often being out of all proportion to that of the remainder of the work.

Class of Labour.—After considering the type and quality of the machinery in general, the class of labour employed must be remembered. If a firm are content to pay sufficient wages to encourage a somewhat higher grade of labour, the necessity for extremely accurate and foolproof equipment might be avoided; again, some firms are very slow to change their methods—to replace an operation employing a file and template by a profiling operation might not always meet with the approval it should. The continual change of operators necessitates the design of what might be called super-foolproof equipment.

The writer remembers a concern situated in an agricultural district, the management of which regarded with dread the approach of the pea and strawberry seasons, because the operators, being mostly females, were attracted to the

fields on the work of picking, which meant engaging new people, and in cases where certain operations required a little practice to accomplish, an amount of scrap work and delay resulted. A jig or fixture having clamps, the design of which were quite successful when operated by male labour, may not meet with the same success with female labour.

The method of loading a component into its fixture is another point, and the designer will do well to imagine himself in the place of the operator, especially where the weight is rather high and the operator a female.

It might be said that it is the duty of the shop foreman to select his operators for the particular job, but the designer should remove the necessity for any such selection by attention to the point in the manner indicated.

Single or Multiple Equipment.—In these days of high production the draughtsman should resist the temptation to design all fixtures on a high production scale, that is to say, to design fixtures capable of holding a quantity of parts at once.

Careful examination will often show that better results are obtained by handling each piece singly.

The writer remembers a very elaborate fixture for milling slots in the periphery of some steel rings 4″ diameter, $3\frac{3}{4}$″ bore, and $\frac{5}{16}$″ thick. It consisted of a steel mandrel about 12″ long to fit the bore of the rings, the latter being threaded thereon and nuts finally locking them in position.

The loaded mandrel was then to be lifted into a cradle on the machine, but as the price of this job only allowed for female labour the lifting was found to be more than a female could accomplish, which necessitated re-designing this fixture.

Another factor to be considered is the supply of components. If this is from outside sources and is insufficient, or perhaps the preceding operation is not fast enough, it does not pay to set up an elaborate equipment, so it is obvious that a simple fixture which can be easily set up and taken down is best under such circumstances.

The same question applies to the designing of jigs and fixture for use on multiple spindle drilling machines, etc., for here again, if the supply of work is inadequate, it scarcely pays to set the machine which would probably remain standing idle in preference to continually setting and resetting it, this in either case being very expensive.

Remember the Tool Room.—This might, with advantage, be hung on the walls of many drawing offices as a text, for certainly, judging by some designs produced, tool makers are regarded as wizards. ' It is worth mentioning here that for a person to produce designs for equipment satisfying all points he must have had tool-room and machine-shop experience.

Though, of course, the points already mentioned must be



FIG. 8.

ALLOWING FOR MACHINING WHEN DESIGNING.

considered first, it would be wasteful to introduce a design that would occupy the time of skilled and consequently expensive tool makers when the same result could have been effected in a much simpler manner.

Fig. 8 is an example of this, where a hole is wanted through the boss B at fixed centres and square with the other holes in the plate.

The tool maker would probably clamp this casting on to

the lathe face plate for boring the hole, but the presence of the boss B would make this exceedingly difficult, as the four corners would have to be packed up equally as high as the boss, and it is doubtful whether, after many vexatious attempts, the holes would all be parallel.

If, however, the designer had called for a separate boss, a quicker and more reliable result would have been obtained, even allowing for the extra work entailed in fitting the boss afterwards.

The length of reamers, spindles, etc., which are to be finally hardened should be kept as short as possible, for it is quite possible that in getting over the difficulties caused by warping of long pieces when heat-treated, two will have to be made to ensure getting one.

Elaboration.—A person whose work brings him continually in touch with mechanical drawings gradually becomes something of a connoisseur, and it may be this, coupled with the desire to produce something pleasing to the mechanically trained eye, that tempts some draughtsmen to introduce extremely elaborate and therefore expensive designs.

Jig and tool offices and similar non-productive departments are regarded as necessary evils, therefore it is necessary that the results of their work should show in a favourable light. The cost of special equipment should be kept as low as possible, and this can most easily be done in the drawing office. Where iron castings form part of a design it is very tempting to include webs, bosses, lugs, and numerous other refinements which certainly make the finished fixture look very workmanlike, but what has been the cost? The extra bosses, etc., all made work for the pattern maker, the moulder found that the casting needed care in moulding, the tool maker had to think how he could best tackle such an awkward piece, and finally, when the cost department figured it all out, that designer had no reason to be pleased with himself. It is quite possible that a plain iron casting would have accomplished the same results, even pieces of channel and girder sections should not be despised.

The designer who judiciously uses materials at hand, and is ever ready to adapt old discarded parts, shows a breadth of experience and indicates the profit-making servant.

Co-operation.—In the writer's opinion there is one essential to the successful production of a commodity, and that is co-operation between the designer of the commodity, the planning department or jig and tool office, and the machine shop.

Often, and with expensive results, do these people "plough a lonely furrow," thinking that it is hurtful to their dignity to alter or moderate their ideas at another's suggestion. When drawings of a component or the component itself is handed to the designer, it is often immediately obvious that by slight modifications the arrangements for tooling and subsequent production can be greatly facilitated.

As, however, it is not within his province to make such alterations, and the point in question may be very vital, he should consult with the people responsible for the design of the article, who should agree any alteration that would make for cheap production.

Having got so far, though the draughtsman may be an expert mechanic, there may be many hidden difficulties in the particular machine shop into which the tools will go for use, so again it will be advantageous to consult with the shop foreman or charge hand before proceeding.

Another very good reason why the policy of allowing the machine-shop people to express their opinion is that if eventually there is a slight hitch in the tooling arrangements, they will do their very best to get over the difficulty with the minimum of trouble, feeling that they have a share of the responsibility.

On the other hand, no matter how well equipment is designed and produced, it is remarkable the difficulties and troubles that can develop when these designs are not to the liking of the machine-shop executive.

To illustrate how co-operation resulted in economy, Fig. 9 is given. It shows the flange of an oil pump, the four holes, A, B, C and D being fixing holes and E an induction hole. It is obviously a job suitable for a multiple-spindle drilling machine, piercing the five holes in one operation, but as it was only possible to adjust the spindles of the machine to drill holes with 1″ centres, this was impossible, as it will be seen on examining Fig. 9 that the centres of the induction hole and the nearest fixing hole

are $\frac{3}{4}$". After arranging with the designer of the pump to widen these centres the five holes were drilled at once, otherwise this piece would have required two operations.

Properties of First-class Equipment.

(1) The cost of designing and making should be in proportion to the price and quantity of work in view.
(2) Should be perfectly reliable as regards accuracy, and production therefrom should be up to the estimate.[1]



FIG. 9.

ADJUSTING DESIGN TO FACILITATE PRODUCTION.

(3) Should be light and easy to handle and manipulate.[2]
(4) It should be foolproof.
(5) Parts subject to heavy wear should be designed to facilitate removal.
(6) The equipment should not constitute a danger to the operator.
(7) All parts should be standardized where possible.

[1] The writer remembers a designer who would sit with eyes closed and mentally carry out movements necessary when operating the jigs or fixtures of his design, and it was very surprising how accurate were the results obtained when estimating production.

[2] The operators should not have cause to complain of fatigue.

CHAPTER IV

DRILL JIGS

Holes through Diameters—Location — Self-Centring Mechanisms — Locating Rough Components—Adjustable Supports—Clamping—A Simple Drill Jig—Drill Jig for Pistons—Jig for Use on Double Spindle Machine—"U" Washers—Jig Feet—"Jigging" a Component—Multiple Drill Head—Simplicity of Design—An Indexing Jig—A Jig Indexing in Four Planes—Continuous Drilling.

In this and succeeding chapters the design of various equipment will be considered, and so as to enable the reader to thoroughly grasp the various points requiring attention, it is proposed, in some cases, to introduce sample components and then to design the equipment for a certain operation. Attempts have been made to classify the various types of drilling jigs, but the dividing line is so faint that it is in many cases indistinguishable. For preference it would be better to classify the operation such as drilling raw castings, half-machined components, parts machined to coarse limits, parts finished to very fine limits, etc., a somewhat different type of jig being wanted in each case.

Holes through Diameters.—In the engineering world there is an enormous variety of parts such as rods, tubes, pistons, etc., having holes passing through their diameters, and though this may appear very simple, it is not so when extreme accuracy is required. To illustrate this Fig. 10 is given showing a piece of steel tube having $\frac{1}{4}''$ holes each end and running at 90 degrees to each other.

It will be noticed that the holes are expected to be accurate within ·002″. The first consideration then will be, how to maintain this accuracy.

It is at once obvious that a drill starting on a convex surface will always have a tendency to run off, which of course would be fatal, therefore the bushing that guides the drill must not only be as near as possible to the tube, but must be extra long so as to provide an extended bearing surface, because the continual tendency of the drill to run wears the

bush considerably, this wear can be further reduced by making the bush a good fit on the drill.

Seeing that the proper guidance and control of the drill presents no difficulty, the method of holding the piece will next be considered.

Location.—The question of the correct locating point is very vital, for it is obvious that the accuracy of the hole cannot be greater than that of the locating point. The usual method for drilling single pieces is to lay them on a vee block as shown at A, Fig. 10, these blocks being very successful where the holes to be drilled are in one direction only, but



FIG. 10.

A.—VEE BLOCK LOCATION.
B.—ACCURACY AFFECTED BY VARIATION OF DIAMETER.
C.—CHEAP JIG FOR SMALL QUANTITY.

where the holes are in different planes another factor enters.

This factor is the accuracy of the diameter of the rod or tube both externally and internally.

A glance at B, Fig. 10, clearly shows that if the external diameter varies accuracy is impossible, because while the line *a*, *b* is correct, whatever the variation, when turning through 90 degrees and drilling, the lines *c*, *d* and *e*, *f* show that the hole position would vary with any difference in diameter. It can therefore be at once decided that while this condition exists, vee block location must be discarded.

On the other hand, had the external diameter been finished to limits as accurate as those called for in the hole to be

drilled, a jig embodying a vee block would have been quite successful. It must be remembered then that if the two diameters are unreliable, the method of holding must be such that this absence of accuracy is avoided, and this can only be done by utilizing a device that will centralize the tube or rod in all planes.

The drawing indicates that the holes must be correct within ·002″ in their relation to the outside diameter. This allows the inside diameter to be ignored, a very useful concession, seeing that the particular piece is from the tube in its raw state, under which circumstances the bore may not be concentric with the outside. A certain path is therefore indicated to the designer, i.e. the jig must centralize the tube, and for this purpose the outside diameter must be made use of.

Having determined the conditions that must be fulfilled to produce the requisite degree of accuracy, the method of securing this will raise the question, What expense can be incurred in making the jig ?

Assuming that only a few dozen are wanted, it may be possible to introduce an operation of turning or grinding the outside diameter at each end, finally resorting to vee blocks as already mentioned. If that is impracticable, another method of getting through a small quantity would be to measure accurately the outside diameters and group these, after which a simple drill jig as shown at C, Fig. 10, could be made. The hole Y would first be made to suit the tube of smallest diameter, and when this batch is finished the hole could be ground out to suit the next size. This method would, of course, make the jig useless for future work, but where the job was known to be the last this would not matter.

Self-Centring Mechanisms.—Quite a number of these will suggest themselves and a few are indicated in Fig. 11. A is a pair of vee blocks arranged to slide, without any "play" and actuated by a right- and left-handed screw. If this method is adopted, the length of the blocks should be sufficient to stand considerable wear and also provide a long bearing surface, because the tendency is for these to lift when tightened. B shows two coned plugs, one of which is fixed and the other provided with a screw or cam lever enabling it to be withdrawn or closed on to the tube. This is quite good where the ends of the material are perfectly square; if this is not

so, it is obvious that the tube will not lay parallel. If the tube being drilled is of thin section, care must be taken to see that the gripping mechanism is not powerful enough to distort it. The method shown at C employs a coned plug one end and an ordinary small three jaw chuck at the other.

D and E, Fig. 11, show the principle of two devices, the former for gripping on the outside and the latter internally. Taking



FIG. 11.

SELF-CENTRING MECHANISMS FOR DIAMETER DRILLING.

D first, it consists of a body piece *a* on to which is screwed the coned nut *d*. Equally spaced round *a* are three hardened steel pegs or jaws *c* of equal length, capable of a sliding motion, so that on inserting a rod or tube in the bore *e* and turning the nut *d*, the pegs are depressed centrally and so grip the rod. The pegs are provided with small helical springs to assist them on their outward motion. E is very similar,

except that the pegs are replaced by three pivoted levers *g* equally spaced round, which tilt when nut *f* is screwed up enabling their ends *h* to grip internally.

Other than these there are spring collets as used on capstan lathes and also various types of expanding mandrels (see Chap. VI).

Locating Rough Components.—In deciding from which point to locate a component the greatest care should be exercised, for upon this the accuracy of the finished work will depend, at the same time excessive operations introduced to provide a suitable locating point should be avoided if possible. Once an operation has been performed on a piece the question of location is simplified, but it is with the rough component that the difficulty arises.

Forgings, stampings and die castings are generally produced uniform in shape, but ordinary castings vary considerably and it will be found in dealing with these that an elementary knowledge of pattern making or foundry work will be of great value, for it will be appreciated that it would be fatal to locate from a point that was continually changing, and the knowledge referred to enables this to be avoided.

In the case of a casting with bores calling for machining, the bores will probably be "cored" out in the casting, leaving a certain amount of metal to be removed. Now in the production of the casting the cores are very liable to move and so produce eccentric bores, whereas the main pattern which produces the mould from which the castings are taken, if well proportioned, should give uniform results.

The correct location point for a casting, then, can be best found by an examination of the method of producing the casting. In locating a piece of irregular form, or when providing a seating for a component, what is known as "three point" location is best. The best illustration of this exists in the comparison of a three-legged stool and an ordinary chair. The latter, when placed on irregular ground, will invariably rock on two diagonal legs, whereas the former will adjust itself under whatever conditions it is placed. The diagrams in Fig. 12 indicate several methods of locating components when in their rough state as for the first operation.

Taking A first, where the component is shown shaded, the operation required is to drill the holes *a* equidistant from the outer rim. In this case it is obvious that though the

holes might be drilled more central to the bosses by locating therefrom, this is not essential, and though the finished piece might have a better appearance when so drilled, the important



FIG. 12.

LOCATING METHODS.

point, i.e. the relation of the holes to the outside rim, would have been missed and probably a quantity of work wasted.

One form of location shown can be employed where three-coned studs are provided equally spaced round the rim at

such a radius that the rim seats on the cones, the latter being provided with springs below, which enables them to drop or lift to suit the component; the latter is by this means centralized, and if the drill bushes are fixed on the jig in correct relation to these coned pegs, accurate results will be obtained.

The angle of the cone on these pegs is generally about 60 degrees, and they can be arranged to suit the inside or the outside of the component according to which is most desired.

Another form of location is shown at B, where the rim again enters into the question. In this case correct location is secured by three hardened steel plungers *a*, behind which are fitted springs, and actuated by means of the cam *b*, a partial rotation of which will force out the plungers equally, thus locating the piece. The springs cause the plungers to fall back when the cam is released.

At C a component having a cored hole calls for machining on the horizontal face indicated, and at a certain distance from the centre of the hole, so that it is necessary to fix the piece with the sides vertical. Two relationships are necessary then, first, the centre of the hole to the top face, second, the latter to be square with the sides.

This can be overcome by having a coned centre *d* capable of a sliding motion and fitted with a spring, and at the sides four coned pegs similarly fitted, so that on pressing the component down on to the coned centre, the latter recedes, the spring being compressed until the component comes in contact with the coned studs *e* which set the sides to the vertical, after which the piece is clamped.

There exist an endless variety of levers and plates having holes a certain distance from the end, and a form of location for this is shown at D.

For locating pieces having a radius, the vee method already mentioned is quite satisfactory, one vee being fixed and the other adjustable, the latter also providing a means of locking the component. In the case of the piece shown the relation of the hole to the vee blocks is important. The accurate dimension must always come between the fixed vee and the drill bush, that is, assuming that block *a* is fixed, and the dimension is given at *y*, the component is correctly located, but if as at *x* the component should be reversed so that the end from which the dimension is given butts against the fixed vee.

Parts having an exceptionally irregular outline are very difficult to locate, one method is as shown at E where the component is forced by the screw *a* against the two pegs *b*, the latter being arranged at the most clean and reliable parts of the casting, also at points that govern the important dimensions. In cases where the piece is so irregular that it has proved impossible to use pegs, the difficulty has been overcome by having the outline of the piece accurately marked or engraved on a jig plate, and then clamping the piece on



FIG. 13.

ADJUSTABLE SUPPORTS.

to it over the outline. Naturally a smart operator will be necessary for this job, but it will be found that the extra time taken or expense incurred by adopting this method will be outweighed by the small amount of scrap, and also by the time saved by not having a jig with pegs to adjust to suit the varying castings.

Where the position of a radius is important, the semi-circular pad provided with a spring seating, indicated at F, is quite successful. To avoid the roughness of the concave

shape, the pad is cut away or relieved so that only two or three points of the pad are in contact with the component.

Adjustable Supports.—It is frequently necessary, after a component has been located in a jig or fixture, to swing or adjust the piece square irrespective of its section and at the same time to provide support. H, Fig. 13, is a form of support where the component is located in a jig at a slightly varying angle so that the support *a* pivoting at *b* will adjust itself to the angle. At J is another very useful form of support which also sets a component horizontal in the fixture. It consists of a coned bolt *a* on which is a sliding cone *b* having a similar angle to the bolt. By turning the nut *c* the two are drawn together thus causing the pegs *e* which are provided with angular flats on their bottoms to move upwards equally at the same time correcting the component should it not be horizontal.

Clamping.---Having correctly located the component, the next thing is to see that it is clamped in an efficient manner.

A large amount of time can be wasted and work spoilt by having unnecessary clamps, or ones that are awkward or complicated, by having them placed in awkward positions, or by making them removable so that they get mislaid.

The first point is that the gripping should take place immediately over or as near as possible to the locating spots, otherwise the work may distort. It has often been found that work, after it has been machined and checked in position, is correct to size, yet on releasing the clamps an entirely different result is obtained. It should also be remembered that the clamping method should take into consideration the operation being performed. If it is horizontal milling, where the tendency is for the work to be lifted up from the machine table, the clamps must be so arranged as to prevent this; if it is vertical milling where the tendency is for the cutter to swing the work off the table, the clamps should be assisted by projections or pegs to take up this thrust.

A variety of clamps are illustrated in Fig. 14, and the designer must see that while the clamp is effective it is not too elaborate. The simplest form is seen at A and no apology is offered for mentioning this old method, because even to-day it is possible to find it being applied in a faulty manner.

It should be arranged so that the pressure of the nut is as near as possible to the work, so that the latter gets the full

value of the leverage. The inclusion of a spring beneath the clamp plate will assist wonderfully in its manipulation. The plate *a* should err rather on the thick side and should



FIG. 14.

TYPES OF CLAMPS.

be provided with an elongated slot enabling it to be slipped back to facilitate the removal of the component.

At B is seen the same type of clamp, but the hexagon nut is replaced by a round-headed one provided with a loose tommy bar which obviates the necessity of the operator using a spanner,

the use of the latter should be always avoided where possible. The opportunity of clamping more than one piece at once as at C should be watched for.

Favourite clamps for holding components in drill jigs of box formation are shown at D and E. In the former the end *a* is pivoted so that the clamp swings clear to enable the jig to be loaded, and when ready for clamping the hooked end *b* passes under the head of a stud as shown so that the plate is effectively held while the clamp nut *c* is screwed home.

That at E works in a similar manner except that the clamp plate is removable.

At F is seen another pattern, the link *a* swivelling about the studs *c*, the bolt *b* gripping the work. The disadvantage of this type of clamp is that it occupies three faces of the jig, thus making it impossible to turn in any but one position, without the use of legs of excessive length, and the latter should be avoided.

It can, however, be made removable if this form of clamp is unavoidable by slotting the pivot hole as shown at *d*.

Where the component varies slightly in shape, the clamps shown at H are very useful. The plate *a* being hinged at *b* and provided with a slot as shown, thus enabling the bolt *d*, which is also swivelled at *e*, to be swung clear, forming a very quick method of holding. The pad *f* is suspended at *h*; so that it swings ready to adjust itself to any variation in the form of the piece. The plate *a* should be of generous proportions, as it will be seen that the tendency is to bend it across the line *x*, *y*.

As it is essential that the minimum time must be spent on the clamping of the piece, the employment of long lengths of thread should be avoided. Particularly in the case of finished or semi-finished work, where there exists a portion having a constant shape, clamps in the form of levers or toggles provided with a cam lobe are an advantage. At J, K and L will be seen three types of cam lever applicable to various cases. That at J is shown in use in Fig. 16, and it is usual to have the centre thrown eccentric by a distance varying from $\frac{1}{32}$″ to $\frac{1}{16}$″. This amount is described variously as the "lead," "throw," "rise," or "lift."

The cam on the lever at K is drawn as indicated, and the portion at *a* must be sufficiently wide to prevent it bending when the lever is thrust home. That at L is of slightly different

pattern to the others and is not so well known, but used in the proper place it is very successful. The cam *a* is fixed to the spindle *b* which is operated by turning the handle *c*, the cam applying pressure to the bolt *d*, the latter being



FIG. 15.

TYPES OF CLAMPS.

provided with a spring to lift it when the pressure is released.

To grip a component having a fairly large area which is not at right angles to the clamp bolt, the method shown at M will be found satisfactory, with the advantage of having

only one bolt to operate. The plate *a* is pivoted at the end of the bolt *b*, and the former has three hardened pegs *c*, so that at whatever angle the face of the component may be, the three points are enabled to reach and lock it, the clamp screw being equidistant from them.

Forgings of small levers, stampings, etc., are not always easily gripped, but N indicates one method where the component is seen held by two vee blocks, one being fixed while the other is actuated by a clamping bolt. To keep the piece from lifting it will be noticed that the vees are not cut at right angles to the face of the blocks, but at about 10 degrees which prevents the component from lifting due to the action of the cutting tool. The movable vee should be accurately dovetailed into the foundation plate of the fixture to prevent it lifting when pressure is applied.

The designer will often meet components that will tax his ingenuity to devise suitable clamps, and as has already been mentioned this may be overcome by consulting those responsible for the design of the piece in question, with a view to making a slight alteration to assist clamping.

At P is a clamp of special design holding a forging of awkward shape. The latter is located on pads at *a* and held by the claws *b*. These are pivoted at *c* and the locking is effected by screwing up nut *e* on bolt *d* which passes through one limb and swivels on the other.

The length of the lip *x* should be as short as possible, otherwise time will be wasted in opening the claws wide enough to permit of removing the component.

The magnetic chuck and the introduction of compressed air for operating clamps will no doubt make a great difference in the future, but as the sphere of usefulness of the former is limited and the latter merely applies the necessary force, the question of the method of holding still remains.

The reader is advised, however, to make himself acquainted with the theory of these two introductions.

A Simple Drill Jig.—Fig. 16 gives different views of a simple yet highly successful jig, for rods or tubes where the holes are in one plane. The rods lay on the vee block and a single motion of the lever *a* locks the rod centrally. The construction also allows of easy removal of the work. Plenty of room also exists for the operator's brush when removing the cuttings, a very important yet much neglected point.

As this jig is shown fully detailed (see Chap. XIII), no further description will be necessary.

Drill Jig for Pistons.—The increase in the production of motor vehicles has brought to light a very interesting machining proposition in the form of pistons, and the points



FIG. 16.

A SIMPLE DRILL JIG.

already mentioned in connection with drilling through diameters apply to this component.

Fig. 17 shows a piston in section, one is also seen in position in the drill jig illustrated. To get these pieces machined quickly a horizontal machine having two spindles opposed

to each other and capable of being fed in simultaneously is often used.

It will be at once seen that the drilling time is halved and also by drilling through from opposite sides greater accuracy is obtained. For the piston to function properly when complete it must be correct to size, a certain weight, and with its walls of sufficient thickness to give the necessary strength.

To secure this evenness of wall special precautions are adopted when turning the diameters (see Fig. 42), and to



FIG. 17.

DRILL JIG FOR PISTONS USING HORIZONTAL DUPLEX MACHINE.

assist when putting in the grooves and also to provide a locating place when drilling, the inside diameter *a* is machined to rather close limits. The hole to be drilled, which is for the gudgeon pin, must be central, at right angles to the axis of the casting, and at a certain distance from the top of the casting, because if the latter varied it would cause a variation in the compression when working.

As the face *c* and the diameter *a* is turned when locating from the top *d* if the hole about to be drilled is located from *c* the dimension *b* should be maintained correctly. Examin-

ing the jig then it consists of a main casting A which is clamped to the bed of a horizontal duplex drilling machine, B is a hardened steel locating pad, C is a 60-degree vee block, mounted on a peg and capable of a vertical sliding motion, but being provided with a key to keep it in position, that is, so that the vee forms a seat for the two bosses *e* and locates them central with the drill bushes D.

Beneath the pad is a helical spring which presses the pad upwards, thus assisting the location. The clamp E (see F, Fig. 14), which swings about F locks the casting securely in position. With such a delicate casting the locking nut G should not be made so as to provide too much leverage, otherwise the casting may be distorted. With any form of jig that suggests a box or receptacle there arises the difficulty of cleaning, or getting rid of the cuttings, which if allowed to remain will interfere with the accuracy of the jig.

To ensure that this does not happen considerable thought should be given, because even if the cleaning is successful, the time taken to accomplish it should not nearly approach that taken for the actual drilling. In Fig. 17 at H are two outlets cored in the body casting just beneath the bushes, so that the cuttings will, when falling, work out of the jig, also the cuttings that may accumulate in the vee piece can be easily swept out in the same direction.

To prevent, as far as possible, any cuttings getting on the main location B, and under the piston, the former is relieved so as to leave but three points for the latter to rest on. The space between the vee block and the pad should also be kept wide enough to avoid the possibility of cuttings interfering with its free movement.

Jig for Use on Double Spindle Machine.—Fig. 18 shows a jig for drilling the component seen in position in the jig. This component, which is a part of an agricultural machine, is a steel forging which has passed through its first operation, which consisted of boring the centre hole and then facing the boss *b* of the latter and also the bosses *a* and *c*, leaving the two holes *x* and *y* to be drilled.

The most important point to be observed in the drilling is that the holes are the correct distance apart and that they run parallel with the centre bore. Seeing that the latter is finished and faced as also is the two small bosses, the method of locating as shown should give the desired result.

As the jig is intended to have a long life the seats on which the bosses rest are made of hardened steel. The arms carrying D, the drill bushes *d* should be as close as possible to the forging so as to keep the length of the drill protruding below the bush as short as possible, thus minimizing the risk of the drill deflecting from its true course. To locate the bosses *a* and *c* central with the bushes *d*, the vee block *f* operated by the lever *g* is used, a spring *h* being provided to keep the block in contact with the component when locking nut *r*.

The height of the vee *f* should be such that it touches the forging just below the centre line of the boss, thus avoiding



FIG. 18.

DRILL JIG NECESSITATING A DOUBLE SPINDLE MACHINE.

the "flash" or burr which generally exists on forgings due to their being formed between two half dies.

The cast-iron arms bearing the drill bushes, it will be noticed, are strengthened by arms *k*, which while adding the necessary strength do not add excessive weight. The reader is warned that while the inclusion of webs, fillets and other strengthening devices is often necessary they considerably increase the cost of the fixture, because of the extra work entailed when making the foundry patterns.

It is assumed that the jig would be used on a double spindle machine, drilling boss *c* right through and boss *a* half-way, after which the small bush *m* is slipped in position and the small hole drilled through. Had both holes been the same diameter

the job could have been dealt with on a single spindle machine or a multiple spindle machine, in the latter case taking half the time.

"U" Washers.—To facilitate the removal of components that are located on a screwed stud, the method adopted in Fig. 18, is very successful. The nut *r* is made slightly less in diameter across the corners than the hole in the component, so that the operator has merely to loosen the nut and slip off the U washer *s* when the component can be lifted off, the nut remaining in its place. Though loose pieces are condemned the washer described should be introduced wherever possible in connection with hexagon nuts, even if it is chained or otherwise anchored to the machine to prevent the operator dropping or losing it.

Jig Feet.—It will be at once seen that if the holes are to be kept accurate, the jig must lay quite flat on the machine table. Pieces of cuttings under one side of the jig would tilt it slightly, thus causing the drill, when entering the bushes, to be strained out of the vertical, which would gradually wear the bushes large and finally produce faulty work. To avoid this, jigs are provided with feet sometimes consisting of hardened steel pegs, at other times the legs are formed by machining a recess in the centre of the base of the jig, thus leaving the corners standing clear as in Fig. 18, w, though in this case the recess was cast.

"Jigging" a Component.—It is worth while halting at this point to indicate a common method of procedure when designing a jig or fixture. Assuming that the various points mentioned in Chap. II. have been decided, the draughtsman takes a blue print of the component, and fixing it squarely beneath his detail or other fine drawing paper, traces it, using red ink for this purpose and including only the outline of the piece and its centre lines. With the component before him, the locating points are considered and lightly drawn in, as also are the methods of clamping. At this point it is well to examine closely an actual component both finished and in the raw state, for when a jig has been designed entirely from the component drawing it is remarkable how many irritating points can crop up after it is made and ready for use.

Having got so far it only remains, as it were, to build the body of the jig or fixture round the component, bearing in

mind strength, chip capacity, lightness and finally the pattern maker!

A Multiple Drill Head.—Though there are in existence many designs of multiple spindle drilling machines, there is another field which has been developing recently, and that is the design of multiple spindle heads of various sizes and spindle centres to suit certain components, the heads being attached to radial or other single spindle machines. The great advantage of these is that no setting of the spindles is necessary, being made for a single purpose, and simply require clamping on the sleeve of the machine. Fig. 19 shows a sectional elevation of one with two spindles, which would be quite suitable for use in connection with a drill jig of the type shown in Fig. 19, drilling the two holes at once.

As there is a bright future in front of these, time will be well spent in examining the construction.

The body is built in two parts, A and B, of cast iron which should not be too heavy, the use of thin section and the introduction of ribs to add strength is advisable. The drill spindles C, which are of mild steel, are integral with the pinion by which they are driven, and run and are supported by the phosphor bronze bushes D. The upward thrust of the spindles is taken by the ball thrust washers E which, it will be noticed, are dropped into a seating in the spindle pinions, and are further retained by the rod F.

The drills are gripped by the spring collets, G being forced up into the coned portion of the spindles by the nut H, the latter being provided with holes or flats to assist when tightening.

The gears are lubricated through the plug hole J, though if the gears are filled with good solid lubricant when assembling, a long time should elapse before further attention is necessary. The two spindles are driven by means of the central pinion K which runs on the peg L and is in turn driven direct by the drilling machine spindle. This is effected by cutting a slot about $\frac{3}{8}''$ square centrally across the end of the machine spindle which engages the square peg shown at M, the latter being fixed centrally across the centre pinion. Another method of securing the drive is to arrange for a tapered spindle to be integral with the centre pinion and allow it to fit the tapered spindle of the machine.

The complete attachment is slipped on to the sleeve of the



FIG. 19.

MULTIPLE SPINDLE DRILL HEAD.

drilling machine, the rack attached to the latter fitting the slot N and on tightening up the bolt P the head is securely held. From this simple example the reader will see that it is quite easy to design another head for any arrangement or number of holes. If the holes are to be closer together it will mean that the gears must be of smaller diameter.

The centre pinion in Fig. 19 had 19 teeth of 12 pitch, while the two side pinions had 17 teeth of 12 pitch. If desired the spindles can be bored to take morse taper shanks instead of the small collets and nuts as shown.

Simplicity of Design.—It has already been mentioned that mass production does not necessarily call for elaborate and multiple tools, in fact sometimes the simplest equipment will give the best results. It is possible to design a single drill jig to include in it bushes for every hole in the component, and while this method is very safe, ensuring the correct relation between the holes, it is possible that production may be hampered by waiting for one operator to complete the drilling, whereas had a more simple jig been designed, the work could have been split up among different operators and production facilitated.

Fig. 20 shows a group of drill jigs for drilling the necessary holes in a brass motor-car wind-screen bracket. This component contained a number of holes in various planes, and to include them in one jig would have resulted in a very awkward piece of work, so that it was decided to make simple jigs as shown.

The three parts of the complete bracket are seen standing behind the group, and the chief one is shown at Fig. 21.

The jig A is for drilling a hole through the lug *f*, and for this purpose the component is held vertically by means of a hook-shaped clamp B operated by nut *c*, and located from the holes *e*.

These two holes are made use of for this purpose throughout all the drilling, they being in turn located from the hole *v* which is drilled first, so that it may be said that all holes are measured off from hole *a*. As the lower fork of lug *f* is tapping size and the upper clearing, the bush D was made to suit the latter, so that when drilling, the clearing drill is set to pass through the upper lug and make a centre hole in the lower, after which a tapping size drill is used, starting in the centre

made by the larger drill this necessitates the use of a two-spindle drilling machine.

As the larger of these holes was only $\frac{1}{4}$" diameter, and the brass was of very soft nature, no support was found necessary underneath the lug to take the thrust of the drill.

For drilling the hole *h* the jigs E and F are used, one being left- and the other right-handed to suit the two opposite handed castings. It will be seen that they are very simple in construction, being plain angle iron castings.

The components are located from the hole *a* on the stud



FIG. 20.—SIMPLE JIGS FOR WIND-SCREEN BRACKET.

H, the machined face *k* of the component butting against the shoulder seen on the stud. The latter is of hardened steel, and is a push fit (see Fits, Chap. IX), and is provided with a nut for locking purposes. To facilitate loading and unloading the nut G is of smaller diameter than the hole *a*, thus enabling the component to be removed without taking the nut from the stud, the U or clip washer seen at the foot of the jig enabling the clamping to be effected.

The extra thick base of this jig, not visible in the illustration, prevents any possibility of the jig tipping over when drilling,

and it would have been an improvement to have made this base of inverted tee section.

As a general rule the feet or foundation of a jig should be equally balanced about the area bounded by the holes to be drilled.

The jig H is for drilling and reaming the main hole *a* where it will be observed that the component, which is semi-circular in section, rests in a vee block J, and is located by two short pegs which engage in the slot *m*, Fig. 21, at the top of the component. No clamping is necessary, because the thrust of the drill, which is about 1″ in diameter, keeps the component in position. For reaming, the drill bush is removed, being



FIG. 21.

WIND-SCREEN BRACKET CASTING (SEE FIG. 20).

specially designed to facilitate this, and a bush of the reamer size inserted. The bush and its locking screw is seen in the illustration, and the reader is reminded that these bushes as well as the clamps, nuts and various parts of jigs are standardized in various drawing offices and the designer should follow any procedure laid down. Fig. 164 shows a drill bush, and its proportions are given in Table No. 14. Fig. 165 shows a reamer bush, and Table No. 15 gives suitable proportions. To prevent wear and consequent inaccuracy due to the constant removal of the bushes, the cast iron or mild steel part of the jig holding the bushes, is generally provided with a hardened steel liner or sleeve; a close examination of H, and also Fig. 165, will reveal one such.



FIG. 22.

INDEXING DRILL JIG.

The face *k* of the component is finished by what is known as a spot-facing operation, and is carried out on the plate L. The hole *a* fits the plug A of the plate, and the pilot pin of the cutter M is a running fit in the small hole seen in this plug. The peg N is merely to prevent the component from swinging round, which is rather dangerous when the cutter is at work. The plate itself is of cast iron, provided with two slots cast in it for fixing purposes, and the centre plug is of hardened steel a force fit into it.

An Indexing Jig.—Fig. 22 shows the drill jig for a component which is the centre portion of an automobile rear axle. The holes to be drilled are six in number, equally spaced round the flanges *a* and *b*, and as a horizontal multi-spindle drilling machine was not available, the fixture was designed to be used under a vertical machine as shown in Fig. 25, the table being removed.

The component was located from its cored hole, the flanges having been previously turned from this point on a mandrel similar to the one shown in Fig. 37, on a coned stud C and a similar stud C_1 provided with a screw at the opposite end completing the location and also acting as a clamp.

To set the face *f*, which was about 10″ diameter, square, a rod provided with cams is arranged at H so that before tightening C_1 this cam rod is brought into contact with the face of the piece and so retained while the clamping is effected. The fixture consists of a cast-iron cradle, which is kept as light as possible and strengthened by webs and fillets at M and revolves on a steel spindle N in the pedestal P. The latter has a bronze bearing, which should be kept as long as possible; the webs R and S support the pedestal, which is subject to considerable strain due to the six holes being drilled at once.

The plunger for indexing the cradle in its two positions is shown in position at U and in detail at A. The plunger pin V, and the bushes W into which it fits, are of hardened steel to prevent wear, and the former is kept reasonably long together with its bearing so as to prevent it working slack with resultant faulty indexing. The plunger is provided with a tapered nose which enables any wear to be taken up by allowing it to drop further into the bush which, of course, could not be done with a straight plunger.

A Jig Indexing in Four Planes.—Another design of indexing jig is shown at Fig. 23, the component in this case

being an automobile gear box casting. The jig is seen in position on an ordinary radial drilling machine, and of course, as only one hole can be drilled at a time unless a head designed on the principles of Fig. 19 be employed, production will be limited. This could be overcome by mounting the jig on a steel truck and passing it beneath the various drilling machines each set for operating on the different faces of the casting—this principle is illustrated in Fig. 155.

The main cradle of the jig is of cast iron, and pivots on steel



FIG. 23.—DRILL JIG FOR AUTOMOBILE GEAR BOXES INDEXING IN 4 PLANES.

studs in the standards A. It has four steel indexing bushes, three being visible at B, C and D, and the plunger for them is seen at E.

To enable the component to be loaded and removed easily, the top plate F is made so that it can be detached from the jig. To hinge this plate as in a box would have necessitated widening the cradle, which must be avoided, as it is essential that the drill bushings be kept as near as possible to the component. The plate was therefore located on the fixture by the plungers J, K and L, which engage in the bushes J_1, K_1 and L_1. The

lug seen at P inside the casting also required to be drilled, so that, as it is impossible to bring the drill bush near to it, an auxiliary bush is introduced to support the drill, which would otherwise bend and "wander" due to its unsupported length.

This is accomplished as shown in Fig. 24, where A is the lug to be drilled and B the drill bush through which the drill will enter, the bush C is attached to another removable part of the jig and acts as a support. In the illustration, Fig. 23,



FIG. 24.

SPECIAL GUIDE PLATE TO SUPPORT EXTENDED DRILL.

the plate F is provided on its other side with an arm carrying a supporting bush as described.

Continuous Drilling.—Making use of the automatic feed of a drilling machine continuous drilling can be accomplished by using two identical jigs, and locating them on a revolving plate arranged on the machine table.

This method has been developed in connection with multiple spindle machines, and Fig. 25 is an illustration of this, where components from harvesting machines are being drilled.

The two necessary fixtures are seen built in one, and it

will be noted that while one is in operation the other can be loaded. The jig plate A carrying the drill bushes is hung on

FIG. 25.

four steady rods so that as the spindles are brought down to or lifted from the work the plate follows.

The correct location of the plate on the jig is secured by

means of the pegs B. The spiral springs seen on the steady rods keep the plate in position at the bottom of the rods as the spindles are lifted after drilling.

If a reaming operation is necessary three jigs can be employed, equally spaced round the table, and the machine spindles arranged in two groups, one holding the drills and the other reamers, so that while one component is being drilled the other is being reamed and a third being loaded into the jig.

The revolving table is generally purchased with the machine, though it can be made quite easily. The plunger for indexing can be seen at C.

In some cases where high production is called for, to save time and more effectively remove the cuttings, a compressed air pipe is attached which blows away the cuttings as they are made.

CHAPTER V

MILLING FIXTURES

Choice of Machine—Setting Spots—A Simple Fixture—String Fixtures—Continuous Milling—Indexing Fixtures—Clamps and Location (see Figs. 11–15, Chapter IV).

The competition in connection with the finishing of surfaces is very keen, the milling machine vieing with the planer and the grinder for supremacy. Where the work is other than a plain surface, however, the milling machine still stands first, but the designer must consider well if the decision of the actual operations is left to him, before fixing on the method. Having decided that the milling operation is best for a given job, the question arises as to whether the fixture is to be a multiple one, that is, to hold a number of pieces at once, or only to operate on one piece at a time. This will naturally depend on the number of components passing through the shops, also whether the operation is a permanent one or not.

Choice of Machine.—The selection of the type of milling machine for a certain operation also calls for care, though in many cases a job is put on a certain machine because another and more suitable one is hard pressed with work. The designer should always consult the shop foreman as to the best machine for any job, and having done so should see that, especially in the case of "string" fixtures, the capacity or length of traverse of the machine table is considered (see Tables Nos. 16 and 16A).

The milling machine of the "Plano" or "Ingersol" type is undoubtedly very valuable for medium and heavy work, especially where large quantities of components are available, but as this type is not known to every shop, time will be better spent on a consideration of the more common machines, seeing that the different points to be watched when designing apply equally to all. Assuming that a component calls for plain surfacing, the choice may rest between horizontal and vertical milling as at A, Fig. 26. If the surface is very wide,

using roller mills (see Fig. 62) on a horizontal machine will probably be quicker than using an inserted tooth cutter in a vertical machine. Should the area be small, however, a vertical operation will be the quicker.

In the case of the component at B calling for "straddle" milling, the fixture can be made adaptable, so that in the case of horizontal machines being pressed with work, the fixture could



FIG. 26.

MILLING METHODS.

be arranged on an angle plate as at C and vertically "straddle" milled, though, in this case, as the end of the arbor is unsupported, in some machines, a slower feed must be used. Here also the "Duplex" type of machine, that is, where the two spindles are horizontal and opposed to each other as indicated at D could be employed, and, in the writer's opinion, this method is ideal.

Where the component is of medium size, with machining operations necessary on the side and face, the "Duplex" machine again proves its value, and it is being used with advantage at E, one spindle being adjusted to mill the top face and the other the side.

At F, Fig. 27, is seen a component having a face to be



Fig. 27

MILLING METHODS.

machined which varies in width, there being a space in the centre before again machining at the opposite end. For work of this class, in order to avoid waste of time due to—

(1) Table traversing during the blank, or
(2) Operator winding the table across the blank, or
(3) Inability to conveniently alter feed and speed to suit the reduced area,

a special type of machine has been introduced which possesses a number of " dogs " clamped to the side of the table, which automatically trip the feed mechanism. So that in the case of the component at F the table would traverse at a certain rate from *a* to *b*, the feed would then be tripped to, a faster one from *b* to *c*, and from *c* to *d* the table moves past at a rate of 100 feet per minute, being again tripped into the correct feed at *d* as before, finally, when arriving at *e* the table is tripped once more, the table running back to its starting place at 100 feet per minute, when the component is removed.

For continuous work the parts are arranged on a fixture H of circular form and fixed to a rotary table used in conjunction with a vertical machine. The table is loaded and the revolving mechanism put in gear, so that while the cutter is at work at *a* the operator is unloading the finished pieces at *b* and replacing them by raw ones. Semi-continuous work can be carried out on the horizontal machine by means of the fixture at J where the components *a* pass under the cutters while those at *b* are being loaded. On the completion of those at *a* the horizontal table is run back and the rotary table turned through 180 degrees, bringing those at *b* into line for machining, at the same time allowing for the removal and replacement of those at *a*.

Another and more common method is to employ what is known as a " string " fixture, that is a fixture holding a number of components in a line as at K. With this fixture, though the pieces can be removed as fast as they pass under the cutters, they cannot be replaced until the fixture has completed its traverse, and has been returned to its original starting-place. In this case a small waste of time occurs, but the operator can load the first one or two pieces into the fixture and then set the machine in motion, loading the remainder as the cutting proceeds.

One other machine caters for semi-continuous work, where the main table of the machine, circular in form, rotates carrying upon it, equally spaced from the centre, two tables capable of longitudinal traverse, as shown at L.

The parts are clamped in the fixture on the slide *a*, and while these are passing under the cutters the fixture *b* identical with that at *a* is being unloaded and loaded; here again, however, a small leakage of time occurs when revolving from *a* to *b*.

Setting Spots.—To facilitate the setting of the cutters relative to the fixture, setting spots are introduced. These vary according to the nature of the operation, but briefly, they consist of hardened steel pieces, generally permanently attached to the fixture in such a position that, by measuring from them, the correct position of the cutter is obtained without trouble.

A usual method is to fix upon a standard amount of space



FIG. 28.

THE USE OF SETTING SPOTS.

that is allowed beneath the spot and the cutter for the latter to be located correctly. For the information of the setter when no standard amount is fixed, the amount decided upon for a particular fixture should be plainly marked thereon.

A and B, Fig. 28, makes clear their use, where at A is seen a cutter milling the piece *b* to the height *d*, and the latter is determined by placing between the cutter a and the setting spot *e* a feeler having a thickness of ·010″, so that any guesswork is eliminated.

At B is a slotting cutter which has to be located correct for depth and also lateral position. This is obtained easily by means of the setting spot *a* which enables a feeler of calculated thickness to be inserted below the cutter and also at its sides.

A Simple Fixture.—The word simple is used in this case to mean a fixture holding only one piece, and from this a multiple fixture could be made by including a number of similar fixtures in one and possibly making one clamp hold more than one component.

At Fig. 29 is shown a fixture for holding an aluminium cover plate which is shown shaded in position. The fixture is intended for use on a vertical spindle milling machine where, as already mentioned, the tendency of the cutter is to fling the component off the machine, so that the small fixing holes previously drilled round the edge of the component are made use of to assist in holding. At *a* will be seen a mild steel pillar surmounted by a small stud, enabling the component to rest on the pillar, and the stud entering one of the drilled holes locates the piece previous to clamping.

As the piece calls for machining on its face, the question of clamping becomes difficult, seeing that it is only $\frac{1}{4}''$ thick and of aluminium. This difficulty is overcome in the manner indicated, provided that too much strain is not put on the nut H.

Describing the fixture it consists of a cast-iron base A provided with four steel pillars as at B and two pads C into which fits slide J. To hold the component down the nut H operates the sliding wedge J seen better in the sectional elevation.

The component is dropped on to the fixture and the knob L passes through the hole K in the wedge, after which the nut H is turned, causing the wedge to be drawn forward, drawing the narrow slot M of the wedge under the knob L thus preventing the component from being lifted out. As this may not necessarily lock the component firmly, the under side of the slot in the wedge is tapered slightly as at P, so that as the wedge is drawn across, it jambs or draws the knob L downwards, the latter being thus firmly held.

To prevent undue leverage being applied to H it should be made with a small head knurled, or a larger head left plain. If tommy pins are fitted to it they should be left very short. In cases like this holes for tommy bars or flats for spanners should never be called for, for there is nothing to prevent

the operator of little intelligence from inserting a bar of extreme length, or as is sometimes done, adding a length of steel tube, thus increasing the leverage and either breaking the fixture



Fig. 29.

SIMPLE MILLING FIXTURE FOR AN ALUMINIUM COVER PLATE.

or spoiling the work; in a few words, every endeavour should be made to render the fixture foolproof.

Fig. 30 shows a milling fixture for a component calling for machining in two planes—this illustration could also represent the end view of a "String" fixture, dealt with later.

Unless a machine of the duplex type indicated at E, Fig. 26, is available, or a milling machine of very heavy pattern, it will be necessary to finish the operations separately, which is not to be recommended.

The component is located in the fixture by means of the vee block A and the studs B and C. By locating under the flanges at B and C their correct thickness is assured, and by carrying out the operation on a duplex type of machine the two flanges will be machined at right angles. The clamp D is of the pattern shown in Fig. 14, C. The setting spots are



Fig. 30.

MILLING FIXTURE FOR COMPONENT REQUIRING MACHINING IN TWO PLANES.

located at E and F and require a "feeler" of ·01" to ensure the cutter being in the correct relation.

The tenon H is fitted with screws, making it possible to change to another size should it be necessary to transfer the fixture to another type of machine.

"String" Fixtures.—As the name suggests, this type occupies a considerable length of machine table and holds a number of components in a line. Unless the machine is provided with a tripping mechanism enabling the table to pass rapidly the blank spaces between the components, care must be exercised in arranging them so as to reduce this space to a minimum.

Needless to mention, that unless the operators are instructed

to handle any fixture to the best advantage, the efforts of the jig and tool department will be wasted.

Fig. 31 is a fixture of this type, the components being bronze eccentric straps for small pumps and the operation to mill each side of the lug. Advantage is taken of the shape of this piece to arrange a double row, employing two pairs of straddle milling cutters. The important point in the milling of the lug is the accuracy of its thickness, the depth not being so important. This being so and the component having had its large hole bored, it is located by this on two plugs A and an extra support is given by the pegs B.

To facilitate loading and unloading the head of the bolt



Fig. 31

STRING FIXTURE.

C and the clamp nut D are made smaller than the bore of the component, enabling the latter to be removed without having to take off the nut. To operate then, the components are slipped on each end of the bolt, the U washers are placed behind them and on tightening up the nut D the bolt C is drawn up, locking the pieces in position.

To prevent the bolt turning round when moving the nut, the former has a slot milled along it, and the grub screw H with the pin at its extremity is adjusted to allow the bolt to slide yet not revolve. The tenon J ensures the fixture being set at right angles to the machine spindle.

The body of the fixture is of cast iron and broadened at its base to give rigidity. The pegs B are made from drill rod



FIG. 32.

STRING FIXTURE FOR CAST-IRON BEARING CAPS.

hardened and tempered, the locating plugs A are of carbon steel left hard. The bolt C, nut D and screw H are turned from case-hardening steel, and after hardening the bolt is ground.

It is good practice when laying out some classes of fixtures, if not all, to indicate the milling cutters required; this tends to prevent anyone in the machine shops using unsuitable cutters and so not getting full productive value from the fixture. Another useful design is shown at Fig. 32, where cast-iron bearing caps for petrol engines are being rough milled before boring. The bolt holes are drilled previous to this operation and these holes are used for purposes of location. Though four holes are drilled in each piece, only two are used, these being at opposite diagonal corners.

The method of clamping on this fixture is interesting, being effected by the two jaws A operated by the nut B on bolt C. The latter passes through the body of the fixture and the nearest jaw into the further jaw, the hole in which is about $\frac{3}{32}$" larger than the diameter of the bolt.

A small pin D passes through the bolt and jaw, thus providing a pivot. The bolt should be arranged as near as possible to the object being machined.

To prevent the jaws from swinging out of position they are provided with a hole into which fits the guide pin at E, the hole being about $\frac{1}{8}$" larger than the pin. The pins also have a shoulder upon which bears the jaw. As the outside of the components are in a rough state, the upper ends of the jaws are serrated or roughened to make their grip more effective.

As with the previous fixture, the locking bolt is slotted and kept from rotating by means of the screw F. The base or body of this fixture is of cast iron, the jaws of mild steel case hardened, and pegs H are of carbon steel hardened and tempered, and the bolt, nut, and studs E are of case-hardening steel. Fig. 33 shows another string fixture in operation milling the stub axles of automobiles. The rigidity of this fixture will at once be noticed, and this is particularly necessary in this case, for the components are forged from steel of 30-ton tensile strength and the whole width of the gap is being machined in one cut. The cutter is of the interlocking pattern, that is, it is made in two pieces which are located side by side, the teeth being so cut as to overlap or interlock, enabling the two halves to be separated slightly when the width of the gap

gets small due to the wear of the cutter or resharpening, and this without leaving a gap where the halves part. The zig-zag or " staggered " parting line can be seen in the illustration.

The previous operations on the components was to turn the stem seen at A and drill the holes at B; these are therefore used for locating purposes. The gripping and location of these pieces is effected as follows. The stem of the component, which is turned at a slight angle to the base of the slot, visible at F, is passed through the slot in an adjustable wedge H, and



FIG. 33.—" STRING " FIXTURE USING AN INTERLOCKING CUTTER AND MILLING AUTOMOBILE STUB AXLES.

the hardened steel plugs D are pushed into the holes B, thus locating the forging square.

To lock it the bolts E are turned clockwise, thus forcing up the wedge H and jambing the component firmly.

The plugs D are an accurate fit in steel liners forced into the main casting, the liners preventing wear.

An advantage would have been to have replaced the hexagon headed bolts E by another form not requiring the use of a spanner, though when the use of the latter is unavoidable, those of the tube or " box " pattern will be found most convenient.

The three fixtures just described could be easily duplicated and used on a machine of the type indicated at L, Fig. 27.

Continuous Milling.—It is impossible to carry out continuous milling on a horizontal machine, but with a vertical spindle machine and a fixture located on a revolving table,



FIG. 34. FIXTURE FOR CONTINUOUS MILLING USING REVOLVING TABLE ON A VERTICAL MACHINE.

it is quite simple. Generally speaking the output by this method is regulated by the operator's ability to unload, clean, and reload the fixture while slowly revolving, and except for the sharpening or adjusting of cutters there need not or should not be an unproductive moment. A portion of a circular

fixture is shown in Fig. 34, where the small levers indicated are to be machined on one face of the larger boss. It will be seen that the components are arranged radially round the fixture as close as possible together, each pair being held by one clamp, the latter being a U washer held by a nut.

A hole previously drilled in the centre of the boss of the levers makes a suitable locating point, for which purpose the shouldered pins A are arranged round the fixture. The opposite ends of the pieces are kept in position by the pegs B.

The setting spot is placed at D, and it is not unusual to add one or two of these equally spaced round the fixture for the convenience of the setter. The steel peg E in the centre of the fixture is a push fit in the hole found in the centre of the revolving table, and is to ensure the fixture being located central thereon.

The body of the latter is of cast iron, the various pins of carbon steel hardened and tempered, while the washers, etc., are of mild steel case hardened.

A fixture of this pattern could be employed, if necessary, on a horizontal machine, and while it could not revolve continuously, a portion of one-half could be loaded and passed under the cutter, during which time the opposite portion of the fixture could be loaded. When the first loading has been milled, the table is run back and the fixture rotated through 180 degrees, bringing the next batch into position in front of the cutters. The cut is then started while the last batch is unloaded, etc.

Indexing Milling Fixtures.—In many cases it is necessary to repeat an operation on another portion of the same component, in which case the fixture is provided with a mechanism to ensure the relation between the two machinings being kept uniform. Fig. 35 is an illustration of such a fixture, where the component, an hexagonal iron casting, requires machining on six sides, having previously been bored and faced. The operation is performed on a duplex machine so that only three indexings are necessary.

To locate the casting an expanding mandrel is introduced, consisting of three segments A held together by means of the steel spring ring B. They rest on a cone piece C and on screwing down the nut D the upper cone E descends, thus forcing out the segments. To assist in arranging the faces of the component square in the first instance, the vee piece

F is released, which engages the corner of the casting while the expansion takes place.

This vee is held when rotating the component, by means of the peg H which, when drawn back, and given a half-turn, catches on the boss at J.

The lower cone C is provided with a wide base which acts



Fig. 35.

INDEXING FIXTURES.

as a platform, and the component being clamped thereon revolves with it. The outer edge of this platform has three slots K milled 120 degrees apart into which drops the lever L, the latter being retained there by the spring plunger M. The three studs P are provided to form a seating for the component. The base of the fixture is of cast iron ; the remaining parts, except springs, are of case-hardening steel.

CHAPTER VI

CHUCKS AND TURNING EQUIPMENT

Mandrels—Expanding Mandrels—Special Purpose Expanding Mandrel—Spring Collets—Thread Chucks—Turning Fixtures—Indexing Fixtures—Cross Slide Tool Holders—Circular and Dovetail Form Tool Holders—End Working Tool Holders—Plain Holders—Bushes for Holders—" Floating " Holders—Tap Holders and Die Adapters—Turning Tools—Cutter for Box Tool—Flat Form Tools—Circular and Dovetail Form Tools—Shaving Tools.

WHILE the tendency is always in the direction of quick and cheap production, which means the elimination of old machinery and methods, the centre lathe in various improved forms is still with us, there being some classes of work that



FIG. 36.

MANDREL FOR MULTIPLE TURNING.

can only be successfully carried out on this machine. This being so, the favourite method of handling work on the lathe will be mentioned first.

Mandrels.—Though the manipulation of mandrels is at least the work of semi-skilled operators, their construction should be as simple as possible. Fig. 36 shows a mandrel for use on a " Fay " automatic lathe, the components being shown shaped in position, consisting of steel ring bevel

gears, the operation being to machine the rim and face indicated, the former by means of a dovetail form tool (see Fig. 60) and the latter using ordinary turning tools.

The gears were about 6″ diameter, so that the rather large mandrel was made in several pieces, the parts A, B and C being steel forgings.

The operation being fixed for this particular lathe, which is arranged for multiple turning, two components were machined at once, and for this reason the correct relation of these must be maintained on the mandrel.

The mandrel would be best made of case-hardening steel, hardened and then ground.

Where the casting is long in proportion to its diameter and it is to be turned from its cored bore, a cheap form of



FIG. 37.

MANDREL FOR TURNING OUTSIDE CONCENTRIC WITH CORED BORE.

centring mandrel can be made as shown in Fig. 37, the component in this case being an automobile axle sleeve, where the rough-cored hole must be reasonably true with the outside diameter.

The coned boss A is integral with the shaft, which is provided with a taper to fit the nose of the machine.

The coned piece B has the same angle as A, i.e. 60 degrees, but is free to slide on the mandrel.

To help to overcome the difficulties caused by any irregularities of the ends of the bore, the two cones are relieved, leaving three points to engage the casting. By having at least one of the cones capable of revolving assists greatly in getting the component to run concentric.

For automobile work a large quantity of gears have to

be turned which have a splined hole of the form shown at A, Fig. 38. These are broached out, and so form a reliable point to work from, yet care must be exercised.

Fig. 38, end view, shows a section of the splined mandrel with gear in position, and it will be noticed at A that the *top* of the spline of the gear seats on the *bottom* of the mandrel spline. This is purposely exaggerated in the drawing, and as this is the condition under which the gears work when finished, the final result should be quite satisfactory.

In all cases the chucking method adopted should be as near as possible to the final working position of the component. The designer must see that the size of the spline on this turning mandrel takes this point into consideration,



Fig. 38

MANDREL FOR SPLINED GEAR BLANKS.

that is, the gear blank, when on the mandrel for turning, must also have its spline top resting on the bottom of that of the mandrel.

It might be considered possible to have a good round mandrel without the spline, but apart from assisting as a positive drive when turning, the final concentricity of the gear is almost assured by using the splines, for the reason already mentioned.

With the mandrel shown, the tapered part *d* is arranged with a draw-bolt *e*, making it possible to attach any other mandrel. The pad *f* is of hardened steel, to take any wear which would cause the component blanks to run eccentrically.

The mandrel shown in Fig. 39 is really intended for grinding the outside diameter of piston-rings, which are

indicated in position, the rings having been previously split ; but the principle of the mandrel may be adapted for turned work when necessary.

The method of using this tool is as follows : The rings, in clean condition, are placed together in the sleeve A, a little pressure being needed as the slots must be compressed to get them in. The sleeve thus filled is slipped on to the mandrel proper B, after which the washer C is put on the opposite end. When the nut D is tightened up, it will be seen that the rings are effectively clamped between the rims X and Y, the sleeve A being then removed.

The sleeve A should have a very long bearing surface, and be a sliding fit without any slackness on the mandrel B, otherwise the rings would not be loaded concentrically.



Fig. 39

MANDREL FOR SPLIT PISTON RINGS.

The washer C also must fit the mandrel accurately and have its outside diameter as large as possible, yet allow for the amount of metal to be removed from the rings.

Expanding Mandrels.—The use of expanding mandrels finds great favour among designers, especially where the work is second operation or rechucking work, that is, where a previous operation affords a machined surface of sufficient accuracy to locate from.

They are not, however, suitable for very heavy turning, that is, where the metal to be removed is excessive or the diameter is very large in proportion to the width of the article, because the absence of a positive drive will allow the component to turn round on the mandrel and become

loose when the tools commence to cut. Fig. 40 shows one form that has proved quite successful, consisting of a hood or nose-piece A made of mild steel, carbonized and hardened, which fits the screwed nose of a capstan lathe.

The steel segments B, three in number and of a diameter to suit the component *x* being machined—in this case a piece of switch-gear—are made of hardened steel to prevent wear, and slide up the coned portion of A when actuated by the coned bolt C. The latter is moved either by a rod passing through the machine spindle and operated by a hand-wheel, or else the usual clutch toggles fitted to the machine are adapted to give the necessary pulling motion.

To retain the segments on the cones, they are provided with a groove, into which fits a round steel spring which,



Fig. 40.

EXPANDING MANDREL USING DRAWBACK MOTION.

while holding the segments in position, allows them to expand when necessary.

To assist the component to adjust itself squarely on the mandrel, and also to give a positive seating from which to work, three hardened steel studs D are fitted equidistant at a suitable diameter, the component being held firmly up against them with one hand while operating the lever with the other. The angle of the cones should not be too great, about 30 degrees being considered suitable.

The nose-piece A can be made of cast-iron where the diameter is, say, over 5″, but the coned portion must be fitted separately, and be made of hardened steel.

Another form of expanding mandrel utilizing the ordinary or "push-out" motion of the capstan is given in Fig. 41.

It will be observed that the expanding portion and the nose-piece are combined, the expansion being effected by means of a plunger A, which is forced into the coned nose. It is noticeable also that the nose does not expand parallel as in Fig. 40, but pivots at X and Y, causing the front to be of larger diameter than the back, indicated by the lines *a*, *b*.

If the bore of the component is fairly accurate, this will not be sufficient to cause trouble, but if the bores are varying the component will only be held on the edge, thus reducing the grip, and the piece will work loose directly the tool touches it. If the component can be provided with a hole



FIG. 41.

EXPANDING MANDREL USING PUSH-OUT MOTION.

through its face and the nose-piece drilled for a steel peg a positive drive can be obtained.

The writer remembers the case of a soft brass tube, $\frac{3}{4}''$ long, $1\frac{1}{4}''$ bore, and about $\frac{1}{16}''$ thick, which had to be threaded on the outside about 26 per inch. In so doing about 70 per cent. were pulled off the mandrel when the die reversed and had to be chipped out of the die with a chisel, and others twisted on the mandrel after a few threads had been cut, using a self-opening die, the rings appearing to expand with the mandrel and so would not be gripped. The trouble was removed in a very simple way. Permission was obtained to make a rather heavy centre punch-mark on the outside

of the rings which would not interfere with their final use, and when putting the rings on the mandrel the "pimple" on the inside of the rings caused by the centre punch-mark only allowed the rings to go on by letting the "pimple" set in one of the slots of the mandrel, and when the latter was expanded it provided a very successful positive drive, with the result that the rings were threaded quite easily.

Special Purpose Expanding Mandrel.—It has already been mentioned that components with cored holes present difficulties where expanding mandrels are concerned, and under such circumstances if possible they should be avoided; but in some cases it is essential that this method of holding



Fig 42

SPECIAL EXPANDING MANDREL FOR PISTONS.

should be adopted, therefore a special mandrel must be designed. Fig. 42 is an instance of this, being a mandrel designed for holding cast-iron pistons while they are being turned.

With this component it is essential that the outside be reasonably concentric with the bore, which is rough as cast, therefore some form of gripping device that will work from the inside walls is necessary. The thick part of the component at B, where the grooves will come, are inconveniently placed for locating purposes, as they are some distance apart, so that the ordinary methods of cone expansion will not be of use.

An examination of Fig. 42, however, will show how this

is overcome. A is the main body screwed internally to suit the nose of the machines; the nose portion of the body has six holes drilled radially and equidistant round its circumference, through which protrude the gripping pegs C and C_1, two only being shown to avoid confusion.

The front pegs C_1 are expanded by the drawing back of the coned bolt D, which is effected by means of the rod E and wheel F, on turning the latter the bolt being drawn back. The pegs C are by the same movement forced out by the cone H, which is connected to the sleeve K.

Therefore by turning wheel F cone H is pushed forward and that at D drawn in till the pegs grip the casting. The boss M is fixed in the rear end of the spindle to support and centralize the sleeve and rod E and K.

To prevent either of the latter from turning round when operating the mechanism and yet allow end motion, the sleeve K is fitted with a retaining pin N and the rod E with a pin at P.

To assist the six pegs C and C_1 to return when the wheel F is released, they are each provided with a spring, shown only in the detail drawing at B_1, which is just sufficient to cause them to return far enough to clear the component as it is drawn off.

The piston butts up against the three small projections R at the end of the nose A, thus ensuring that the piston tops are of uniform thickness.

There is another type of mandrel where the pegs are replaced by two segments expanding on the double-cone principle as here described; but should the inside of the castings vary in form or be very irregular, loading and unloading is very difficult.

To add strength to the rather weak nose part of A, the radius at their junction should be made as large as possible, also the diameter of the nose should be made as full as possible—only the radius of the pegs need show above it.

Spring Collets.—These are employed in a variety of machines, and vary from the simple form shown in Fig. 19 to the more elaborate ones fitted with adapter pads as used on automatics. The most common type seen on capstan lathes are too well known to need any description here, but as special ones are often called for one is given in Fig. 43. This is described as an extra capacity collet, because it will

hold a diameter larger than the capacity of the machine, i.e. the size of the spindle bore.

Examining Fig. 43, it is seen to consist of a nose-piece A, made of mild steel, case hardened and ground on the coned portion *a*, and threaded at the opposite end to suit the particular machine. The collet B is usually of carbon steel and hardened, the rear portion being finally tempered to give the necessary spring.

Mild steel case hardened has given fairly good results, but it does not retain the springiness necessary for free working. As these collets are very expensive to produce, the draughts-



Fig. 43.

EXTRA CAPACITY SPRING COLLET AND NOSE-PIECE.

man must watch carefully the design, for a large number are spoilt in the hardening and in use, due to very thin section and also allowing sharp corners to exist.

The shell must be of as even thickness as possible, any sharp corners must be avoided, and if a square corner is unavoidable the danger should be minimized by putting in a small radius as at *b*. The small radius at *c* is to enable the grinding wheel to work right up to the back of the collet when grinding the stem *d*, and the latter must also be a good sliding fit in the machine spindle. The slots *e*, which give the necessary spring, in this case are four in number, equally

spaced round the collet, and extending to the rear face of the collet, and, as already mentioned, to avoid the chance of the collet breaking at their termination a hole is drilled for them to open into.

To ensure the true running of a chucking mechanism of this type, where it can be done, the draughtsman should call for the principal diameters to be ground when in position on the machine.

That is to say, after the nose has been threaded and hardened it should be screwed in position on the machine it is intended to be used, and by means of a portable emery-grinder the cone *a* should be ground perfectly concentric, because it is upon this part that the collet depends to assist it setting true. When the collet has been ground on the parts *h* and *d* it can be fitted to the nose-piece by whatever "drawback" mechanism is to be employed and the diameter *x* ground, thus securing perfect concentricity.

When making the collets, to prevent them closing in or opening out, which generally happens when heated and quenched for hardening purposes, the slots are not allowed to break completely through the front face of the collet, but a thin section, about $\frac{1}{8}''$, of metal is left, which retains the shape of the collet while being hardened and ground, the small piece of metal being finally removed by means of a thin elastic emery-wheel.

One difficulty with this type of chuck is that a slight variation in the diameter of the component will not allow the collet to draw back so far in its seating, and where the operation on the piece may be turning or grinding to a certain length or thickness this variation in diameter will cause a variation in thickness also.

One way of overcoming this trouble is to insert steel pegs into the holes placed as at K, which can either protrude through the slots in the collet or through holes specially drilled therein, and so form a positive seating for the component.

It might also be mentioned that in the hole K, or upon the pegs that may be used, can be placed an helical spring, which will assist the collet if it is inclined to stick when released.

Thread Chucks.—With some components that have passed through one or more operations, one of which is

threading, it may be necessary to perform further operations which must be perfectly concentric with the threaded portion.

In this case it is clear that unless the operations can be arranged so as to combine the threading with this later operation, the threaded portion must be made use of for purposes of gripping. Though this practice is not generally recommended, it is sometimes unavoidable, and if carried



FIG. 44.



FIG. 45.

THREAD CHUCKS.

out carefully no trouble should result. Figs. 44 and 45 show two designs for holding from a previously screwed part, the former making use of the drawback mechanism of the capstans and the latter the "push-out."

Taking Fig. 44 first, A is a hardened steel nose fitted to the machine, into which slides the plunger B, the latter being threaded to take the component. To operate this, the component C is screwed into the pad while the chuck lever of the machine is released until the component butts

against the face of the nose A. Upon closing the chuck lever the pad is drawn back, thus effectively locking the component in position.

To remove it, the operations mentioned are reversed.

Fig. 45 works on similar principles, except that the pad C is thrust against the component, giving a seating which helps to take up some of the cutting thrust.

The latter, however, though simpler to arrange, should be avoided, as the thrusting of the component away from its seating is bad practice. In both cases it will be seen that if the component was screwed into a plain nose without any pads, when the cutting tools in the machining operation had finished great difficulty would be experienced in releasing the component, due to the tightening effect of the tools.

In both cases, however, the fit of the component into the nose or pad must be good, otherwise in the jambing action when locking the threads will get distorted ; also the adjustment of the clutch on the machine must not be too heavy.

It will be noticed that both Figs. 44 and 45 can be also arranged to take components having female threaded parts.

Turning Fixtures.—The numerous awkward-shaped pieces that exist and call for turning operations necessitate the design of special holding devices to save time, and also to obviate the necessity of employing a fully skilled man, which otherwise would be necessary. To give a survey of the huge variety of such fixtures would require a separate volume ; but to give some idea what is meant by a turning fixture Fig. 46 is shown, where the piece, a steel forging, is indicated in position, and the extreme awkwardness of it will be noted.

This fixture was designed for a capstan lathe, the body A being screwed to fit machine nose. The boss of this component was previously milled on both sides and a hole drilled through, providing a good locating point by seating on the stud B, and being finally locked thereon by means of the swing clamp C, which holds the plunger D into the other side of the boss.

To centralize the round stem of the component E some form of self-centring clamp is necessary, and this is secured by introducing two vee-pieces F, F fixed to the slides G, G, which are actuated by the screw H, the latter being provided with a left- and right-handed thread. Thus, on turning the knob J,

the two slides are drawn together, thereby centralizing the stem.

The clamp C, swinging on its stud K, not only partly holds the component, but also acts as a binding unit on the necessarily peculiar-shaped chuck, the clamp screw and the mass of metal about it further acting as a counter-weight to the other half of the chuck casting.

Indexing Fixtures.—With components having a number of holes in the same plane the question arises as to whether they should be finished on a boring machine, drilling machine, or capstan lathe. Where the piece is exceptionally heavy



FIG. 46.

TURNING FIXTURE FOR AN AWKWARD FORGING.

and of large dimensions, the boring machine will be best; if of rather small size, a good drilling jig will get over the difficulty.

For work of medium size and weight, especially where the bores in question call for the use of several tools, such as boring, recessing, threading, etc., the capstan lathe undoubtedly is best. An interesting example of one of this class of fixtures is shown in Fig. 47, where an aero engine crank case is being machined.

The cast-iron body A is screwed to the machine nose in the usual way, the mass of metal at the top part being added to balance the fixture when running. The crank case is located

on a platform 6, being held by three plain clamps locked by means of a box spanner, the platform being provided with nine index holes, that is one for each hole being bored.



FIG. 47. INDEXING FIXTURE FOR OPERATING ON NINE BORES OF AN AERO ENGINE CRANK CASE.

The form of index plunger is rather important, the pattern shown in Fig. 22 being very satisfactory.

The tapered form of pin finds its location easier and auto-

matically adjusts itself to the hole, thus preventing any slackness and consequent rocking of the work being operated on. With fixtures that revolve, care should be exercised to see that any plungers, clamps, etc., are not so arranged that the centrifugal force will tend to loosen them, which, of course, would be very dangerous.

Nevertheless, the value of the fixture may be lost if the indexing and locking mechanism are too complicated.

The one illustrated was responsible for reducing the time per piece from 14½ hours to 4, the operation being to rough bore, finish bore, face and screw nine holes to a limit of ·001″.

Another form of indexing fixture allows of a lateral movement instead of revolving, an instance being the boring of a twin-cylinder motor casting, or the two bores of a water-meter, the slide carrying the work in this case being operated by a rack and pinion, and indexed for each hole by a plunger as usual, means also being provided to lock the slide before the fixture is allowed to revolve.

Cross Slide Tool Holders.—The designing of tool posts for holding ordinary turning tools of the flat type does not often become necessary, they being generally supplied with the machine. As, however, those in general use vary greatly in their degree of usefulness, a few remarks may be of value.

The first essential is that, having set the tool accurately, it should remain so under ordinary conditions. It should also be easily clamped and provided with some form of fine adjustment.

A comparison of the two types shown in Fig. 48 is interesting.

Taking A first, the tool *d* passes through the column *c* and rests across the top nut *a*, which screws into the lower nut *b*, these nuts making it possible to adjust the tool up and down.

It will be seen, however, that there exists a weak point, because the tool is being held by one screw only, which allows the tool to pivot when under cutting strain, and further, instead of having a solid foundation, this clamping screw is directly over the hole through which the stem *c* passes, with the result that if the tool happens to be somewhat soft in the shank or of thinner section than is general for that post, on tightening the screw *e* the tool will tend to bend to the line XY, shown exaggerated.

It will also be seen in the view C that it is impossible to set the tool near to the machine nose without excessive overhang, whereas with the other post, shown in position, the tool can be arranged both near the nose and with very little overhang. The post shown at B is an exceedingly good design, the body *h* with base broader than its top gives rigidity, and the tool is also held by two screws *ee*,



FIG. 48.

TOOL POST DESIGN.

and therefore cannot swivel. Adjustment is secured by means of a screw *b* engaging the wedge *a*, a movement of the former raising or lowering the tool *d*, a further advantage being that as the tool lays flush with the side of the tool-post it can be brought within $\frac{1}{32}$" of the spindle nose, as shown in the view C.

Circular and Dovetail Form Tool Holders.—To hold these types of tools special holders are required, for unless

they are correctly held considerable trouble will result. Not only must they be held well, but a means of fine adjustment is essential, especially with circular tools (see Fig. 59).

There are numerous patterns of these holders, but a very useful pair are shown in Fig. 49. Taking the circular tool holder first, it consists of a cast-iron bracket A provided



FIG. 49.

CIRCULAR AND DOVETAIL FORM TOOL HOLDERS.

with slots B for holding-down purposes, and a tenon C to fit the slot in the machine cross-slide, thus ensuring the bracket setting at right angles to the machine spindle.

The bolt D also passes through the bracket, and to enable the tool to be used close up to the machine nose the bolt-head is sunk into the tool; the bolt is also keyed as at F, so as to prevent it turning round when tightening up.

Fine adjustment is secured by means of the plate H and nuts J, J. On examining the detail drawing of the plate H, it will be seen that one side is perfectly flat, while the other is provided with a serration.

At the tail of the plate is a boss, through which is drilled a hole that clears stem P, and the boss is arranged between two nuts J, J thereon. The form tool itself being provided with similar serrations to those on the plate, is assembled with the latter, so that the two serrated faces meeting form a secure lock.

To make a fine adjustment it is only necessary to loosen the binding nut R and then raise or lower the plate H by means of the two nuts J, J.

In some cases the serrations are replaced by equally spaced holes in the plate, and a peg fixed in the side of the tool, but the former method is best. The fine adjustment is also secured by replacing the stem P and nuts J, J by a lever and nut, the latter being provided with a cam, a movement of which raises or lowers the lever. In making Fig. 49 care must be taken that the plate H is ground perfectly flat, otherwise the tool will not set square with the spindle.

The height X is less with tool brackets designed for the rear side of the cross slide by twice the amount the tool-cutting edge is cut below centre (see Fig. 59).

The holder for dovetail form tools can be made either of mild steel or of cast iron. The angle *a* is made 10 degrees or whatever angle is adopted in the particular works.

It will be seen that the body is slotted, thus enabling the tool *b* to be gripped by tightening the bolts *d*, and to prevent the latter turning the body is cut away at *c* to engage the bolt head. A good method of obtaining fine adjustment has yet to be devised ; but the mechanic sometimes overcomes this by putting a short bolt fitted with a nut under the tool, so that by unscrewing the nut the tool is forced up. This also acts as a positive stop should the tool have a tendency to work down, due to it taking an excessive cut or perhaps the fit of the dovetail being bad.

The dovetail should, of course, be to a standard form.

End-Working Tool Holders.—Holders for end-working tools, that is drills, taps, counter-bores, etc., are generally purchased from the machine tool builders, but, in the writer's opinion, it is cheaper to make even a small quantity if the

points really calling for attention are watched and the non-essentials neglected.

Plain Holders.—The simplest possible type of holder is shown in Fig. 50, and is quite satisfactory provided it is kept in good condition. The body A is made of case-hardening steel, and is ground on the stem and in the bore as indicated ; to add a fine finish anywhere else is a waste of time. The stop-screw B, though generally omitted, is of great value, preventing any possibility of the tool pushing back, and when short ends of tools are being used up a piece of steel of suitable length can be inserted to fill up the space.

A small point, though very important, is the end of the



FIG. 50.

FIG 51.

FIG. 50.—PLAIN END-WORKING TOOL HOLDER.
FIG. 51.—COLLET TYPE END-WORKING TOOL HOLDER.

screw D, which should have about two of its end threads removed and be hardened, to prevent it spreading or flattening due to continual tightening up.

The front bore must be ground perfectly concentric with the stem.

The collet type (Fig. 51) is a favourite for drills of small size from $\frac{7}{16}$" downwards, but with this method of gripping the stop-screw B should not be forgotten.

The body of the holder should be hardened, and both this and the coned mouth ground, making them both concentric and well finished. The cap A is of the same material as the

body, and, as it is subject to hard wear, should also be hardened.

The collet B1 should be made as long as possible, so as to give a good bearing surface and a better grip. The practice of splitting it into separate segments should be avoided, but if the reader has ever attempted to find a small part of a tool among the oil and "swarf" in the machine bed this warning will not be necessary.

Bushes for Holders.—These unimportant-looking pieces go a long way towards making a successful holder and are worth a little consideration. The one shown at A, Fig. 52, is split through one side and partly through the other, and the bottom of the slot is in the form of a radius to prevent the bush breaking.

The one at B has two splits, one opposite the other, both commencing at opposite ends and finishing a short distance



Fig. 52

BUSHES.

from the other end. With very large bushes a number of slots are introduced in a similar manner.

The bush C is, in the writer's opinion, the best, having a hole drilled half-way through clearance size for the holder screw, which grips positively on the tool itself, a small flat being ground thereon to assist this. The flange on the bush is also of assistance when it is being removed from the holder, a point much appreciated by tool setters.

Where the holder screw binds direct on to the bush, the latter should always be provided with a flat, otherwise the burrs thrown up by the continual tightening of the screw will make it impossible to remove the bush when necessary.

Floating Holders.—The object of this type of holder is to provide a means of allowing the tool to avoid an error due to the non-alignment of the machine spindle with the turret tool holder or turret itself.

The weak point with some forms of "floating" holders is that the movement or "float" is not parallel to the centre

line of the machine. A glance at Fig. 53 will make this clear, where A_I represents a piece of work with a hole to be reamed and the reamer is shown out of line. B_I shows the wrong method of "floating" the reamer to bring it in line, where it will be seen that the end of the tool only has been moved. C_I is the correct movement where the entire length of the reamer has been moved parallel to the centre line of the machine.

The result of reaming with the tool out of line or with the "float" incorrect is indicated at D_I, the hole being tapered or commonly called "bell-mouthed."

A very useful and simple pattern holder which fulfils



FIG. 53.

"FLOAT" AND "FLOATING" HOLDERS.

the necessary condition is given in Fig. 53. It consists of two main parts, the shank A and the nose B, the latter being held against the former by the two screws C, D, which are provided with a coned portion.

It will be seen that the nose can either be locked firmly against the body part A or given "float" according to how far the coned screws are released, in which case the "float" will be seen to be quite parallel. To prevent the screws working loose they are locked by means of a small screw H bedding on the brass pad J.

Tap Holders and Die Adapters.—There still exists much room for a good and simple design of releasing tap holder. Many are on the market which are both expensive and elaborate, and it is thought that the same results could be obtained with much simpler equipment.

Two are shown in Figs. 54 and 55, the former being a very old pattern and the latter a much simpler and more useful



Fig. 54.

Fig. 55.

Fig. 56.

Figs. 54 and 55.—Tap holders.
Fig. 56.—Die adapter.

type. The chief faults with that at Fig. 54 are that the wear is excessive, the pins A and B, also the end of the catch C, quickly wearing or breaking. The jarring that takes place when the pins disengage and when C engages is objectionable, especially with fine threads. Also, when using a tap of large diameter it is necessary to grip the sleeve D very tightly, and it will often happen that by so doing the sleeve closes slightly, gripping the stem E with disastrous results.

With the holder shown at Fig. 55 absence of vibration and accessibility to the parts that wear are its strong points.

In the position shown, the nose is out to its fullest extremity, and on reversing its direction of rotation the two pegs B, C will engage quite smoothly, C being provided with a spring to take the thrust. To retain the nose H on the shank D a race K is ground and a steel ball put in.

Peg B is fixed in its correct position, and C is provided with a flat which enables screw E to prevent it turning round yet allowing sliding motion. Both pegs have their tops shaped like a tooth to assist the release and to favour smooth working. The peg C is made as simple as possible, consisting of standard drill rod, so that if it wears or breaks the tool-setter can replace it in a very few minutes, this not being possible with the general design of holder.

The hole into which the peg B is driven should be continued straight through the nose, so that the peg, which is driven in, can be removed without much difficulty when necessary.

Die Adapters.—Though holders on the same principles as have already been described for taps can be bought or made, it is common practice to employ adapters of the pattern shown in Fig. 56. These are made of mild steel, and case hardened to prevent them getting damaged. The shank A, which fits into the bore of a standard tap holder, and the recess B, which takes the button die (see Chap. VIII), must both be quite concentric, and the shank should be a good push fit in the tap holder.

The recess is also better for the narrow channel removed from its corner, which prevents dirt or cuttings lodging therein and causing the die to set at an angle.

Three screws are fitted, the one at C having a coned point of about 60 degrees to open the die, and the remaining two, D and E, help to both close and hold the die, the latter generally having small hollows round its rim for the screws to engage in. As the wear on these screws is heavy, they should be made of tool steel and properly hardened and tempered ; also, if there is sufficient room between the cross slide tools, the screws should have thin heads in preference to the grub type generally used.

Turning Tools.—As the question of turning tools as used on the centre lathe has been dealt with in so many works

already published, it is not proposed to include them here. It is, however, worth mentioning that tool designers are getting much bolder with regard to cutting angles, especially those for use on capstans and automatics.

Cutters for Box Tools.—A cutter from a box-turning holder is illustrated in Fig. 57, which is intended for soft steel, aluminium or iron. The top rake is 35 degrees, which will enable the cuttings to sheer off with the minimum of friction, and the front clearance of 4 degrees is quite sufficient otherwise the strength of the cutting angle, which is 51 degrees, would be jeopardized.

In designing any tools the steel called for should be of standard section, so as to avoid extra machine work necessitated in reducing a piece perhaps from a large standard size to a smaller size which is out of standard.

To assist the tool setter, it is advisable to indicate on the drawing that the base of the tool must be ground flat; this will facilitate setting, and also the production of accurate work.

Flat Form Tools.—This type of tool is only used where a small quantity of a component are wanted and where accuracy is not of first importance. Their life is short, due to the fact that they can only be ground on their top face, and of course the form alters every time this takes place. Fig. 58 shows one of these tools, and the clearances will be noted are in violent contrast to the tool in Fig. 57.

In settling the amount of clearance a compromise must be effected between the material being machined, the width of the face being formed and the anticipated quantity of work to be accomplished. An average front clearance might be 4 degrees, and side clearance, which is not always put in, about 2 degrees. If the face being formed is wide, the tool must be kept as massive as possible, and in any case, while lack of clearance will produce friction which will spoil the tool at the point it takes place, excessive clearance will cause "chatter" or vibration, and so render the tool almost useless because of the badly finished work that results.

Circular and Dovetail Form Tools.—To maintain accuracy of form and avoid expense caused by the continual making of flat form tools, circular tools, i.e. tools of circular shape having the desired form on the periphery and with a portion cut away to form a cutting edge, are employed.

Standard diameters are fixed for these by firms to suit their machines, and here again a size should be selected that will not necessitate the reduction of a bar of material when making.

For machines like the popular Brown & Sharp Automatic the size of the largest diameter of the tool for use thereon is determined by the makers, and tables are also supplied by them to assist in the design of the tools.

The design and production of these tools would be greatly



FIG. 57.

FIG. 58.



FIG. 59.



FIG. 60.

FIG. 57.—FORM OF CUTTER GENERALLY USED IN BOX TOOL HOLDERS.
FIG. 58.—FLAT FORM TOOL.
FIG. 59.—CIRCULAR FORM TOOL.
FIG. 60.—DOVETAIL FORM TOOL.

simplified if it was possible to make the cutting face A, Fig. 59, on a level with the centre line of the work and the tool; but a glance will show that to do this would provide no clearance at B, with the result that rubbing and not cutting would take place. To get over this difficulty the cutting edge of the circular tool is arranged a certain distance, *a*, below the centre. In so doing, however, another difficulty is introduced when the tool is stepped to form more than one diameter.

It will be easily seen that the depth b increases as the cutting face A is lowered, so that this must be taken into account when designing and producing the form of the tool in the first instance.

For the purpose of calculating the diameter of the tool to allow for this, the following formula is given, where—

R = Largest *radius* of tool.
H = Amount cutting edge is below centre.
D = $\frac{1}{2}$ difference in diameters of work being turned.
r = *Radius* of smallest diameter of tool.

$$r = \sqrt{(\sqrt{R^2 - H^2} - D)^2 + H^2}$$

To give an example. The diameter of the tool blank is, say, 2″, to suit the machine and tool holder, the cutting edge must be, say, $\frac{3}{16}$″ below centre, and the diameters to be turned 1″ and $\frac{3}{4}$″ respectively.

Then—

$$R = 1''$$
$$H = \cdot1875''$$
$$D = \cdot125''$$

The smallest diameter of the tool will equal $2r$, and inserting these values in the formula, we have—

$$r = \sqrt{(\sqrt{1^2 - \cdot1875^2} - \cdot125)^2 + \cdot1875^2}$$
$$= \sqrt{(\sqrt{1 - \cdot03516} - \cdot125)^2 + \cdot03516}$$
$$= \sqrt{\cdot731025 - \cdot03516}$$

So that $r = \cdot8775''$.

This means that the diameter of the tool is $2 \times \cdot8775'' = 1\cdot755''$, from which it will be seen that the allowance necessary to make good the dropping of the cutting edge is $\cdot005''$.

Side clearance should be also given as indicated in e, Fig. 59, though in the writer's opinion side clearance should end at h, leaving a flat surface of about $\frac{1}{16}$″ according to the heaviness of the work and the degree of finish required, it being found that this tends to reduce the scoring of the work when the tool is withdrawing.

The serrations shown at d, Fig. 59, are intended to mesh with those on the plate H, Fig. 49, to prevent the tool turning

and assist fine adjustment. Some designers, however, prefer a number of equally spaced holes of about $\frac{1}{4}''$ diameter, the tool being provided with a steel peg to engage therein.

Dovetail Form Tools.—These take their name from the part A, Fig. 60, which enables them to be held firmly in holders of the type shown in Fig. 49. The points mentioned in regard to circular tools have a bearing on these also, for to secure satisfactory cutting action they must be tilted at an angle which affects the relation of one diameter being turned with another.

The cutting edge *a* is longer than the dimension *b*, which is taken at right angles to the tool face, and will vary according to whatever angle the tool is inclined. Where more than one diameter is to be turned, as with the circular tool just dealt with, allowance must be made for this, and the depth of the shoulder *b* is obtained from the formula—

$$D = d \text{ (cosine C)},$$

where $d = \frac{1}{2}$ difference of diameters to be turned,
C = Clearance angle of tool,
D = Depth of shoulder required.

Giving an example, suppose the diameters to be turned are $1{\cdot}250''$ and $\cdot 875''$ and the clearance angle is 10 degrees. Then—

$$d = \cdot 1875$$
$$C = 10°$$
$$\therefore \cdot 1875 \times \text{cosine } 10°$$
$$= \cdot 1875 \times \cdot 98481$$
$$= \cdot 1847''$$

So that the step *b* must be machined to a depth of $\cdot 1847''$ to produce a shoulder on the work of $\cdot 1875''$.

Shaving Tools.—As the name suggests, these tools are designed to remove a very light cut, thus securing extreme accuracy and fine finish. This is effected by giving the tool a certain amount of "float," and a glance at Fig. 61 will make its application quite clear.

The shank A is held in the machine tool holder, and pivoted about the bolt B is the cradle C.

The cradle has a fixed seat at D and an adjustable one at E, the latter being adjusted by the screw G.

A dovetailed recess is machined in both seats to take the tool and its steady.

The cradle C is "floated," and steadied by means of the screw H and the spring K.

In the view Fig. 61 the tool is seen shaving to size a shoulder, the work being, as it were, sandwiched between the tool and the pad, the latter being always a little longer than the tool, enabling it to secure a seating before the tool



Fig. 61

SHAVING TOOL.

commences to cut. The tool should be provided with about 2 degrees top rake and 5 degrees front clearance.

The tool shown in Fig. 61 is arranged for an "Acme" multi-spindle machine, the spindles of which run anti-clockwise; and this point should not be forgotten by the tool designer, otherwise expensive losses will be the result.

Parts A and C, together with the screws, are of mild steel case hardened, and the tool and pad are of high-speed steel.

CHAPTER VII

CUTTERS

Roller Milling Cutters—Inserted Tooth Cutters—Relieved Form Cutters—Hollow Mills—Running Stops—Cheap Type of Hollow Mill—Reamers—Expanding Reamers—Special Purpose Reamers—Boring Tools and Holders—Boring Cutters of Special Form—Flat Bits—Counter Bores and Spot-facing Cutters—Countersink Cutters—Spot-facing Cutters—Trepanning or Spirally Relieved End-Working Tools—Broaches.

As it would be impossible to deal individually with the vast number and variety of tools coming under this heading, those that form a basis for the design of others will be dealt with, and the word cutter will mean any cutting tool other than those already mentioned.

Roller Milling Cutters.—Standard cutters of this type



FIG. 62.

ROLLER MILLING CUTTER.

cannot be made profitably in small quantities by a firm not specially laid out for their production, but as sizes out of standard and of special form may be called for, their consideration will be well worth while. Fig. 62 shows one form of roller milling cutter, such as is used for heavy work on broad surfaces.

Assuming that the outside diameter of the cutter, which should be as small as possible without making the shell too weak, has been fixed, the next point will be to decide upon the number of teeth. With facing or "slabbing" work where a heavy cut is generally taken and where the escape of cuttings from under the cutter is difficult, a coarse pitch cutter, i.e. one with few teeth, thus leaving plenty of room between them, is best.

While it might be argued that the cutting strains would be reduced by dividing the work between a greater number of teeth, it should be remembered that the finer the pitch the more teeth would be in action at once. The chief objection to fine pitch cutters, however, is the lack of room for the escape of cuttings, sometimes called clearance or chip capacity, which, offering resistance to the cutting action, develops friction. In securing the full chip capacity, the strength of the teeth must not be sacrificed, a tooth of sufficient strength is obtained by allowing about $\frac{1}{32}$" for land at the cutting edge and then making the clearance angle about 85 degrees as shown. Tooth spacings that have been found by experience to give satisfaction are given in table No. 1.

TABLE NO. 1.

MILLING CUTTERS.

Diameter.	Bore.	Number of Teeth.	Key Slot.
In.	In.		In.
2	1	8	$\frac{5}{32} \times \frac{3}{64}$
$2\frac{1}{2}$	1	8	—
3	$1\frac{1}{4}$	8	$\frac{3}{16} \times \frac{3}{32}$
$3\frac{1}{2}$	$1\frac{1}{4}$	8	—
4	$1\frac{1}{4}$	9	—
$4\frac{1}{2}$	$1\frac{1}{2}$	9	—
5	$1\frac{1}{2}$	10	—
$5\frac{1}{2}$	$1\frac{1}{2}$	11	$\frac{1}{4} \times \frac{1}{8}$
6	$1\frac{1}{2}$	11	—
$6\frac{1}{2}$	2	12	—
7	2	12	$\frac{5}{16} \times \frac{5}{32}$

The spiral tooth is preferable to the straight one as the cutting action is greatly eased by the gradual shearing action due to this formation, especially where the material is of a tough fibrous nature. As with the majority of questions arising in connection with tool design opinions vary considerably, but an average angle for a spiral tooth would be from 10 to 15 degrees, and with cutters of less than $1\frac{1}{2}$" in length the teeth are generally left straight.

With all milling cutters of over $\frac{3}{4}$" wide the bore is undercut



FIG. 63.

INSERTED TOOTH CUTTER.

as shown at *a*, Fig. 62, the length of the undercut being between one $\frac{1}{2}$ or $\frac{2}{3}$ of the width of the cutter. This undercut facilitates grinding the bore of the cutter when being made and in no way interferes with its strength.

The table No. 1 gives proportions for roller mills, and it might be mentioned that the key slots are not always put in for special cutters, its absence allowing the cutter to slip on the arbor should any excessive cut or other strain be put

upon it, thus preventing the breaking of the teeth. On no account should any sharp corners be allowed to occur on a cutter, for this will greatly help in the breaking of the cutter when working, though it may never get past the hardening process for this reason. With cutters of $1\frac{1}{2}''$ length the nicks *b*, Fig. 62, known as chip breakers are employed. It will be seen that the cutting is broken up by this means, and the strains somewhat relieved. These nicks should be of concave form and of a depth equal to about twice the "land."

Inserted Tooth Cutters.—Milling cutters of whatever type should be kept as small a diameter as possible, because apart from the cost of the steel the life of these tools is very limited, also there is always the risk of the cutter breaking in the final hardening process—thus making the expense heavier. When, therefore, a cutter of large diameter is essential, it is well to introduce the inserted tooth type, one of which is shown at Fig. 63. The body *a* is generally of mild steel and the bushes *b* of tool steel. These bushes are provided with about 2 degrees taper, thus acting as a wedge holding the cutter blades *c*, which are of high-speed steel, in position.

The screws *d*, which hold the bush in its seating, are also made of tool steel for strength.

The holes *e* into which the bushes fit have a taper corresponding to that of the bushes, the latter being provided with a flat to effectively grip the cutter blade.

Table No. 2 shows some proportions for designing satisfactory cutters.

TABLE NO. 2.

INSERTED TOOTH CUTTERS.

T.	A.	B.	J.	K.	L.	Number of Blades.
In.	In.	In.	In.	In.	In.	
5	2	$4\frac{5}{8}$	$2\frac{3}{8}$	$\frac{15}{16}$	$\frac{3}{8}$	10
6	2	$5\frac{5}{8}$	$2\frac{3}{8}$	$\frac{15}{16}$	$\frac{3}{8}$	12
8	2	$7\frac{5}{8}$	$2\frac{3}{8}$	$\frac{15}{16}$	$\frac{3}{8}$	14
9	2	$8\frac{5}{8}$	$2\frac{3}{8}$	$\frac{15}{16}$	$\frac{3}{8}$	16
10	2	$9\frac{5}{8}$	$2\frac{3}{8}$	$\frac{15}{16}$	$\frac{3}{8}$	18
12	2	$11\frac{5}{8}$	$2\frac{3}{8}$	$\frac{15}{16}$	$\frac{3}{8}$	22

Another and cheaper method of gripping the blade is to drill holes at right angles to the face of the body as shown at B, Fig. 63, these holes being tapered to take standard taper pins which, having a flat machined on them, are driven home, thus securely wedging the blade.

Relieved Form Cutters.—With cutters relieved or backed off in the ordinary way, it is obvious that, as the cutting face is ground, the form produced is altered, and as it is essential with some cutters that their form must be accurately maintained, the cutter must be so designed and finally kept, in such a way that grinding does not alter this form, and form relieving is a method that gives the necessary clearance while fulfilling the qualification mentioned.



FIG 64

CUTTER FORM RELIEVED TO ALLOW FOR GRINDING.

This relieving is accomplished in a special lathe or machine, and it is necessary that the designer should indicate on his drawing that this method is required.

Fig. 64 shows a cutter of special formation with relief indicated. The latter must not be excessive, otherwise a weak tooth will result at the same time; if insufficient the cutter will rub rather than cut, which will quickly destroy the tool. A reasonable relief is obtained by striking an arc from a centre $\frac{1}{8}$ to $\frac{3}{10}$ offset from the true centre of the cutter as indicated. It will be noticed that the clearance angle is in this case only 45 degrees, this being done to increase the length of the tooth, thereby prolonging its life. As it is

unusual for form cutters to take heavy cuts, the angle giving chip capacity need not be so great as with the roller mill just dealt with. These cutters are, however, often provided with chip breakers in a similar manner to plain cutters.

Hollow Mills. — These are used plentifully on screw machines and capstans, though in some cases they can be employed with advantage on drilling machines. The most common pattern is shown in Fig. 65, and Table No. 3 gives two dimensions having a bearing on the diameter of the cutter bore.

This tool is usually provided with either three or four teeth milled straight as at A and suitable for brass, or at an angle as at B, thus giving rake and enabling mild steels and ductile materials to be machined with ease.

Their lengths will be about two to three times the outside diameter of the mill, though this must be altered to suit any special conditions prevailing.

To prevent the material seizing or getting jambed in the bore *c* the latter is tapered about $\frac{1}{8}$″ per foot for a length as shown at Fig. 65.

The length for this part is indicated in Table No. 3, where

TABLE No. 3.

HOLLOW MILLS.

Bore.	Outside Diameter.	Taper Portion.
In.	In.	In.
$\frac{1}{8}$	$\frac{3}{8}$	$\frac{7}{16}$
$\frac{3}{16}$	$\frac{1}{2}$	$\frac{7}{16}$
$\frac{7}{32}$	$\frac{5}{8}$	$\frac{1}{2}$
$\frac{1}{4}$	$\frac{5}{8}$	$\frac{1}{2}$
$\frac{3}{8}$	$\frac{7}{8}$	$\frac{3}{4}$
$\frac{1}{2}$	$1\frac{1}{4}$	$\frac{3}{4}$
$\frac{3}{4}$	$1\frac{9}{16}$	1

also will be found the outside diameter of the cutter. If the latter is kept too small, and the teeth made extra long, the tendency is for the mill to open out at the mouth as it is

fed on to the work, thus producing a taper on the latter. A flat *d* is machined on the outside diameter to enable the holder screw to grip properly.

The front clearance on the teeth is about 5 degrees, and this amount should not be exceeded, otherwise they will chip or "chattering" may ensue.

As the grinding of these cutters must necessarily produce



Fig. 65.—Hollow mills.
Fig. 66.—Large hollow mills.
Fig. 67.—Running stops.
Fig. 68.—Cheap type of hollow mill.

work of enlarged diameter due to the tapered bore, some means of adjustment is often provided, and this is accomplished in two ways. The mill is either split as shown in Fig. 65, the slot breaking into the bore on one side and a nick being made opposite this on the outside, which enables the clamp collar *a* to be used as a means of opening or closing the mill. In this connection it is well to mention that unless the tool has been properly hardened and tempered, while the mill will

close under pressure of the screw, the lack of spring in the tool will prevent it opening when the pressure is released.

The second method is to make the teeth of increased length and fitting a clamp collar as before, by which means the teeth are closed or opened at the front. The same remarks in regard to the correct hardening will apply here also.

Hollow mills have been used very successfully in drilling machines, being guided through steel bushes in the same manner as drills. Fig. 66 is a large type of mill used in this way, and to avoid the waste of expensive high-speed steel, it will be seen that the mill is separate from the shank, the latter being made of mild steel. They can be assembled by either making the mill a light push fit on the shank and then driving a tapered pin through them both, as shown, or providing them with threads and screwing them together.

The stem can be straight or be made to a standard taper to fit the spindle of the drilling machine.

Running Stops.—In the particular cutter illustrated at Fig. 66 it was found an advantage to introduce a running stop, that is, the two collars a and a_1, being locked together on the shank, were adjusted at a certain height so that when the mill had reached its depth they butted on the top of the bush through which the mill was passing, the usual machine stop being rendered unnecessary. This principle can be used to great advantage in drilling and boring, where the depth dimension is very particular and the height of the component varies. Fig. 67 will make this clear, where it will be seen that if the height of the component varies by however small an amount, if the cutter is dependent on the machine stop, the length of the portion machined will vary, but if the tool is provided with a running stop, which it is obvious, fixes the distance from the cutting edge to the stop face, and the latter butts against the face x of the component, the length of the machined portion will be kept constant.

A Cheap Type of Hollow Mill.—A hollow mill which for small work can be made much cheaper than other types is shown in Fig. 68. The cheapness lies in its being provided with only two teeth.

The teeth are formed by the milling cutter which should have an angle of about 50 degrees making two gashes at opposite sides, after which the front clearance angle can be put on by means of a file.

As there are only two teeth there is more of the cutter bore in contact with the work, and it is claimed that for this reason the diameters produced are more cylindrical. The proportions for these are as for the mills already described.

Reamers.—As with milling cutters the chief point with reamers is the teeth and their clearance. Naturally the size and form of the teeth will depend on their number, and standard reamers contain a larger number of teeth than the



FIG. 69.



FIG. 70.



FIG. 71.

FIG. 69.—TOOTH FORMATION OF PLAIN SOLID REAMERS.
FIG. 70.—EXPANDING REAMER.
FIG. 71.—SPECIAL REAMER AND COUNTERBORE.

designer usually calls for in special ones. The number of teeth are given in Table No. 4 for various diameters.

Special milling cutters are made for cutting the flutes in reamers, the angle of the teeth of which are generally about 85 degrees ; this size will be found to leave a substantial form of tooth, and at the same time provide a groove of sufficient size to facilitate the escape of cuttings. It has been found that when reaming bronze, brass, etc., the reamer produces a much finer surface if the teeth are not made radial, but slightly ahead of the centre as shown at *a*, Fig. 69, the amount

a being $\frac{1}{64}$″ for reamers between $\frac{1}{4}$″ and $\frac{3}{4}$″ diameter and about $\frac{1}{32}$″ for those above this. In the writer's opinion, however, if the clearance is correct and cutting lubricant used the teeth can be cut radial with every chance of success. "Chatter," the great enemy of the machinist, is often caused by the reamer being too keen, the remedy for which is in his own hands; excessive clearance on the outside is another cause of this trouble, and the designer should see that sufficient land is left which will act as a steady for the reamer, the width of this land as indicated in Fig. 69 should vary from $\frac{1}{32}$″ to about $\frac{1}{16}$″. Rose-chucking reamers, that is, reamers reserved for use on capstan lathes for "hogging" out rough holes, are provided with cutting edges at 45 degrees on their front edge, the flutes being milled as usual to assist in getting rid of the cuttings, but no side clearance is provided.

It is the practice in some works to make reamers with teeth unevenly spaced, it being claimed that this prevents chatter, but the idea does not meet with general approval. The teeth are generally milled straight, but a large quantity of standard and special reamers have teeth either left- or right-handed spiral. It is claimed for these that the shearing cut due to the spiral formation produces a better finish. The left-hand spiral prevents the reamer being drawn into the work which would occur with a right-hand spiral if hand fed. As, however, in most cases the reamer is fed in by power, this point does not arise, and a right-hand spiral which will assist the withdrawal of the cuttings from the hole being reamed will be found an advantage.

Expanding Reamers.—To avoid expense caused by the scrapping of reamers when they are worn undersize, various methods have been introduced, and the majority patented, for expanding them. A very simple yet successful form is shown in Fig. 70, consisting of stem A, a screw B, and the shell portion C.

The stem, which is made of mild steel, has a tongue at *a* which engages in a slot milled in the bottom of the reamer C, forming a positive drive, and a hole is bored and tapped to receive the screw B. The latter is made of case-hardening steel and has the thread of fine pitch, about 26 threads per inch to avoid working loose, and the coned portion *b* is ground after hardening. The shell portion is of high-speed steel bored to fit the plain part of the screw B and with a female

cone of 15 degrees. To allow of expansion it has three slots equally spaced round its circumference, breaking into the bore and terminating about $\frac{3}{8}''$ from the rear end. So that on turning the screw B by means of the square end, the male cone of the screw forces open the reamer.

Though the expansion is not parallel, as only the front of the reamer expands, this is by no means objectionable as a back clearance or taper is thus provided which is, in some classes of work, a distinct advantage.

Special Purpose Reamers.—While standard tools, which can be bought cheaper, should be introduced wherever possible, occasions occur when the design of a special tool is essential. Fig. 71 shows a reamer and counterbore combined in one tool, a method often adopted on turret lathe work when there are more tools than the turret can accommodate. If the hole is to be reamed to very accurate limits this combination is best avoided, because if the front cutting edges of the tool are unevenly ground or are allowed to become dull, the cutter will tend to spring away from the work, thus enlarging the hole. The method of relieving or backing off the reamer as indicated at *b* where the outer edge is convex in form instead of having a flat, tends to strengthen the teeth and also prevents "chatter."

TABLE, No. 4.

REAMER TEETH.

Diameter.	Number of Teeth.
In.	
Up to $\frac{1}{2}$	4 to 6
$\frac{1}{2}$ to $1\frac{1}{2}$	6 to 8
$1\frac{1}{2}$ to $2\frac{1}{2}$	8 to 12

The clearance on the front end of the reamer and on the teeth of the counterbore should not exceed 5 degrees, otherwise the tool may "dig" in and possibly break. This particular cutter is used to ream a "blind" hole, i.e. a hole blocked at one end, and also to make the bottom of the hole square, the latter being accomplished by the teeth on the

front part of the reamer. Fig. 72 is another reamer specially designed, and to avoid expense and hardening difficulties due to its length the main body of the tool is of case-hardening steel, the reamer portion *a* only being made of high-speed steel. The stem is provided with a tongue *b* which engages in a slot in the top of the reamer.

The sleeve *c* is bored out to slide on the stem *d*, the last $\frac{3}{4}$" of which is provided with a screw for holding purposes. Four holes *e* are drilled round the end of the sleeve to enable a tommy bar to be inserted when unscrewing the sleeve.

As the reamer *a* is hollow, the grooves for forming the



Fig. 72



Fig. 73.

Fig. 72.—special type of reamer.
Fig. 73.—shell reamer on boring bar.

teeth must not be allowed to sink too deep, otherwise there will be a danger of the reamer breaking. The spindle *d* is case hardened, as also is the sleeve *c*.

Fig. 73 shows a shell reamer A fixed on a boring bar, immediately behind the roughing cutter, thus enabling a hole to be rough bored and finished at one setting. Had it been necessary to remove the component between the roughing and finishing operations it might have been found that the work would not set itself in the same position, in which case the reamer A could have been made to "float" (see Fig. 53) by opening its bore a few thousandths of an inch, and the non-alignment of the component would thus be overcome.

Boring Tools and Holders.—Several firms have given considerable attention to the subject of boring bars and tools, and the result has been a number of patents covering their products, nevertheless many of the old types of bars still find favour.

One of the simplest is shown at Fig. 74 where the tool A is inserted in the bar B and held by means of the set screw C.



FIG. 74.

FIG. 75.



FIG. 76.

FIG. 77

FIG. 78.

METHODS OF FIXING BORING TOOLS.

To facilitate adjustment, and also to prevent the tool pushing back when under a heavy cut, the screw D is set behind the tool. By arranging the tool across the bar at an angle a slightly longer tool can be used. If necessary the finishing tool can be arranged close behind the rougher, in which case it should be so located that the cutting edges of the two tools are at opposite sides of the bar, thus equalizing the cutting strain. Where the hole being bored is very small and the bar

is being kept as large in diameter as possible, the existence of a binding screw on the circumference is impossible, unless a form of grub screw be used, and this is not satisfactory. In some cases this can be overcome by locating the binding screw at the end of the bar as shown in Fig. 75.

Fig. 76 shows another method of holding a boring tool, the length of the latter equalling the diameter of the hole to be bored. A flat is made on the side and in the centre of the tool, and a taper peg *a* is driven in.

As a rough idea of the proportions of this type of cutter to the boring bar, it will be found that the diameter of the cutter, or the thickness if not of round section, will be found quite satisfactory if made to equal about $\frac{1}{3}$ the diameter of the boring bar.

Figs. 77 and 78 show two other methods of fixing cutters. In the former the bar *a* is accurately slotted to take the tool *b*, the latter being held in place by means of a tapered screw *c*.

This taper proves very useful when it becomes necessary to "float" the cutter, it being merely necessary to release the screw according to the amount of "float" desired. With Fig. 78 the cutter *a* has a portion milled out of the centre which enables it to be located central with the bar without any adjusting, and is held there by means of the wedge *b*.

The cutting angle and clearance for boring tools will, of course, depend upon the material and in some cases on the section or form of the component being bored. Fig. 79 shows at X and Y a roughing and finishing tool. The former, it will be noticed, has a pronounced cutting edge *a* due to the tool angle of 60°. This provides a very free-cutting action, but the feed must not be too coarse, and if properly heat-treated such a tool will have a long life.

Clearance is provided on the side *a*, the top *c*, and the end *b*. For the two former this should be about 4 degrees for cast iron and brass, increasing to 6 degrees for malleable iron and soft steel and 10 degrees for aluminium. The end clearance need only be about 2 or 3 degrees, in fact for the finishing tool some designers leave this without any clearance on its end, merely providing a few degrees on its side. This is not advisable, as considerable friction takes place, and particles of metal will sometimes seize on to the cutter and cause enlarged bores. Fig. 79 is another form of cutter for obtaining the finished size, but is not adjustable for wear.

As the accuracy of the fit of the boring bar in its guide bush decides final accuracy of the work produced, any method of maintaining this should be taken advantage of.

Fig. 80 shows one method where the bar has, milled along its length, several slots equally spaced round its circumference, into which are fitted hardened steel strips. The bar is then placed between centres in a grinding machine, and the strips circular ground to the required diameter.



FIG. 79.

FIG. 80.

FIG. 79.—BORING CUTTERS.
FIG. 80.—BAR CONSTRUCTION.

The diameter of the slotted bar is, in this case, about $\frac{1}{8}$" less than the final diameter required, and the strips stood out about $\frac{3}{32}$" above this, before grinding.

Boring Cutters of Special Form.—It is necessary with some components to make a cutter of special irregular form, or else with several steps of different diameters which must produce a hole with these diameters concentric and at certain distances apart.

Fig. 81 shows a special flat-bladed boring cutter, perhaps familiar to the reader, used for forming the interior of certain



FIG. 81

SPECIAL FORM BORING CUTTER.

projectiles. The method of securing top rake is seen at *a* and this also allows the edges to lay central for the purpose



FIG. 82.

STEPPED FORM BORING HEAD.

of machining a flat bottom when necessary, the front clearance at *b* being about 5 degrees.

For roughing purposes the profile of the cutter is provided

with a number of nicks or chip breakers. This cutter is located centrally on the bar *c* by milling a slot to form a seating, in which it is held by means of a screw and a dowel pin as shown.

A boring head holding another special cutter is shown at Fig. 82, where the cutter *a* has three steps, and is held in a slot in the head *b* by means of the cheese-headed screw *c* and dowel pin *d*. Where it is possible, a component having a bore with several steps should be machined on the capstan lathe, using separate tools for each diameter, as the manufacture of these formed blades, which are scrap when worn undersize, is a very expensive item. The illustration shown is taken from actual practice, but cannot be described as good tool engineering for the reason mentioned.

Flat Bits.—Flat bits, one of which is illustrated in Fig. 83, share the work of the reamer and counterbore, their big advantage being cheapness of manufacture. During the late war, huge quantities of this type were used on fuse work, it being an easy job to turn the blanks on a good capstan lathe, set up an indexing head on the milling machine to mill the two sides; there then remained the three most important operations of giving side clearance, hardening, and finally grinding to size.

The portion *a* performs the work of an ordinary reamer and the rear part of *b* that of the counterbore. To enable the cutting edges at *c* to be so ground as to produce a square shoulder and also to facilitate any subsequent grinding, the blade is undercut as shown at *c*.

The blade portion should not be of too thin a section, and it will be found that a thickness of about $\frac{1}{5}$ D, where D equals the diameter of the cutter, or where there are two diameters as in Fig. 83, D can represent the mean of these.

The front clearance for the counterbore, also for the bottom of the reamer if it has to make the bottom of the hole square, should not exceed 4 degrees, otherwise the cutter will tend to dig into the work and probably break.

To avoid the tendency of bits and reamers generally to produce holes "bellmouthed," i.e. larger at the mouth than at the back, a slight back taper of about ·005″ per foot will be an advantage. The side clearance on all cutter foot the flat-blade type should be represented by an arc as shown in Fig. 84, A, in preference to the double flat method as at B, the latter

often being the cause of "chatter," particularly when new or recently sharpened.

Counterbores and Spot-facing Cutters.—There does not exist a great difference between these two types of cutter,



FIG 83.

FIG. 84.



FIG. 85.



FIG. 86.



FIG. 87.

FIG. 83.—FLAT BIT.
FIG. 84.—CORRECT RELIEF OR SIDE CLEARANCE.
FIG. 85.—SPOT-FACING AND COUNTERBORING.
FIG. 86.—COUNTERBORE WITH REMOVABLE PIN.
FIG. 87.—COUNTERBORE WITH REMOVABLE CUTTER AND PIN.

but it will be well to point out, that while a counterbore can be used for spot-facing, a spot-facing cutter cannot be used for making a counterbore. A glance at Fig. 85 will show that the cutter at A, which is not provided with any side teeth, would not allow of the escape of the cuttings if taken

far below the surface. Fig. 86 illustrates a counterboring cutter with removable pin allowing for the insertion of a pin of varying diameter, the cutter and shank being in one piece. The cutter is generally made of either carbon or high-speed steel. The pin can be either carbon steel hardened and tempered, or case-hardening steel.

The teeth can be cut spiral or straight, depending upon the nature of the material to be machined. With counterbores over $\frac{5}{8}$" diameter the shank can be made separate from the cutter portion, the latter being slipped on and retained by the pilot pin which screws into the shank as shown in Fig. 87.

Table No. 5 gives fair proportions for counterbores, though, naturally, the relation between the pilot pin and the cutter

TABLE NO. 5.

COUNTERBORES.

A.	B.	C.	D.		F.	G.	H.	Number of Teeth.
In.	In.	In.	In.	Pilot Pin to suit component.	In.	In.	In.	
$\frac{3}{4}$	$3\frac{1}{2}$	1	$\frac{1}{2}$		$\frac{1}{4}$	$\frac{5}{8}$	$\frac{3}{4}$	4
1	$3\frac{1}{2}$	$1\frac{1}{8}$	$\frac{9}{16}$		$\frac{5}{16}$	$\frac{5}{8}$	$\frac{3}{4}$	4
$1\frac{1}{2}$	4	2	$\frac{7}{8}$		$\frac{7}{16}$	$\frac{3}{4}$	1	4–6
2	5	$2\frac{1}{2}$	1		$\frac{9}{16}$	1	$1\frac{1}{4}$	6

diameter will vary, and must be made to suit any particular job. The stem or shank can be made straight or to a Morse taper, or any other standard taper required.

The angle of spiral should be about 5 degrees, and this amount will also be quite satisfactory for front clearance on the teeth. To avoid a common trouble with piloted cutters, that is, the seizing of the pilot pin in the hole, the pin is provided with a small groove which retains any grease and also collects any cuttings which would cause binding. Some form of groove or slot should be introduced on all bars or pins used for steady or guiding purposes.

Countersink Cutters.—As these are generally used for letting screw heads below the surface and the largest size called for is about $\frac{3}{4}$" diameter, they are usually made in one

piece as in Fig. 88. The diameter of the stem is equal to the diameter of the screw head for which the tool is intended, plus about ·002″ for clearance. Four teeth only are provided, these being formed by using a milling cutter with an angle of 90 degrees.

For large work, where a chamfer or radius is wanted for any purpose, the pattern at Fig. 89 is quite useful, being pro-



FIG. 88.—SMALL COUNTERSINK.
FIG. 89.—COUNTERSINK FOR LARGER WORK.
FIG. 90.—SPOT-FACING CUTTER.
FIG. 91.—TREPANNING OR SPIRALLY RELIEVED END-WORKING TOOL.

vided with a standard taper shank. If it is intended to use the tool on aluminium or steel rake must be given to the teeth, which can be done by cutting them at an angle of about 5 degrees as indicated by the line *a*, *b*. Note here also the groove in the pilot pin.

Spot-facing Cutters.—It has already been mentioned that this tool is employed for facing purposes only, therefore

no side teeth are provided. Fig. 90 shows a very useful pattern, the stem and pin A being made in one piece of case-hardening steel hardened and ground, while the cutter B is of high-speed steel held on to the pin by a grub screw C and driven by the tongue D. This convenience of being able to remove the cutter for grinding purposes is much appreciated in the machine shop.

Some idea of the proportions of this tool can be gained by an examination of Table No. 6. The diameter of pin and cutter as with counterbores, will be governed by the work to be done, but a set of cutters and bars to this standard will be found to be very useful and covering a very large range of work. For exceptionally large work the pattern shown in

TABLE No. 6.

SPOT-FACING CUTTERS.

l.	m.	o.	c.	h.	b.	a.	Taper (Morse).	Number of Teeth.
In.	In.	In.		In.	In.	In.		
$1\frac{1}{16}$	$\frac{3}{4}$	$\frac{1}{8}$	2 B.A.	$\frac{1}{4}$	$\frac{5}{8}$	$1\frac{15}{16}$	1	4
$\frac{7}{8}$	$1\frac{1}{8}$	$\frac{5}{32}$	0 B.A.	$\frac{1}{4}$	$\frac{3}{4}$	$1\frac{15}{16}$	2	4
1	$1\frac{1}{8}$	$\frac{5}{32}$	$\frac{1}{4}$ Whit.	$\frac{9}{32}$	$\frac{7}{8}$	$2\frac{3}{4}$	2	4
$1\frac{1}{4}$	$1\frac{1}{2}$	$\frac{1}{4}$	$\frac{5}{16}$ Whit.	$\frac{9}{32}$	$\frac{7}{8}$	4	2–3	4
$1\frac{3}{4}$	$2\frac{1}{8}$	$\frac{1}{4}$	$\frac{5}{16}$ Whit.	$\frac{5}{16}$	$1\frac{1}{8}$	5	3	4

Fig. 92 will be more economical as the circular cutter is replaced by one of the blade pattern.

This particular design of cutter is used in conjunction with the spot-facing fixture. Fig. 93 where the component locates on the hollow stud A which is perfectly square on its base B and the pilot pin of the cutter is a running fit in the bore C.

This method is very satisfactory where the hole in the component varies, making it impossible to pilot directly into the component itself.

The peg E prevents the component from swinging round when the cutting is taking place. The cutter blade, it will be noticed, is held in a similar manner to the boring cutter in Fig. 78.

Trepanning or Spirally Relieved End-working Tools.—The economy effected by the use of circular form tools for producing a desired profile on the circumference of a component has resulted in the introduction of a tool on similar principles for reproducing a form on the ends or faces of components in the lathe. Fig. 91 illustrates such a tool where the form can be accurately maintained after the tool has been ground.



Fig. 93.

Fig. 92.—SPOT-FACING TOOL FOR LARGE WORK.
Fig. 93.—SPOT-FACING FIXTURE WITH COMPONENT IN POSITION.

A section of the component is shown at A where the internal recess *a* is required to be maintained at a certain width. It is obvious that with a flat type of tool re-grinding would be very difficult, and the weak form of tool thus produced would "chatter" and probably break.

The lead of the spiral necessary to provide front clearance, assuming the circumference of the tool to be, say, 6″, would

be $\frac{1}{2}''$, from which it will be found that the clearance angle will be approximately 5 degrees. The diameter of the tool x should be a running fit in the component to act as a guide, and it might be said that the only objection to this type of tool is its lack of chip capacity. The cutter can be attached to a mild or other steel holder.

Broaches.—Broaching is an operation that is rapidly coming to the front not merely to displace some reaming operations, but on the actual production of formed work, an instance of this being the broaching of teeth on internal gears.

An illustration of a broach use on blanks for automobile gears to produce the spline in their bores is shown in Fig. 94.



Fig. 94.—broaches.
Fig. 95.—keyway broaches.

As the material from which the gears were made was a very tough steel, it was found necessary to have two broaches, one to follow the other, the one shown being the second.

In designing broaches there are several points to be kept in mind, the first of which is the amount of metal to be removed, and next, the proportion per tooth. For round holes that merely require sizing about ·20″, that is ·010″ each side, will be found a correct amount for the broach to remove, and the amount per tooth can be ·001″ or ·002″.

With the broach in Fig. 94, the total amount to be removed is shown by the depth of the spline, and allowing the same amount per tooth and the necessary amount of space between the teeth for clearance, it is obvious that a broach longer

than any standard broaching machine could accommodate would be necessary, hence the two broaches as already mentioned.

With this broach, seeing that only about $\frac{1}{16}''$ of the circumference of the hole is in contact with the broach, an amount of ·0025″ per tooth was removed.

The question of pitch of distance between the teeth must also be dealt with, and as a starting-point it has been found by experience that not less than two teeth, or more than four, should be in contact with the work at once. It is also clear that the space between the teeth must be greater in larger holes to give the necessary clearance for the cuttings.

There were 48 teeth in the broach shown, their diameter commencing at 1·3945″, leaving the last three parallel at 1·398″ to guarantee the finished size.

The correct form and spacing for the teeth is largely a matter of experiment, for when large chip capacity is secured it generally means a weakened section of broach.

The teeth are generally given a front rake of about 4 degrees and back clearance of 3 degrees as indicated and the land width of about $\frac{1}{16}''$. The diameter at B is a slide fit in the component, the splines at C having an outside diameter of 1·392″ and being a fit in the gear blank as it leaves the first broach. When operating the broach, the lack of chip capacity due to strengthening the teeth may be compensated by having plenty of lubricant pumped on to the broach; there are, however, some broaches on the market of hollow section, allowing lubricant to be pumped through and out of holes drilled at different points in the circumference which assists cutting.

Broaches are generally made in one piece, except where excessive wear occurs, and in this case very successful results have been obtained by making this part removable by providing it with a screwed portion. Keyways are also easily broached, the cutting portion of this type of broach being made separate from the body, into which it is carefully fitted and then pinned as shown in section at Fig. 95.

CHAPTER VIII

SCREWING EQUIPMENT

Dies—Hinged Button Dies—Spring Dies—Taps—Double Taps—Chasing Tools—Thread Milling Cutters.

Dies.—The development of the releasing die head, holding chasers which can be removed for grinding purposes, and replaced when worn, has sounded the death-knell of ordinary round dies, commonly known as button dies.

As, however, they are at the moment still widely used, it will be well to deal briefly with them.

The chief proportions are given in Table No. 7, the out-

TABLE NO. 7.

BUTTON DIES.

Outside Diameter.	Thickness.	Thread Size.
In.	In.	In.
$\frac{5}{8}$	$\frac{1}{4}$	$\frac{1}{16}$
—	—	$\frac{3}{32}$
—	—	$\frac{1}{8}$
—	—	$\frac{5}{32}$
—	—	$\frac{3}{16}$
—	—	$\frac{7}{32}$
—	—	$\frac{1}{4}$
$1\frac{3}{16}$	$\frac{1}{4}$	$\frac{1}{8}$—$\frac{5}{16}$
1	$\frac{5}{16}$	$\frac{1}{4}$—$\frac{3}{8}$
$1\frac{1}{2}$	$\frac{1}{2}$	$\frac{3}{8}$—$\frac{1}{2}$
2	$\frac{5}{8}$	$\frac{1}{2}$—$\frac{3}{4}$
$2\frac{1}{2}$	$1\frac{1}{16}$	$\frac{1}{2}$—1
3	1	$\frac{5}{8}$—$1\frac{3}{16}$

side diameter and the thickness being important because die holders and adapters are generally made to this standard.

In deciding the proportion of the teeth *b* (Fig. 96) and the size of the clearance holes *c*, a compromise must be effected between the two. As the majority of these dies are made with four teeth, a fair diameter for the clearance holes will be found to equal about $\frac{4}{5}$″ of the threading size of the die. The land *a* or width of the teeth must not be excessive, otherwise considerable friction will result, which generally means pieces of the thread being twisted off in the die.

It will be noticed that the size and position of the clear-



FIG. 96. FIG. 97.

FIG. 98.

FIG. 96.—BUTTON DIE.
FIG. 97.—BUTTON DIE HINGED.
FIG. 98.—SPRING DIE.

ance holes affect the width of the teeth, and also the amount of rake, if any is wanted, on the cutting edges.

With the clearance hole proportioned as already mentioned, the centre of the latter should be such that the clearance circle cuts away about $\frac{1}{8}$″ of the circumference of the centre hole.

The small hole *d* is inserted to add spring, and so facilitate the adjustment of the die. In some cases this hole is elongated as shown dotted, but in any case this hole or slot should not extend further than half-way between the clearance hole and the outside of the die.

Slot *e* is usually about $\frac{1}{16}$″ or $\frac{1}{32}$″ wide and its front is opened at an angle of about 60 degrees to enable the

tapered adjusting screw in the die holder or adapter to engage therein. The three countersunk depressions *h* are arranged 120 degrees apart, one at the back and one each side of the slot, for adjusting purposes, and their diameter should be to suit the diameter of the screws in any particular holder in use, or at least $\frac{1}{3}$ of the thickness of the die.

In some cases these dies are left quite solid, the slot *e* being omitted.

Hinged Button Dies.—The great disadvantage of button dies lies in the fact that it is impossible to sharpen them easily, and also, unlike other cutting tools, the cutting angle, rake, etc., cannot be varied to suit the various materials used. Button dies provided with a hinge as shown at Fig. 97, however, do permit of regrinding and the provision of rake when necessary, the only objection to these dies being their extra cost of manufacture.

The diameter of the head of the hinge-pin P should be about $\frac{1}{2}$ the thickness of the die, its thickness $\frac{1}{3}$, and the pin or portion between the heads $\frac{1}{3}$, and for the diameter of the pin, about $\frac{1}{4}$ of the die thickness will be quite good.

Dies should be made of steel made for that particular purpose, any alteration in form and pitch of thread after heat treatment rendering the die useless. If the size or form of thread is in any way special, the designer is advised to mark his drawing calling for suitable identification marks to be stamped on the die before finishing.

Spring Dies.—This type of die, illustrated in Fig. 98, is not so popular as the button shape, and the writer does not know of any particular quality it possesses, but it appears to find favour in America rather than this country. Its proportions are indicated in Table No. 8.

The gashes that form the cutting edges, generally three in number, are made with a milling cutter having an angle of from 60 to 70 degrees. The length of the threaded portion is from $1\frac{1}{2}$ to twice the diameter of the threaded bore. The lands *a* are proportioned as for button dies, that is, their width should equal about $\frac{1}{8}$ of their threaded bore.

The finished die should be hardened and tempered so as to provide spring for the jaws, because adjustment is obtained by slipping a collar over the jaws, the latter having three grub screws by which means the jaws are set in or released.

If the die is too hard the jaws will break on adjustment, if too soft the jaws will not open out after having been once set in.

Taps.—The manufacture of taps for ordinary commercial purposes is quite simple work, but where the form and pitch of the thread have to be very accurate, the various dimensions of the standard thread have to be modified.

In some cases the test for a threaded bore, apart from the fit of a thread gauge, will be a cylindrical plug gauge, of a diameter about equal to the core diameter of the thread being produced, and if this enters, the hole is not considered satisfactory. When inspection is very strict on this point,

TABLE NO. 8.

SPRING DIES.

Outside Diameter.	Length.	Size of Thread.
In.	In.	In.
$\frac{1}{2}$	$1\frac{1}{4}$	$\frac{1}{8}$
$\frac{1}{2}$	$\frac{1}{4}$	$\frac{1}{4}$
$\frac{3}{4}$	$1\frac{3}{4}$	$\frac{3}{8}$
1	2	$\frac{1}{2}$
$1\frac{3}{16}$	$2\frac{1}{4}$	$\frac{5}{8}$
$1\frac{3}{16}$	$2\frac{1}{4}$	$\frac{3}{4}$

the correct size can be obtained by varying the depth of the thread on the tap by a few thousandths.

Also when the form of the thread on the tap is affected by final heat treatment, thus interfering with the fit of the finished component, the effective diameter which governs the angle of the thread can be corrected to obviate this. Ordinary hand taps are rarely made, being bought cheaper from firms who specialize and produce them in huge quantities. Taps of special form of thread and diameter, however, are drawn by the jig and tool department.

As the length of the shank and its diameter is often decided by the conditions and holders available, it is not proposed to offer any proportions for this.

A tool having rake would be preferable for general work to one without any, so that in forming the cutting edges of a tap, the designer should call for a groove which will give this rake, at the same time not make it necessary to have a special milling cutter made for the purpose.

Cutters are available on the market for this work, though in the writer's opinion none are more successful than the ordinary concave cutter. Clearance for cutting is a very important point with taps, otherwise breakages become frequent, and it can be best secured by giving a liberal width of groove. A fair rule for this with taps having four



FIG. 99.—CORRECT RELIEF OR CLEARANCE ON TAPS.
FIG. 100.—DRAWING OF A SPECIAL TAP.

grooves is to use a convex cutter of a width equal to $\frac{1}{4}$ the diameter of the tap itself, and to sink it to a depth equal to one-half its thickness. As the threads are concentric with the hole being tapped, friction is ever present, but can be reduced by relieving the thread on a special machine commencing from a point in the centre of the land as at *a*, Fig. 99. If the relief commences at the cutting edge there is a risk of cuttings getting wedged at *b* when the tap reverses, also the life of the tap is shortened because this unsupported edge cannot last so long as that at *a*.

Fig. 100 is a representative drawing of a special tap,

where it will be noted that the root diameter is decreased by ·004″ for a special purpose. The heat treatment symbol (see Chap. XIII) is also added, calling for "Osborne's" carbon steel, which is considered to be quite satisfactory for this purpose.

The development of the collapsible tap for producing internal threads of large diameter, that is, of 2″ and over, has obviated the necessity for the designing of large solid taps, and also internal chasing is often preferred. There



FIG. 101.



FIG. 102.

FIG. 101.—LARGE "SHELL" OR SIZING TAPS.
FIG. 102.—DOUBLE TAPS.

are still, however, large taps in use for sizing purposes, that is, they are passed through a hole after rough chasing to give the final size, very little metal having to be removed.

These taps are generally made without a shank as shown in Fig. 101, the object being to make the latter of mild steel so that when the tap portion is worn it can be discarded without scrapping the shank, thus tending to reduce expenses.

The taps are held on to the shank by means of the screw A, and to prevent the tap from slipping the slot B engages on the tongues C on the shank.

Double Taps.—Where two concentric bores require threading, and the threads are of equal lead, this can be accomplished by means of a double tap as shown at Fig. 102. The larger tap is a sliding fit on the smaller and is held thereon by means of a screw A, the latter having a plain pin which enters a small slot, the length of which is sufficient to allow the large tap a small amount of movement, about $\frac{1}{8}$″, in the direction of the axis of the tap. This " play " is useful where the two taps are screwing up to a shoulder, guaranteeing the thread reaching up to this point. With larger size taps proportions laid down for smaller sizes are not adhered to, but where they can be followed it is much better. The lands of these large taps can be obtained by dividing the circumference into twelve parts and taking six of them as teeth, and the diameter of the shank should be made according to the size of the sliding tap, the bore of which must not be made too large, so as to run the risk of the tap cracking when going through heat treatment.

For the same reason the clearance slots of this part of the tap are made shallower, about $\frac{1}{2}$ the width of the grooves will be found to answer. In this design of tap the lengths x will, of course, depend on the component.

Chasing Tools.—For the production of threads for ordinary commercial work, a simple single-point chaser of the pattern shown in Fig. 103 is used, where it will be noticed that the tool only allows for a radius at the bottom of the thread, and if the blank diameter of the work is left oversize, a thread with a knife edge will result.

It is usual, however, to make the blank size slightly small, so that a very small flat on the thread top replaces the radius. Where the form is to be produced more accurately, provision must be made for the top radius in the manner shown in Fig. 104. The front clearance for these tools should be as small as possible, 2 to 4 degrees being quite enough, otherwise the cutting-point is weakened.

The chaser in Fig. 104, it will be noticed, is to be made ·001″ deeper than the standard size, making the core diameter ·002″ small, the effective diameter is also to be ·0015″ higher than the standard.

Thread Milling Cutters.—Thread milling is an operation that was greatly developed during the war, and lends itself to cheap production.

When considering the design of cutters, the points mentioned in connection with milling cutters hold good.

Fig. 105 shows a very useful type of cutter which is held on its arbor by means of a cheese-headed screw, the head of which fits the countersunk portion *a* laying flush with the end *b*, thus enabling the cutter to work close to a shoulder.

To assist in driving the cutter, a keyway of circular form



Fig. 103.—simple single-point chasing tool.
Fig. 104.—single-point chaser with provision for crest radius.
Fig. 105.—thread milling cutter.

is cut in the bore, which fits a key of corresponding shape on the arbor. The round form is selected because the avoidance of sharp corners prevents cracking, which could easily happen in so thin a shell. It will be noticed that this pattern cutter is counterbored both ends, permitting it to be turned round when cutting threads of different hand.

The teeth for this diameter cutter are ten in number and

the clearance slots are milled with a cutter having an angle of about 60 degrees, provided with a radius, and to a depth equal at least to twice the depth of the thread. The slots are so milled as to make the cutting edges radial and the top of the threads are form relieved (see Fig. 64), allowing for sharpening by grinding the cutting faces. The slots are also best milled at an angle of 10 degrees, which will greatly assist cutting and avoid " chatter."

In some types the cutter is integral with the arbor, but, in the writer's opinion, that indicated in Fig. 105 is both satisfactory and economical.

CHAPTER IX

GAUGES

Limits—Plug Gauges—Caliper Gauges—Scissor Gauges—Depth Gauges—Screw Thread Gauges—Profile Gauges—Combination Gauges—Variety—Materials.

To produce repetition work quickly and to dimensions, it is necessary to obviate the necessity of taking measurements with the usual precision instruments, micrometers, verniers, etc., and more so is this essential where unskilled or semi-skilled labour is employed. Another reason for their use is to secure interchangeability at as low a cost as possible. This is accomplished by fixing limits of accuracy to whatever class of apparatus is being manufactured, which will allow of the component parts being assembled without difficulty, and at the same time allow them to be produced cheaply. The plug gauge, Fig. 106, for example, has one end made to a diameter of ·75″ and the other ·760″, the difference, or tolerance, being ·010″.

This means that the hole produced must allow the ·75 end to enter and not the ·760 end, thus the hole will be within the limits decided.

Limits.—It is not proposed here to discuss in detail the question of limits and the methods of fixing them, because almost every firm has a different method, and also at the moment correct limits and gauging methods generally is forming the subject of much controversy. Further, the fixing of limits is usually accomplished by the chief inspector in conjunction with the person responsible for the design of the article being produced. As, however, in the building of jigs and fixtures some system of limits is necessary to secure interchangeability and the correct fit, details of a well-known scheme known as the "Newall" are given.

Table No. 9 gives various classes of fits for diameters, ranging from $\frac{1}{2}$″ to 12″, which is a useful range. As it is generally easier to secure varying degrees of accuracy exter-

NEWALL STANDARD LIMITS. — ALL SIZES UP TO 12". —

TOLERANCES IN STANDARD HOLES. (2 GRADES.)

TABLE No. 9.

CLASS.	NOMINAL DIAMETERS	UP TO 1/2"	9/16 - 1"	1 1/16" - 2"	2 1/16" - 3"	3 1/16" - 4"	4 1/16" - 5"	5 1/16" - 6"	6 1/16" - 7"	7 1/16" - 8"	8 1/16" - 9"	9 1/16" - 10"	10 1/16" - 11"	11 1/16" - 12"
A	HIGH LIMIT	+.00025	+.00050	+.00075	+.00100	+.00100	+.00100	+.00150	+.00150	+.00175	+.00175	+.00175	+.00200	+.00200
	LOW "	-.00025	-.00025	-.00050	-.00050	-.00050	-.00050	-.00050	-.00075	-.00075	-.00100	-.00100	-.00100	-.00100
	TOLERANCE	.00050	.00075	.00100	.00150	.00150	.00150	.00200	.00225	.00250	.00275	.00275	.00300	.00300
B		+.00050	+.00075	+.00100	+.00125	+.00150	+.00175	+.00200	+.00225	+.00225	+.00250	+.00250	+.00275	+.00275
		-.00050	-.00050	-.00050	-.00075	-.00075	-.00075	-.00100	-.00100	-.00125	-.00125	-.00125	-.00125	-.00150
		.00100	.00125	.00150	.00200	.00225	.00250	.00300	.00325	.00350	.00375	.00375	.00400	.00425

ALLOWANCES FOR VARIOUS FITS.

FORCE FITS.

F	+.00100	+.00200	+.00400	+.00600	+.00800	+.01000	+.01200	+.014	+.016	+.015	+.020	+.022	+.024
	+.00050	+.00150	+.00300	+.00450	+.00600	+.00800	+.01000	+.012	+.014	+.016	+.018	+.020	+.022
	.00050	.00050	.00100	.00150	.00200	.00200	.00200	.002	.002	.002	.002	.002 -	.002

DRIVING FITS.

D	+.00050	+.00100	+.00150	+.00250	+.00300	+.00350	+.00400	+.00450	+.00500	+.00550	+.00600	+.00650	+.00700
	+.00025	+.00075	+.00100	+.00150	+.00200	+.00250	+.00300	+.00300	+.00350	+.00400	+.00450	+.00450	+.00500
	.00025	.00025	.00050	.00100	.00100	.00100	.00100	.00150	.00150	.00150	.00150	.00200	.00200

PUSH FITS.

P	-.00025	-.00025	-.00025	-.0005	-.0005	-.0005	-.0005	-.00050	-.00050	-.00050	-.00075	-.00075	-.00075
	-.00075	-.00075	-.00075	-.0010	-.0010	-.0010	-.0010	-.00125	-.00150	-.00150	-.00200	-.00200	-.00200
	.0005	.0005	.0005	.0005	.0005	.0005	.0005	.00075	.00100	.00100	.00125	.00125	.00125

RUNNING FITS. (3 GRADES)

X	-.00100	-.00125	-.00175	-.00200	-.00250	-.00300	-.00350	-.00350	-.00350	-.00375	-.00400	-.00400	-.00425
	-.00200	-.00275	-.00355	-.00425	-.00500	-.00575	-.00650	-.00675	-.00700	-.00750	-.00800	-.00825	-.00850
	.00100	.00150	.00175	.00225	.00250	.00275	.00300	.00325	.00350	.00375	.00400	.00425	.00425
Y	-.00075	-.00100	-.00125	-.00150	-.00200	-.00225	-.00250	-.00275	-.00275	-.00300	-.00325	-.00325	-.00350
	-.00125	-.00200	-.00250	-.00300	-.00350	-.00400	-.00450	-.00475	-.00500	-.00550	-.00575	-.00600	-.00625
	.00050	.00100	.00125	.00150	.00150	.00175	.00200	.00200	.00225	.00250	.00250	.00275	.00275
Z	-.00050	-.00075	-.00075	-.00100	-.00100	-.00125	-.00125	-.00125	-.00150	-.00150	-.00150	-.00175	-.00175
	-.00075	-.00125	-.00150	-.00200	-.00225	-.00250	-.00275	-.00275	-.00300	-.00300	-.00325	-.00350	-.00350
	.00025	.00050	.00075	.00100	.00125	.00125	.00150	.00150	.00150	.00150	.00175	.00175	.00175

nally than internally, only two grades of fit, A and B, are given for holes, and the letters F, D, P, X, Y, Z indicate limits that will ensure a certain class of fit. For example, a shaft machined to F limits will require machine pressure to force it into a hole. One arranged for D limits will allow of a driving fit, while P limits give a push fit. Shafts machined to the limits at X and Y are suitable for revolving work, or running fits, and that at Z for the very accurate work called for in tool production.

This system simplifies matters considerably, for, instead of writing a dimension, say, $3\frac{1}{16}'' + \cdot0010''$ and $- \cdot0005''$, it is only necessary to call for $3\frac{1}{16}''$ A, and the mechanic knows at once what class of fit is required, and, more important still, any number of mechanics working to this method would produce exactly the same results.

Plug Gauges.—These vary somewhat in construction, but the chief points to be watched are, that they are not too bulky, and therefore expensive, and also that no elaborations are indulged in, some designers making this an opportunity to indulge in a variety of radii and diameters which are both costly and useless.

Remembering the huge variety of components produced, it would be deceptive to lay down any fixed rules for the dimensions of gauges of whatever pattern, and it is obvious that they must vary slightly according to the accessibility of the part being gauged. Table No. 10 gives proportions

TABLE No. 10.

SOLID PLUG GAUGES.

Z.	B.	C.	D.	E.	F.
In.	In.	In.	In.	In.	In.
$\frac{3}{16}$–$\frac{3}{8}$	$1\frac{1}{4}$	$\frac{1}{2}$	$1\frac{1}{4}$	$\frac{3}{16}$	$\frac{1}{8}$
$\frac{3}{8}$–$\frac{3}{4}$	2	$\frac{3}{4}$	$1\frac{1}{2}$	$\frac{3}{8}$	$\frac{1}{8}$
$\frac{3}{4}$–1	2	$\frac{3}{4}$	$1\frac{11}{16}$	$\frac{3}{4}$	$\frac{1}{8}$
1–$1\frac{1}{2}$	$2\frac{1}{4}$	1	2	1	$\frac{5}{32}$
$1\frac{1}{2}$–2	$2\frac{5}{8}$	$1\frac{1}{8}$	$2\frac{1}{2}$	1–$1\frac{1}{2}$	$\frac{1}{4}$

for plugs up to $\frac{3}{4}''$ diameter, below which diameter they are usually made solid. Above this size to about $1\frac{1}{2}''$ diameter

they are either lightened by having a hole drilled through, as shown at Fig. 106, the hole having a diameter of about half that of the gauge itself, or the two end-pieces are made separate and hollow, as shown at Fig. 107, thus allowing these to be replaced when worn, without scrapping the



Fig. 106.



Fig. 107.



Fig. 108.



Fig. 109.

Fig. 106.—SOLID PLUG GAUGE.
Fig. 107.—SOLID PLUG GAUGE WITH RENEWABLE ENDS.
Fig. 108.—PLATE PLUG GAUGE FOR LARGE BORES.
Fig. 109.—PIN PLUG GAUGE FOR SMALL HOLES.

entire gauge. In some works, where the hole to be gauged exceeds 3″ diameter, a plate gauge of the form shown at Fig. 108 is used.

It will be realized that when the limit on a hole of large diameter is very close, it will be found very difficult with a gauge that is heavy to hold it sufficiently square to enter the

hole, with the result that the work may be condemned, apart from which considerable time is wasted.

Endeavour should always be made to secure light gauges, while at the same time the possibility of distortion due to weakness must not be overlooked. The type of gauge at Fig. 108 is usually made from sheet steel $\frac{1}{4}''$ to $\frac{1}{2}''$ thick, and the diameter is removed or relieved as indicated at C, leaving a land at A, making it necessary for the inspector to test any hole in two positions to ensure that the latter is quite round.

The handle B is often made of steel tube for lightness, and if necessary the plate can be holed as at D for the same reason. Upon the holder a blank is ground, and the number of the gauge as well as the limits marked thereon.

For very fine holes, say $\frac{1}{8}''$ diameter and less, a useful and cheap form of gauge is shown at Fig. 109, consisting of two pieces of silver steel wire, one on the high and the other on the low limit, linked together, each having a steel or celluloid disc attached marked with the details.

Caliper Gauges.—These are often referred to as gap gauges, and again as snap gauges, but it is considered that the word caliper is more fitting, so this word will be adhered to.

This type is used for measuring external diameters and thicknesses, and as the tendency is for the jaws to be forced open, slightly, the strength of the part A, Fig. 110, must be of such a section as to withstand this. The thickness B will depend on the article being checked, if a shoulder exists, as at C, Fig. 111, then a very thin section of about $\frac{1}{4}''$ will suffice. The stem D would call for a gauge of wider section, not for strengthening purposes, but to enable the inspector to check over the length of spindle quicker. It will be best to err on the wide side with all gauges of the caliper class, thus securing a good seating, as at A, Fig. 112, in contrast to that at B, where, owing to the small area of seat, there is the risk of the operator not holding the gauge square and obtaining a false result.

To-day it is not the practice to make these gauges of sheet material, unless a very special form is wanted, as it is possible to buy steel forgings of very strong section visible at A in the photograph, Fig. 122, at a very low price, so that the designer should call for these.

Scissor Gauges.—The checking of diameters or recesses

calls for the introduction of a special form of caliper gauge known as a scissor gauge. Fig. 113 shows one in position, where it will be noticed that the two limbs are pivoted at a certain point, not too near the measuring points, otherwise the gauge would be clumsy when held in one hand, yet so as to multiply the limit allowed in the recess on the dial B.



FIG. 110.



FIG. 111



FIG 112.

FIG. 110.—CALIPER GAUGES.
FIG. 111.—DECIDING WIDTH OF GAUGE.
FIG. 112.—ADVANTAGE OF WIDTH.

Here it is seen that the limb C has a point which must rest between the high and low limits marked on the dial when the component is correct.

A somewhat similar form of gauge is used for roughly measuring the walls of cylinders, or other pieces where a direct measurement cannot be taken. In the latter case the pivot

pin is equidistant from both ends, so that the actual measurement taken on one end is shown fully on the other.

The spring D, Fig. 113, keeps the jaws E in contact with the object being checked, and also makes it possible to use the gauge in one hand.

Depth Gauges.—For checking the depth of holes where



FIG. 113.



FIG. 114



FIG. 115.

FIG. 113.—SCISSOR GAUGES.
FIG. 114.—PLATE DEPTH GAUGES.
FIG. 115.—PLUG DEPTH GAUGES.

there is a shoulder or flat bottom, the simplest form of gauge is, as shown at Fig. 114, made from sheet steel $\frac{1}{16}$ to $\frac{3}{16}$" thick. The limb A is inserted in the hole till it bottoms, when the shoulders B should swing clear of the top of the component.

When the opposite or low limb is introduced, it should just clear the bottom of the hole and rest on its shoulders D, the difference in the lengths of the limbs being equal to the tolerance allowed in the hole depth.

Another form of depth gauge is shown at Fig. 115, the gauge stem A being a slide fit in the casing B, and retained there by the spring C and the pin D. The tolerance allowed is represented by the step E at the top of the casing, so that the stem A is inserted in the hole, and the outer casing B depressed till it seats on the work, and the top of the stem should rest on the mean of the step E, when the depth of the component is correct. The edges of plate gauges should be chamfered to almost a knife so as to enable the operator to "feel" better, and also to prevent dirt lodging under and giving false results, where the edge of the gauge is hidden this is essential, and in the case of the depth gauge, Fig. 115, the bottom of the stem A should be hollowed, leaving a rim to touch the work.

Screw Thread Gauges.—These are among the most expensive gauges to produce, the final hardening process calling for considerable care. If, however, a suitable grade of steel is secured, this risk of spoiling is greatly reduced. Suitable proportions for ring gauges, Fig. 117, that is gauges for checking external threads, are given in Table No. 11.

TABLE No. 11.

RING SCREW GAUGES.

Bore.	Outside Diameter.	Thickness.
In.	In.	In.
$\frac{1}{8}$	$\frac{3}{4}$	$\frac{3}{16}$
$\frac{1}{4}$	1	$\frac{9}{32}$
$\frac{3}{8}$	$1\frac{1}{4}$	$\frac{1}{2}$
$\frac{1}{2}$	$1\frac{1}{2}$	$\frac{9}{16}$
$\frac{3}{4}$	2	$\frac{3}{4}$
1	$2\frac{1}{2}$	$\frac{7}{8}$

The gauge should always be provided with a knurl to assist when the screw fits rather tight.

As the hard work of a thread is taken on its side or angle, this is the part that should be watched carefully ; the crest and the root are obviously not so important.

The finished plug and ring gauge should not screw together, or at least the fit should be rather tight, because there is a tendency for operators to work on the high side for safety, and if the two gauges fit together easily, there is a probability that the components will not assemble.

The writer has found it a great advantage to have a groove made across the threads, as at A, Fig. 116, which enables screwed components, the threads of which are clogged with



Fig. 116.



Fig. 117.

Fig. 116.—Male screw gauges.
Fig. 117.—Female screw gauges.

dirt or cuttings, to be checked without having to wash out the threads previously, the groove acting as a scraper.

The difficulty with the gauging of a large quantity of screw threads is that, while the feel of a gauge is quite satisfactory for work that can be seen as well as felt, it is impossible to tell whether the screw that has passed is not low on the effective diameter and simply fits the screw gauge by binding on the tops of the thread, or whether the screw that has been rejected is a little low on the outside diameter, yet has a good angle. In this connection it might be mentioned that there is being developed a method of checking screw threads by reflecting their forms, considerably enlarged,

on a screen against the outline of a perfect specimen, by which means the real dangerous defects are at once made apparent.



FIG. 118.



FIG. 119.

FIG. 118.—PROFILE GAUGE.
FIG. 119.—PROFILE AND POSITION GAUGE.

Profile Gauges. — As the name suggests, this gauge checks the shape of a component or part of a component. One such is shown at Fig. 122, c, and in outline in Fig. 118

for checking the form and position of the grooves in the component B.

An improvement on this gauge would be to mount the gauge on two small blocks so that its profiled edge is raised from off the surface plate an amount equal to that of the centre line of the component as at E, thus facilitating accurate checking. Another profile gauge, which is also a position gauge, that is, a gauge which checks the relation of one part with another, is shown at D, Fig. 122, and in principle at A, Fig. 119. The component is a worm-wheel blank,



FIG 120

FIG. 121.

FIG. 120.—COMBINATION GAUGE.
FIG. 121.—COMPONENT AUTOMOBILE ENGINE VALVE FOR WHICH FIG. 120 WAS DESIGNED.

and the concave throat must be of correct radius, and also in correct relation to the seat of the recess C. The gauge therefore takes its seating from this recess, and the circular part checks the form of the throat D, this checking disc being provided with a knife-edge to facilitate this.

Combination Gauges.—It is often convenient to combine two or more of the gauges already mentioned, and to illustrate this Fig. 120 is given. The component is an automobile engine valve, shown in the photograph, Fig. 122, at E, as well as in Fig. 121. The gauge checked the diameter of

the stem, the straightness of the stem, the angle of the seat B, the diameter of the seat, the concentricity of the seat with the stem, and, lastly, the position of the slot C. The gauge fails in one respect, that is, there is no check on the stem should it be oval or undersize slightly.

Variety.—The writer has already mentioned that the designing of production equipment provides a wide field for the ingenious, and to give a very small idea of the multi-



FIG. 122.—GROUP OF VARIOUS GAUGES.

tude and variety of shapes of gauges alone the illustration, Fig. 122, is given.

Some shown have already been mentioned, and the remainder will be briefly introduced. The plate bearing the three pegs at F is for testing the smooth running and correctness of centres of three-gear wheels; by turning them slowly on this, any irregularity in the size or form of the teeth being immediately noticeable.

The base of this fixture is of cast iron, with pegs of hardened steel. The three gauges at H are for checking the relation of the crank pins of a four-throw crank shaft. The thin

stem is of steel tube with a hardened steel knife-edged roller at *a*, and the base is of aluminium, with a thin steel sole to avoid wear. The latter locates on the flange at the end of the crank shaft, and a gauge is provided for each crank pin or journal, thus ensuring their correct relation.

J is a plate-length gauge made from $\frac{1}{4}''$ sheet steel, with the high and low limits on each side. The small caliper gauge at K is made from a piece cut from a bar of round section, and for measuring up to about $\frac{3}{16}''$ this type can be economically made. The gauge L is for checking the thickness of the rim of a gear wheel, the long upper edge of the gap resting on the gear blank, the gauge being moved down till the small lip touches or misses the other side of the rim. The high and low limits are seen to the right and left.

Immediately above this is an adjustable caliper gauge, allowing an adjustment of $\frac{1}{4}''$ to $\frac{1}{2}''$, that is, its steel measuring pegs can be moved forward or backward to check any piece of a $\frac{1}{4}''$ thickness to $\frac{1}{2}''$, after which the pegs can be locked to prevent their getting accidentally altered. The "Go" pegs are, of course, at the front of the jaws, and the "No Go" immediately behind them. The large plug gauge at M was introduced for purposes of comparison with the plate plug gauge N laying in front of it. The extreme weight and cost of the former will be at once suggested.

At O is seen a dissembled plug gauge, of which mention has already been made. P is a position gauge for the two bores of the engine connecting rod seen laying across it. The two plugs T being a sliding fit in the frame, will not enter the bores of the connecting rod when it is placed in position, should either of its holes be out of position in any way.

The end view of the combination gauge already dealt with can be seen at R. A partial view of a $1\frac{1}{4}''$ male screw gauge is also visible at S. Two ring screw gauges will be noticed at B.

Materials.—As gauges are generally expensive tools, the degree of accuracy determining this, the material from which they are made should be such that the possibility of wear is reduced to a minimum. Tool or carbon steel is the best material for getting hardness with a view to avoiding wear, yet it carries with it danger, for it is possible that it may crack in the hardening, and perhaps a very expensive gauge scrapped.

This is partly overcome by using mild steel or case-hardening steels, and hardening to instructions supplied on application to the makers. In the case of plate gauges, only the parts where wear takes place need be hardened.

With thread gauges the steel should be selected that will harden at a low heat, thus reducing the tendency of the threads to warp or otherwise distort.

Where gauges are of rather bulky size the introduction of aluminium parts to secure lightness should be done with great caution, otherwise the relation of the more important parts may be thrown out by an accidental blow or strain.

CHAPTER X

PRESS TOOLS

Simple Blanking Tools—Multiple or Gang Tools—Holding Punches—Bolsters—Strippers—Stops—"Follow" Dies—Piloted Punches—Drawing Tools—Re-Drawing—Combination Tools—Bending Tools—A Special Forming Die—Sub-Presses—Materials.

THIS branch of tool engineering, together with that relating to automatic work, are in the writer's opinion the most important and offering the brightest future. The range of



FIG. 123.



FIG. 124.



FIG. 125.



FIG. 123.—SIMPLE BLANKING TOOL.
FIG. 124.—MULTIPLE OR GANG TOOL.
FIG. 125.—ARRANGEMENT OF PUNCHES FOR IRREGULAR SHAPED BLANKS.

articles produced by means of the press is enormous, reaching from pins and pen nibs to steel coffins and automobile side frames. More recent engineering practice is against the

addition of weight to secure strength, an example of this existing in line-shaft hangers, which, until a few years ago, were made of heavy cast iron, are now pressed out of steel.

A piece of, say, $\frac{1}{32}''$ sheet steel will bend easily in two hands, but make an acute corrugation in it, then try and bend across this, and the result that can be obtained by carefully designed press-work will then be apparent. The

TABLE NO. 12.

CLEARANCE BETWEEN PUNCH AND DIE ON DIAMETER.

Thickness of Material.	Clearance for Soft Brass and Steel.	Clearance for Hard Material.
In.	In.	In.
·0156	·0015	·0019
·025	·0025	·0031
·0375	·0037	·0046
·05	·005	·0062
·062	·0062	·0078
·093	·0093	·0117
·125	·0125	·0156
·1875	·0187	·0234
·250	·025	·0312
·312	·0312	·039
·375	·0375	·0468
·437	·0437	·0546
·5	·050	·0625
·625	·0625	·0781
·750	·075	·0937
·875	·0875	·1093
1·0	·10	·125

reader is advised to make a special study of this very interesting branch.

Simple Blanking Tools.—The simplest possible type of blanking tool is shown in Fig. 123, the blank being a round disc.

The fit of the punch A in the die B depends on the thickness of the material being punched. With heavy thick material more clearance must be allowed between the punch and

die so as to assist in reducing the strain of punching. With thin metal such as sheet "tin," etc., too much clearance would cause the finished blanks to have a burr on their edges. Some idea of the correct clearance can be gathered from Table No. 12, which is followed by the famous firm of Bliss.

The mouth of the die is generally left straight for about $\frac{1}{8}$" as indicated at H and then tapering away, the amount of this taper being about 1 or 2 degrees.

The punch should also be a good fit in the stripper plate D, preventing the tool setter from shearing the edge of punch or die when setting them in the press.

Multiple or Gang Tools.—In this type two or more blanking punches are grouped in one holder, and in arranging the punches care must be exercised so as not to waste any material, at the same time too close an arrangement of punches will mean thin walls between the dies. The general practice is to allow about $\frac{1}{16}$" or an amount equal to the thickness of the material being blanked. The actual punches could not, of course, be so closely arranged, but are located as shown in Fig. 124, where with the first stroke of the press the two blanks A are punched, the material is then fed along and those at B are completed.

To avoid waste of metal with irregular shaped blanks, the strip of metal is often fed through the press blanking one side A, Fig. 125, and afterwards passed through again so that the opposite side B is punched.

Holding Punches.—The most common and successful method of holding punches is indicated at Fig. 126, where the punch is forced through the punch plate accurately at right angles and the back is then riveted over.

Another method, especially with bending and forming tools, is shown at Fig. 127, where they are held by means of a countersunk headed screw and dowel pins, the latter passing through the back of the punch plate into the punch. With fine punches that are liable to break, provision must be made for quickly extracting them, and this can be accomplished as in Fig. 128 where the punch is held by an ordinary set screw, or the punch can be made with a head and passed through the punch plate, being a very accurate fit, the head being sunk below the surface as in Fig. 129.

Bolsters.—This name is given to the cast-iron or steel bed plate upon which is fixed the die when in the press, some

dies being fixed permanently thereon, others are removable. One form of bolster is given in Fig. 130, consisting of an iron casting with two lugs A for holding down purposes and a dovetail seating into which fits the die. The set screws B



FIG. 126.—HOLDING PUNCH BY RIVETING.
FIG. 127.—HOLDING PUNCH BY SCREWS AND DOWELS.
FIGS. 128 AND 129.—HELD SO AS TO FACILITATE REMOVAL.
FIG. 130.—BOLSTERS.

engage in small depressions in the side of the die holding the latter securely. The hole C should not be large enough to weaken the bolster, yet there is danger, if made too small, of a blanking operation being fixed on it and the hole not

being large enough to allow of passage of the blanks as they fall, the result being a continual jambing of blanks till finally either punch or bolster breaks.

Other pattern bolsters do not have the dovetail portion but are quite flat, the die being bolted direct on to the face.



Fig. 131.



Fig. 134.



Fig. 132.



Fig. 133.

Fig. 131.—Punch and stripper combined.
Fig. 132.—Spring actuated pressure rings as stripper.
Fig. 133.—Rubber buffer actuated pressure ring as stripper.
Fig. 134.—Drawing punch "knockout" as stripper.

Strippers.—The punch having pierced the metal would, on its upward stroke, take the metal with it, and as it can only be removed with difficulty, some device or stripper must be included in the equipment. The most common method of stripping is shown in Fig. 123, where the plate D would remove the metal from the punches as the latter

passed upwards. This form has the advantage of giving support to the punch, but makes it practically impossible to see the punch at work. A punch with stripper combined is shown in Fig. 131 where the punch A is inside the stripper sleeve B, so that on descending, the punch A passes through the material and the sleeve B is pushed up; as the punch is withdrawn, however, sleeve B, due to the action of spring C on the plate and pegs D, forces the material off the punch. In some cases the pressure ring (see Drawing Tools) also acts as a stripper, Figs. 132 and 133 are illustrations of this, where the rings A surrounding the drawing punch B strip or remove the drawn shell from punch. The ring receives its return motion from the springs C in the case of Fig. 132 or the rubber buffer D in Fig. 133.

India-rubber is preferred to steel springs in press tools, as it is more resilient, and also the life of the rubber is longer, due to the practice of building the buffers up with a number of pieces; adjustment is also secured in this manner.

In the upper tool of blanking and drawing dies, a stripper or "knockout" is located as at A, Fig. 134, where the component is prevented from sticking in the die B by its action. It is actuated by a projection in the press engaging the top C on the upward stroke. The "knockout" is retained by the pin D.

Stops.—These are arranged on the die to determine the relation of one blank to another. The usual method is shown at A, Fig. 135, where the bent steel peg is inserted, the metal butting against *a* when being punched. The peg is bent as shown, enabling the hole *b* to be drilled a greater distance from the die hole, thus avoiding the possibility of a crack when hardening.

One great trouble with this form of stop is that when feeding the metal along, if the latter is not kept under proper control, it may rest *on* the stop instead of against it, with the result that the punch descending on to a sloping surface as at B, Fig. 136, will be damaged.

This can be partly avoided by introducing a spring beneath the stop pin as shown at C, Fig. 137, so that it would be depressed in the event of the metal being punched thereon.

At D, Fig. 138, is seen another type of stop: the trigger *a* is suspended from the stripping plate *b*, and as the metal is fed along to the left it lifts and drops into the latest punched



FIG. 135.



FIG. 137.



FIG. 138



FIG. 136.

FIG. 135.—PLAIN STOP.
FIG. 136.—DANGER OF FIXED STOPS.
FIG. 137.—SPRING STOP.
FIG. 138.—TRIGGER STOP.

hole, after which, on giving the material a slight pull to the right, it is safely located against the trigger at C.

"Follow" Dies.—The name "follow" is employed because more than one operation—ranging from two to six—is completed with each stroke of the press, the tools for



FIG. 139.



FIG. 140.

FIG. 141.

FIG. 139.—SIMPLE FOLLOW DIE.
FIG. 140.—ADJUSTABLE GUIDE.
FIG. 141.—PILOTED PUNCHES.

the operations being located or following one behind the other.

Fig. 139 is an illustration of a simple tool of this type, the component being seen at A, each stroke of the press punching the slot and two holes and blanking out the shape. The

punches are seen located in the punch plate B which is screwed to the holder C, the shank of the latter fitting the ram of the press.

The strips or guides D are wide enough to allow of a free passage for the material being punched and as the width of the latter may vary a little and so either move laterally or stick between the guides, one of the latter is often provided with springs as at Fig. 140, enabling the guide A to meet any variation in width of material—the strength of the springs must be arrived at by experiment.

It will be noticed that the heavy blanking punch E is a trifle longer than the finer punches, this allows the former to enter the work first, avoiding the vibration or shock that would otherwise be thrown on the more delicate punches. The punches should not be too long, because they may buckle, but allowance must be made for grinding which is done on the faces F. The thickness of dies, naturally, will depend on the thickness and area of the piece being blanked, but it may vary between $\frac{1}{2}''$ and about $1''$.

Piloted Punches.—In cases where a very accurate relation must be kept between a hole and the outside edge of a stamping, it is usual to make a pilot pin on the end of the punch as in Fig. 141, so that the pilot pin enters the punched holes before the blanking punch.

The part *a* of the pilot must be parallel and a good fit in the hole.

Drawing Tools.—The production of cups, shells, metal boxes, etc., necessitate the use of drawing tools, the simplest form of which is known as the "push-through" type shown in Fig. 142.

It is obvious that only a shell of straight formation can be so drawn, the blank for which is located in the guide plate A and the punch B descending forces it through the die C and on the upward stroke of the punch the shell is stripped off by catching on the edge D which is left sharp for this purpose. The edge of the die E and the punch F must have a radius to assist the operation, and if the component must have a sharp corner, this must be arranged later by introducing another operation.

The method of drawing indicated in Fig. 142 can only be carried out with material of about $\frac{1}{8}''$ thick and over, because below this size the edge of the metal as it is entering the die

will cockle and form a number of creases in the shell. To prevent this a pressure ring is introduced, as in A, Fig. 144, so that the blank *b* is located in its guide over the die, and when the punch descends the steel ring A holds the blank firmly under pressure of the rubber buffer C while the punch continues downwards drawing the blank from beneath the



FIG. 142.



FIG. 143.



FIG. 144.

FIG. 142.—PLAIN PUSH-THROUGH DRAWING TOOL.
FIG. 143.—SIMPLE RE-DRAWING DIE.
FIG. 144.—DRAWING WITH PRESSURE RING.

pressure ring and so avoiding the formation of any creases. The ejector B operated by the buffer D removes the shell when drawn.

The buffer C must not be too strong, especially if the drawing punch has a small radius, as it will probably tear the metal instead of drawing it, yet if the pressure is too weak, the

creases will re-appear. As the drawing operation stretches the metal it is obviously impossible to give the size of the original blank to begin with, especially where the shell drawn is of irregular shape, but by mensuration some idea of the size can be calculated and then it is a matter of experiment to find the exact shape of the blank.

For cylindrical shells the blank can be found roughly from the formula—

$$D = \sqrt{d^2 + 4dh}$$

which is from the practice of Messrs. E. W. Bliss, of New York, where

D = Diameter of blank,
d = Diameter of shell,
h = Height of shell.

Re-drawing.—Where the depth of a shell is such that it cannot without risk of splitting be drawn in one operation, a re-drawing operation becomes necessary, as shown at Fig. 143. The shell previously partly drawn is located on a die having a "start" of about 45 degrees and the punch forces it through the die.

The number of draws necessary for a shell cannot be decided by rule; many points enter into the question, such as—

(1) Quality of material,
(2) Depth of draw,
(3) Radius required,

so that the matter becomes somewhat experimental. An idea can be gained from the telephone receiver, Fig. 149, which required 6 draws, the original blank being $\frac{9}{32}''$ thick and about 3″ diameter, and a brass projectile case 12″ long, 3·3 diameter can be produced from a blank 6·2″ diameter and ·330″ thick in 8 draws.

Combination Tools.—High production makes it necessary to reduce the number of operations to the minimum, and for this reason two or more operations are carried out with one tool, as shown at Fig. 145. A is the die and B the blanking punch, C is the pressure ring supported by three studs equidistant from each other, the studs being screwed into the plate D, the rubber buffer being compressed between it and plate

E. The drawing die F, which is of hardened steel, is located centrally to the die A. Pressure ring C should be a close fit between the blanking die and drawing die. The "knockout" pad H which also helps to form the shell is a push fit in the punch B and a hole is usually placed as at J to allow of the escape of air from K behind the pad. With this tool then, one stroke of the press blanks and draws the shell as shown



Fig. 145.

COMBINATION TOOLS.

at L. If the latter calls for embossing, the figure or letters can be arranged on the top of die F and pad H.

Bending Tools.—For plain right-angle bends the most simple form of tool is shown in Fig. 146, where the strip A to be bent is located in a guide plate B while punch C descends. For accurate work the possibility of the piece slipping while being bent is removed by employing a tool of the type shown

in Fig. 147 where the strip of material rests on its guide and on the spring pad A, the latter descending with the punch and ensuring a perfect bend. To assist bending a radius should always be arranged at B. The gap B is equal to the width of the finished component plus ·002″, and the punch



Fig. 146.



Fig. 147.



Fig. 148.

Fig. 146.—Plain bending tool.
Fig. 147.—Bending tool with spring pad.
Fig. 148.—Allowing for foreign substances in the guide plate.

D will therefore equal the same width, less twice thickness of metal and minus ·002″.

The guide plate for locating a piece to be pierced should be slightly chamfered as at A, Fig. 148, which prevents any chips of metal or other matter lodging in the corner, so that the piece to be punched does not lay flat, which may result in broken punches.

A Special Forming Die.—Fig. 149 shows an operation on

a brass shell, the latter being the case of a telephone receiver. The shell is first drawn from the blank which leaves the thickness at A about $\frac{1}{32}''$. To get the bulged part the drawn shell is placed in a die made in two halves B and C and having the desired shape cut out, the halves being retained by an outer clamp D. A definite quantity of water is then poured into the shell and a leather disc of a diameter to lightly fit the bore placed in after. The ram of the press descends and



FIG 149.

SPECIAL FORMING OPERATION.

rod E, attached to it, forces the leather blank down the shell, causing the water to bulge the shell bottom and conform to the shape already cut out in the die. Water and special india-rubber pads can often be used in this manner for unusual forms.

The clamp D operates on the principle of a two-jaw chuck, the clamps being tightened or released by means of a right- and left-handed screw.

Sub-Presses.—The latter consists of a ram working in a sleeve operating a punch and die which are permanently

assembled, so that no setting is necessary, the sub-press being placed under the press ram, and nut A, Fig. 150, connected thereto, after which the base B is clamped to the press bed and the stroke adjusted to suit the die.

This type does not pay except for very delicate and important parts such as clock gears, etc., but once made they last a considerable time, as no interference with the alignment



Fig. 150.

SUB-PRESSES.

of punch and die is necessary, the latter being the chief source of wear in press tools.

The one shown at Fig. 150 is for producing the brass disc C with its four holes, which must be kept very accurate. The ram, which is also the blanking punch, is seen at D and the die portion at E. The stripper ring, spring actuated, is visible at F. The upper stripper H is arranged inside the punch D, where it is connected by means of three steady rods J to the plate K which thrusts against the spring L.

The punches M for the holes are located in the upper stripper H, being a very accurate slide fit therein, and reaching almost to the bottom of the blanking punch. The metal is fed beneath the punch and die, and when the blanking punch descends, the disc is momentarily held between the upper stripper H and the die E, while the ram of the press, still descending, forces the small punches M down to complete the work. As the press ram ascends, lifting with it the punch D, stripper F forces the metal up to its original position, and as the disc is at that moment held by the upper stripper on the die face, the disc is lightly pressed back into the hole in the material from which it was previously blanked, from which it must afterwards be very carefully removed. By the method described it will be seen that a perfect stamping is continually being produced, not even the usual distortion due to the "flow" of the metal interfering, because when the holes are punched the disc is sandwiched between the upper stripper H and the die E. The punch D is held central in the outer casting by a babbit liner P which can be adjusted when necessary by the nut R.

Materials.—Press tools score over cutting tools because the expensive high-speed steel is not necessary. The steel used will largely depend on the material being punched, but one would be perfectly safe in using carbon steel for all punches.

For punching brass and softer materials a mild steel punch left in its soft state is often used, the dies in all cases being made of carbon steel hardened and tempered.

For piercing punches, ordinary silver steel or drill rod is quite good if not left too hard.

A common practice is to use case-hardening steel and give it the necessary heat treatment, afterwards finishing by grinding.

When punching or forming ebonite, a common occurrence in the electrical trade, it will be found of great service to arrange a small water boiler near the particular press and run the hot water through pipes which can be arranged to pass through the die bolster; by this method very little work is scrapped due to cracked ebonite. In very hot weather this can be obviated by allowing the ebonite to remain in the sun an hour or so before using.

CHAPTER XI

BROWN & SHARP CAMS

Feeds and Speeds—Direction of Spindle Rotation—Total Revolutions per Piece—Correcting the Revolutions—Selecting Gears—List of Operations—Determining Cam Surface—Plotting the Cam—Back Slide Cam—Front Slide Cam.

While the tendency in the design of machine tools is to reduce the skill required for their setting up and operation, the Brown & Sharp automatic, one of the few that require special cams designed for every new piece of work, still retains its popularity. The objection to the necessity of continually designing cams is outweighed by the fact that when so doing the designer is able to reduce the idle time to an absolute minimum, and the finished cam can then give the maximum production in the minimum time. To give an idea of the method adopted, it is proposed to design cams for a Brown & Sharp automatic No. "00," for making a quantity of mild steel screws as shown in Fig. 151.

The cams are three in number, the lead cam, Fig. 152, which controls the movements of the end-working tools, the rear and front cross-slide cams, Fig. 153, which are responsible for the working of the cross slides, carrying the cutting off and form tools.

Feeds and Speeds.—The working out of the proportions of the various lobes of the cam is based on the revolutions of the spindle, therefore this is the first consideration.

For machining mild steel 70 to 80 feet per minute is quite a satisfactory speed, so that an examination of a surface speed table will give the number of revolutions for material $\frac{1}{4}''$ diameter as 1,069. It must be remembered, however, that the speed changes on the machine are limited and the nearest speed to this is 1,087, so this will be decided upon as near enough.

The threading, to obtain satisfactory results, should be carried out at a lower speed; about 30 feet per minute is considered correct, and the nearest obtainable to this is

792 revolutions per minute, so that the two speeds, 1,087 and 792, will be accepted as giving good cutting results. As the rate of travel or feed of the cutting tools is an important factor in designing the cam this must also be decided upon, it being possible to proportion the cam so as to vary the speed to suit any particular tool. Considering the component Fig. 151, which is of mild steel and has no extremely fine limits, a fairly coarse feed may be selected.

To machine down to the thread diameter $\frac{3}{16}''$, only $\frac{1}{32}''$ of metal each side requires removing, so that a feed of about ·010″ per revolution will not be too coarse. The reduction of this thread diameter for the formation of the $\frac{1}{8}''$ pin also only calls for the removal of $\frac{1}{32}''$ of material, therefore the same feed can be used here. The feed of cross-slide tools must not be quite so coarse, and its selection is not quite so easy as for end-working tools, there being several points which must be watched.

The grade of material being used, the diameter, the width of the form and cutting-off tools, and the condition of the machine, must all be considered.

With the component under consideration, it will be assumed that the cut-off tool is of substantial width, the material quite ordinary and the machine bearings in good condition, then as the form tool has only to make the recess under the head and remove burrs, a feed of, say, ·002″ per revolution will not be excessive.

Direction of Spindle Rotation.—As the threading die must be run on to the work at the slow speed, i.e. 792 r.p.m., there is no reason why the high speed at which the spindle revolves when reversed for running off the die should not be taken advantage of.

It can be arranged therefore that the reduction of the stock diameter by the hollow mill or box tool can be done on the forward motion, and the forming and cutting off when the spindle is running backward at high speed.

Total Revolutions per Piece.—Having fixed upon the necessary feeds and speeds, the operations can be fixed and timed from which the total revolutions can be obtained. For the component Fig. 151 the operations will include turning down to $\frac{3}{16}''$ diameter as far as the head, which is best accomplished by means of a hollow mill, and then turning the $\frac{1}{8}''$ nose portion, using for the purpose a box tool.

The piece is threaded next, and immediately the die is withdrawn the form and cut-off tools move forward, operating simultaneously. First, however, the turret is indexed into position, and the spindle reversed which both take place together. For this particular machine the time for this is one half-second, so that with the spindle running at 792 r.p.m., the indexing will take $6\frac{1}{2}$ revolutions, to which it is usual to add two or three more, in this case to make even figures add, say, $3\frac{1}{2}$, making the revolutions for indexing 10.

The turning operation comes next, and the length $\cdot 750''$ divided by the feed per revolution $\cdot 01''$ will give 75 revolutions, to which add $\cdot 01$ for clearance, making 76 revolutions.

The turret is again indexed, taking as before 10 revolutions, and bringing into position the box tool for turning the point. The length $\frac{1}{4}''$ is divided by $\cdot 01''$, giving 27 revolutions for this operation, after which the indexing of the turret again adds ten revolutions.

The threading operation comes next, and the revolutions for this are obtained by multiplying the length to be threaded by the number of threads per inch, so that $\cdot 5 \times 26 = 13$, to which is added 2 revolutions for clearance, making 15.

To run the die off the screw on reversal of the spindle will add a similar number. Following the die is the cross slide tools, and taking the cut-off tool as the one that moves the greater distance and therefore upon which any calculations should be based, it will be seen that the travel equals $\cdot 125''$, that is, half the diameter of the component plus another $\cdot 01''$ to allow for the small angle at the point of the tool, and a further $\cdot 01''$ for clearance, making in all $\cdot 125 + \cdot 01'' + \cdot 01'' = \cdot 145$. This amount, then, divided by the feed per revolution, which for the cross slide is $\cdot 002'' = 72$, which is the number of revolutions required for the working of the cross slides.

During this operation, however, the turret has indexed round to the stock stop position, that is, three indexings, and has also fed forward another length of metal, which means that to the previous numbers must be added another $\frac{1}{2}$ second or 14 revolutions.

Correcting the Number of Revolutions for the Higher Speed.—Though two speeds are employed in making the screw, all calculations when proportioning the cam are based on the fast speed. It is necessary, therefore, to increase the

number of revolutions of the slow-speed operations proportionately, which is done by using the simple formula—

$$R = \frac{H \times r}{L}$$

where R = Revolutions required,
r = Existing number of revolutions,
H = High-speed revolutions,
L = Low-speed revolutions.

ORDER OF OPERATIONS.

	R.P.M.	Corrected R.P.M.	Proportion of Cam Surface.
At 792 r.p.m.—			
Index turret and reverse spindle ..	10	14	5
Hollow mill ..	76	105	33
Index turret ..	10	14	5
Finish point (box tool)	27	37 + 2	12
Index turret ..	10	14	5
Thread on	15	21	7
At 1,087 r.p.m.—			
Run off die ..	15	15	5
Form. Index 3 times and cut off ..	72	72	23
Feed stock ..	14	14	5
		306 + 2	100

So that taking the operation of indexing the turret, etc., we have

$$\frac{1{,}087 \times 10}{792} = 14 \text{ revolutions approx.}$$

This method is followed out for all operations on the slow speed, and it will be seen by examining the order of operations that the total revolutions of all operations is 306.

Selecting Gears.—Having found the number of revolu-

tions necessary to make one piece, it is a simple matter to find the time per piece. With the spindle running at 1087 r.p.m., by proportion it will turn 18 times in one second and the 306 turns will be made in 17 seconds. With the machine for which these cams are intended, it has been arranged that the rate of motion of the cams controlling the various tools can be varied by altering a system of change gears, and to produce the piece in 17 seconds it is essential that gears having the correct number of teeth to give the required rate of motion must be selected.

The "Table for Laying Out Cams," No. 13, is similar to the one supplied with the machine, and to which reference must be made when selecting the gears.

Looking down the column headed "1,087 Revs.," it is found that the nearest "revolutions per piece" is 308, which gives on the extreme left 17 seconds per piece, and to the right of this number it will be seen that the gears necessary to give this result are a 20-toothed wheel on the driving shaft and a 34-toothed gear on the worm shaft.

It is only necessary then to adjust the original number of revolutions to meet this, which can be done by adding two to the operation, "Finish Point," making this 39 as indicated in the "Order of Operations."

Determining Cam Surface.—To convert the number of revolutions already calculated into a measure of cam surface, a circle equal to the diameter of the cam blank is drawn and its circumference is divided into one hundred equal parts. These hundred divisions represent then, in the case of the cam being designed, 308 revolutions of the machine spindle, so that one division equals $308 \div 100 = 3 \cdot 08$. If after dealing with each operation in this manner the total divisions exceed or are less than 100, a slight adjustment must be made to correct this. The number of divisions are indicated in the "Order of Operations."

Plotting the Cam.—The cam blanks are provided with a central hole to fit the shaft upon which they are located when in use and also with a hole $\frac{1}{4}''$ diameter which provides a positive drive for the cam and also fixes its position on the shaft.

These two holes and the zero point of the 100 divisions are on the same radial line, and it is from this line that the

No. 00 AUTOMATIC SCREW MACHINE.

TABLE FOR LAYING OUT CAMS.

TABLE No. 13.

SECONDS TO MAKE ONE PIECE.	GROSS PRODUCT - 10 HOURS.	NET PRODUCT - 10 HOURS. GROSS MINUS 10%.	GEARS ON DRIVING SHAFT.	1ST GEAR ON STUD.	2ND GEAR ON STUD.	GEAR ON WORM SHAFT.	HUNDREDTHS OF CAM SURFACE STRIKED STOCK.
3	12000	10800	70			21	17
4	9000	8100	50			20	13
5	7200	6400	60			30	10
6	6000	5400	50			30	9
7	5142	4600	60			42	8
8	4500	4000	60			48	7
9	4000	3600	60			54	6
10	3600	3200	40			40	5
11	3272	2900	40			44	5
12	3000	2700	40			45	5
13	2769	2500	40			52	4
14	2571	2300	30			42	4
15	2400	2100	40			60	4
16	2250	2000	30			48	4
17	2117	1900	20			34	3
18	2000	1800	30			54	3
19	1894	1700	20			38	3
20	1800	1600	20			40	3
21	1714	1500	20			42	3
22	1636	1450	20			44	3
23	1563	1400	20			46	3
24	1500	1350	20			48	3
25	1440	1300	20			50	3
26	1384	1250	20			52	3
27	1333	1200	20			54	3
28	1286	1150	20			56	3
29	1241	1100	20			58	3
30	1200	1050	20			60	3
32	1125	1000	30	30	48	60	3
34	1050	950	20	44	50	60	3
36	1000	900	30	30	54	60	3
38	947	850	20	30	38	60	3
40	900	800	20	30	40	60	3
42	857	775	20	30	42	60	3
44	818	725	20	30	44	60	3
46	782	700	20	30	46	60	3
48	750	675	20	30	48	60	3
50	720	650	20	30	50	60	3
52	692	620	20	30	52	60	3
54	666	600	20	30	54	60	3
56	642	575	20	30	56	60	3
58	620	550	20	30	58	60	3
60	600	525	30	21	54	70	3
63	571	500	30	20	54	70	3
70	514	450	20	20	40	70	3
77	467	420	20	20	44	70	3
84	428	385	20	20	48	70	3
91	395	355	20	20	52	70	3

* ONE WAY ONLY.

NUMBER OF REVOLUTIONS TO MAKE ONE PIECE.

MINUTES.	SECONDS.	1ST. SH	2ND SH. A	2ND SH. B	2ND SH. C
		3·5	4·1	4·8	5·6
		7	8·2	9·6	11·2
		420	492	576	675
3		21	25	29	34
4		25	33	38	45
5		35	41	48	56
6		42	49	58	67
7		49	57	67	79
8		56	66	77	90
9		63	74	86	101
10		70	82	96	112
11		77	90	106	124
12		84	98	115	135
13		91	107	125	146
14		98	115	134	157
15		105	123	144	169
16		112	131	154	180
17		119	139	163	191
18		126	148	173	202
19		133	156	182	214
20		140	164	192	224
21		147	172	202	236
22		154	180	211	247
23		161	189	221	259
24		168	197	230	270
25		175	205	240	281
26		182	213	250	292
27		189	221	259	304
28		196	230	269	315
29		203	238	278	326
30		210	246	288	337
32		224	262	307	360
34		238	279	326	383
36		252	295	346	405
38		266	312	365	428
40		280	328	384	450
42		294	344	403	473
44		308	361	422	495
46		322	377	442	518
48		336	394	461	540
50		350	410	480	563
52		364	426	499	585
54		378	443	518	608
56		392	459	538	630
58		406	476	557	653
60		420	492	576	675
63		441	517	605	709
70		490	574	672	788
77		539	631	739	866
84		588	689	806	945
91		637	746	874	1024

SPINDLE SPEEDS. BELT ON *A *B *C	480	492	576	675	792	927	1087	1273	1492	1748	2048	2400
480 1087	40	41	48	56	66	77	91	106	124	146	171	200
492 1273	41	42	49	57	67	79	93	109	127	149	175	205
576 1273 1492	48	49	58	67	79	93	109	127	149	174	204	239
675 1273 1492 1748	56	57	67	79	92	108	127	149	174	204	239	280
792 1492 1748 2048	66	66	77	90	106	124	145	170	199	233	273	320
927 1273 2048 2400	77	90	106	124	145	170	199	233	274	320	375	440
1087	84	98	115	135	158	185	217	253	298	350	410	480
1273	91	107	125	146	172	201	236	276	323	379	444	520
1492	98	115	134	157	185	216	254	297	348	408	478	560
1748	105	123	144	169	198	232	272	318	373	437	512	600
2048	112	131	154	180	211	247	290	339	398	466	546	640
2400	119	139	163	191	244	263	308	361	423	495	580	680
	126	148	173	202	238	278	326	382	448	524	614	720
	133	156	182	214	251	294	344	403	472	554	649	760
	140	164	192	224	264	309	362	424	497	583	683	800
	147	172	202	236	277	324	380	446	522	612	717	840
	154	180	211	247	290	340	399	467	547	641	751	880
	161	189	221	259	304	355	417	488	572	670	785	920
	168	197	230	270	317	371	435	509	597	699	819	960
	175	205	240	281	330	386	453	530	622	728	853	1000
	182	213	250	292	343	402	471	552	647	757	887	1040
	189	221	259	304	356	417	489	573	671	787	922	1080
	196	230	269	315	370	435	507	594	696	816	956	1120
	203	238	278	326	383	448	525	615	721	845	990	1160
	210	246	288	337	396	463	543	636	746	874	1024	1200
	224	262	307	360	422	494	580	679	796	932	1092	1280
	238	279	326	383	449	525	616	721	846	990	1161	1360
	252	295	346	405	475	556	652	764	895	1049	1229	1440
	266	312	365	428	502	587	688	806	945	1107	1297	1520
	280	328	384	450	528	618	724	849	995	1165	1365	1600
	294	344	403	473	554	649	761	891	1045	1224	1434	1680
	308	361	422	495	581	680	797	934	1094	1282	1502	1760
	322	377	442	518	607	711	833	976	1144	1340	1570	1840
	336	394	461	540	634	742	870	1018	1194	1398	1638	1920
	350	410	480	563	660	773	906	1061	1243	1457	1707	2000
	364	426	499	585	686	803	942	1103	1293	1515	1775	2080
	378	443	518	608	713	834	978	1146	1343	1573	1843	2160
	392	459	538	630	739	865	1015	1188	1393	1631	1911	2240
	406	476	557	653	766	896	1051	1231	1442	1690	1980	2320
	420	492	576	675	792	927	1087	1273	1492	1748	2048	2400
	441	517	605	709	832	973	1141	1337	1567	1835	2150	2500
	490	574	672	788	924	1082	1268	1485	1741	2039	2389	2800
	539	631	739	866	1016	1190	1395	1634	1915	2243	2628	3080
	588	689	806	945	1109	1298	1522	1782	2089	2447	2867	3360
	637	746	874	1024	1201	1406	1649	1931	2263	2651	3106	3640

spacing of the cam commences. Taking the operations as already laid out, the indexing and reversing take 5 hundredths, so that a radial line can be drawn at mark 5.

Leaving this space unmarked, the space for the turning operation with the hollow mill is measured off, which takes 33 divisions, and the radial line drawn at point 38. As it is the work of this cam to take the end working tools to their work and return them, it is obvious that the question of length of the tool and holder will have an effect on the position of the highest point of the cam in relation to the outer edge of the cam blank, the latter being $4\frac{1}{2}''$ diameter to suit the machine in question.

This point is made clear in the diagram Fig. 154, where the component is represented in position in the machine, and the turret slide is indicated at the extremity of its stroke, which leaves $1\frac{5}{8}''$ between it and the machine nose.

It is assumed that standard equipment or equipment of similar proportions is being used on the machine, because the position of the highest point is found by measuring off as shown, from the point on the component where any particular tool finishes back to the turret face. If the measurement extends past the turret face, it means that the highest point of the cam for that tool will be that amount from the outer edge of the blank.

Taking the hollow mill and the turning operation, it will be seen that the length of the mill in its holder, say $1\frac{1}{2}''$, measured from under the screw head, extends about $\frac{1}{4}''$ beyond the turret face. The highest part of the cam on the lobe for turning, therefore, will be $\frac{1}{4}''$ from the outside measured on the radial line number 38. Within the space enclosed by the lines 5 and 38 commencing from a point on the line 5 equal to $\frac{1}{4} + \cdot 750$, that is, the distance from the outside edge already fixed plus the amount of rise called for by the component, a curve is drawn having a uniform rise.

One way of securing this is to divide the space between the lines 5 and 38 into an equal number of parts, also the line 5, commencing at the start of the curve to a point $\frac{1}{4}''$ from the outer edge into a similar number. Through the latter, using the cam centre as a pivot, describe arcs, and through the former radial lines are drawn cutting the arcs, and through the points of intersection, the lobe for operating

the hollow mill is drawn. Fig. 152 will make this clear. Indexing the turret again occupies five divisions, another line being drawn at 43. From line 38, the turret must rotate



FIG. 151.—COMPONENT FOR WHICH CAMS FIGS. 153 AND 154 WERE DESIGNED.
FIG. 152.—LEAD CAM.
FIG. 154.—DIAGRAM SHOWING RELATION OF TOOLS TO TURRET AND MACHINE NOSE.

and recede for the next tool, which means that the roll on the actuating lever must drop from the high point on 38 to a position ready to rise for the next tool.

The line generally drawn for this drop is made tangential to the centre hole of the cam, and at the bottom of the drop, an arc is described equal in radius to that of the roller on the cam lever, and blending with the rising curve for the next tool at its commencing point. This point at which begins the curve for operating the box tool is determined in the manner already described, the length of the tool being $1\frac{3}{8}''$, which, it will be seen on examining the diagram, passes the turret face by $\frac{5}{8}''$.

The curve for the box tool will, therefore, commence on line 43 at a point $\frac{5}{8}'' + \frac{1}{4}''$ from the outside and rise to a point $\frac{5}{8}''$ from the outside on line 55, twelve divisions intervening. Another drop is now made for indexing the turret in a manner already described, reaching from line 55 to 60.

The lobe for controlling the die comes next for consideration, and in determining the amount of its rise a different method is followed to that for ordinary cutting tools.

This is generally arrived at by dividing the number of revolutions required for threading by the number of threads per inch to be cut, and then, as it is essential in the production of good threads that the die should be neither forced on nor torn from the work, an amount between 7 to 12 per cent. is usually deducted. Also when the lobe has been drawn, the high point is removed for about $\frac{1}{32}''$, which enables the die holder to draw out of its socket and finish up close to the screw head without the positive thrust of the cam.

With a component having 26 threads per inch and having found that 21 revolutions are required to run the die on, the rise will equal $21 \div 26 - 10$ per cent., say $\cdot 7$. Next, considering the room for the die holder as with previous tools, it will be found that $\frac{1}{4}''$ must be added to the $\cdot 7$ as the starting-point of the lobe, rising to within $\frac{1}{4}''$ of the outside of the cam blank. The curve for feeding the die to its work fills the space between lines 60 and 67 and for removing the die from the work between 67 and 72.

For threaded work of extreme accuracy the lobe must be very accurately drawn, taking into consideration the different speeds at which the die is run on and off the work, the relative position of the cam lever, and the number of threads per inch; for ordinary work, however, the method described will give satisfactory results.

After the threading operation the turret is indexed three times, during which time the form and cut-off tools on the cross slide come into operation. For this purpose the form of the cam after the threading lobe from line 72 consists of a portion of a circle, described with the centre of the cam as centre, and a radius of $1\frac{1}{8}''$, continuing for twenty-three divisions, thus ending at line 95.

The last five spaces of the cam are occupied by the lobe for feeding forward the stock in the machine. The top of this lobe is an arc concentric with the outside of the cam, forming what is known as a "dwell," that is, being concentric, or having no "rise," the tool it controls remains stationary during its passage. The stop for fixing the amount of metal to be fed forward is actuated by this lobe, and the distance from its top to the outside of the cam blank is determined in a similar manner to that for the previous tools. The stop, therefore, extending, say, 1″ from the end of the component, passes the turret face $\frac{1}{2}''$, which is the distance the arc must be described from the outer edge.

From point o a line is drawn tangential to the centre hole and blending with the turning lobe commencing at line 5 an arc is drawn to suit the cam lever roll. After printing on the cam the revolutions and the gears necessary for the benefit of the machine setter, the cam is finished.

The Back Slide Cam.—Only one large lobe is necessary on this cam, and as according to the lead cam just completed the cross slide operates at division 72 and extends twenty-three spaces, this area is marked off for the back slide cam. It was also figured when arriving at the revolutions necessary, that the travel of the cut-off tool was ·145″, so that the low point of the cam on line 72 will be that amount from the outer edge as shown in Fig. 153. The remainder of the cam surface is reduced concentrically, using a radius of $1\frac{1}{4}''$. The lines 72 and 93 are tangential to the centre hole, the former, however, having a slight radius as indicated, and both blending into the remaining portion of the cam.

Front Slide Cam.—As the form and cut-off tools operate simultaneously, line 72 is again used as a starting-point. To fix the amount of cam area, the number of hundredths must be first found, which is accomplished in a manner already described.

The travel of the form tool will equal the difference

between the radius of the screw head, Fig. 151, and the radius of the undercut portion, plus about ·01″ for clearance, equalling ·0625″ + ·01″, from which the revolutions and then the number of divisions can be figured.



FIG. 153.

CROSS SLIDE CAMS.

The low point of the cam, therefore, will be on line 72 and ·0725 from the outside and extending to line 84.

The last division on this cam is generally left unmachined and concentric, thus providing a "dwell" for the form tool which enables it to remove burrs thrown up by the front cut-off tool.

CHAPTER XII

SPECIAL EQUIPMENT

Truck Jig—Friction Screwdriver—Special Cut-Off and Forming Tool—Watertight Inlet Gland.

Though in offices employing a large number of men it is usual to grade them, certain men always dealing with one class of work, it is a big advantage for the designer to gain as wide an experience as possible so as to be in a position to deal with all types of equipment. To give some idea of the diversity of work which comes to the tool and jig draughtsman, several examples of what would be described as special equipment are mentioned in this chapter.

Truck Jig.—Fig. 155 shows a multiple-drilling operation on a cylinder block, the latter not being visible because it is located inside the body A of the movable or truck jig. This method of dealing with heavy components originated in America and enables a very high rate of production to be maintained, the truck passing to different machines where the necessary operations are performed. The component in Fig. 23, as already mentioned, could be easily handled in this manner, and the only disadvantage in the method being that the lines upon which the trucks run and the absence of machine tables make the machines inconvenient for working on any other component, should work slacken enough to allow of this. A fixture of this type needs to be very strong, and as the rails are fixed direct to the bed of the machine, there should be no difficulty in machining due to the truck not being square with the spindles.

To enable the drills to find and enter the drill bushes easily, a slight lateral float is allowed on the truck.

The jig plates B are located by means of the stud and latch C, and the handles D are provided to facilitate lifting the plates when removing the finished casting.

The body A revolves on two trunnions in the bearings E and the indexing and clamping levers are seen to the right,

while one hole for the indexing plunger is visible at *p*. The rails upon which the truck runs can be of standard section



FIG. 155.—"TRUCK" JIG BENEATH A MULTIPLE SPINDLE DRILLING MACHINE.

or of solid rod as in the illustration, specially designed "chairs" being designed to hold them. The body of the truck is revolved directly by means of the handle H, but

in some cases where the component is extra heavy a hand wheel with gearing is necessary.

The important point in the arrangement of the body casting is its balance, and when considering this the component itself as well as the jig plate must not be forgotten. Should the balance not be correct the jig becomes a danger to the operator, and to safeguard himself the designer should indicate on his drawing that the final balance is to be got by trial, that is, pieces of metal must be added or removed



Fig. 158.

Fig. 157.



Fig. 156.

Fig. 156.—friction screwdriver for assembly work.
Fig. 157.—special cut-off and forming tool.
Fig. 158.—component produced by fig. 157.

as is found necessary when the jig is completed, it being impossible to calculate this exactly.

Friction Screwdriver.—In a factory producing enormous quantities of cheap electrical accessories it was found that the greater part of the time spent on the assembly of the parts was taken in screwing in screws of varying lengths. The tool office was called upon to design something simple and cheap to get over this difficulty, and the idea in Fig. 156 resulted.

This can be made from brass or steel, though the former

will not stand the rough usage which is general in establishments employing unskilled labour. The shank A is held in the chuck of a drilling machine or lathe, while its other end, terminating in a boss B, is a sliding fit in the sleeve C and is retained there by means of the spring D, two lock nuts E and fibre washer F.

The nosepiece H, carrying a steel blade or screwdriver J, screws into the lower end of the sleeve C, and for special size screw heads another nosepiece must be made and kept by. The tool, gripped in the machine chuck, is brought down on to the screw head sending the screw down to its seat. When at this point the sleeve C, carrying the screwdriver, slips until raised by the operator. The tension of the spring D which controls the slip of the sleeve is adjusted by means of the two nuts E to suit tight- and loose-fitting screws.

Special Cut-Off and Forming Tool.—To produce the brass ring of unusual section shown at Fig. 158 a tool holder was designed and is seen in Fig. 157. The bar A is of mild steel, and upon it is arranged two circular form tools B and C, edge *d* of the former cutting off the finished ring. The brass tube E, from which the rings are made, is fed forward against the stop screw F, which is adjustable, and the tool C is moved forward forming the internal convex shape of the ring, after which B is fed in forming the outside and cutting off the finished ring.

Watertight Inlet Gland.—To force water into some hollow castings at a pressure of about 80 lb. to the square inch, the existing flange of the casting not being provided with any studs with which to secure a grip, proved a difficult proposition, especially as the operation had to be finished to time. The device illustrated in Fig. 159, where it is seen in position on the flange of a casting, successfully overcame this.

The two hook bolts A are a very close fit in the bush B. The latter is a watertight fit in the sleeve and nut C and D and resting on the top of the latter. To ensure the sleeve being watertight a groove *a* is turned into which is fitted some packing. The sleeve C beds down on to an india-rubber washer W, which should not be less than $\frac{3}{16}''$ thick because the surface of the casting X may be very rough.

The hose connection E passes down between the two hook

bolts. To remove the gland from its present position, the nut D is screwed down lower on the sleeve C, the handles J facilitating this, which allows bush B to be pressed down together with the bolts A. The latter can then be lifted



Fig. 159.

WATERTIGHT INLET GLAND.

slightly by means of the short levers L, which lay in shallow grooves made in the top of bush B and turned round so that the hook end of the bolts are in such position that the whole apparatus can be lifted off. The grooves M are so

placed as to remove guesswork, when the levers lay in one end of the grooves the hook bolts are in position under the casting, and when in the opposite end of the grooves the apparatus is ready for removal. It will be seen from Fig. 159 that as nut D is raised, the flange of the casting and the rubber washer are compressed between the sleeve C and the hook bolts A.

CHAPTER XIII

JIG AND TOOL OFFICE PROCEDURE

Personnel of a Jig and Tool Office—Duties of Jig and Tool Office—Method of Working—Detailing—Checking—Tracing—Filing and Recording—Alterations—Operation Sheets.

HOWEVER skilful a draughtsman may be, it is necessary that he should, to some extent, sink his individuality and work on the lines laid down for that particular office, in fact, though it may sound rather far-fetched, procedure must be practically standardized (see Chap. XIV).

Personnel of the Office.—A word is necessary first on the duties of the staff, which, of course, will vary according to the size and financial strength of the firm.

It is usual to employ a chief, who is responsible for the grade of the designs produced, the general conduct of the department, and also the cost of running. He may be supported by an assistant, or rely on section leaders, to whom he will give instructions, and who generally act as a kind of foreman between himself and the rest of the staff.

The section leaders are generally put in charge of a number of draughtsmen and "detailers," who probably specialize on one or more particular branches of jig and tool design.

"Detailers," whose work consists of taking the design or "General Arrangement"—abbreviated G.A.—and making separate drawings of the parts comprising it, are generally youths or apprentices working with the draughtsmen, more or less as assistants, and in working thus any hidden talent is quickly discovered.

The tracing section, now consisting entirely of females, has generally a leader who is responsible to the head of the office. Provided that there is enough work forthcoming, this section is a great success, as the work is admirably suited to female labour.

The printing department, where the Blue Prints—abbreviated B.P.—are produced, is also worked by female labour.

The introduction of electric printing machines, electric drying irons, etc., displacing the old cumbersome frames, has made this possible.

There remains a clerk and storekeeper, though this work is often carried out by one person. The duties consist of taking care of the stocks of drawing materials, and keeping the drawing and tracing filing system in order, a simple though very important duty.

Duties of the Jig and Tool Office.—It must not be assumed that all offices are conducted in the same manner, but a knowledge of one system will always act as a guide, and be helpful when encountering a new one. In some cases the jig and tool office acts as a "Planning Department," that is, it "lays out" the complete method of manufacture of the product in all details, and then proceeds to design and draw the necessary tools, etc.

Alternatively the chief draughtsman may receive a set of prints of the various components, comprising the finished article, together with a list giving the sequence of the operations, also indicating the particular machines on which they are to be carried out, the work is then divided between various draughtsmen, and in due course the designs are produced. Apart from new work, the machine shops are continually calling for replacements for wornout or broken equipment, and it is for the jig and tool office to supply the print, and also give the necessary orders.

If the tool in question has not been quite a success, the matter is investigated and improvements included in the new drawing.

Method of Working.—In developing an idea for a tool, jig or fixture, the designer relies on his past experience of similar work, and will probably recall some design that proved very successful. He may, by examining the record cards already referred to, find that equipment exists on the firm for another component of somewhat similar form, and then follow its design. If he has not met anything like this particular job in the past, he must exercise his ingenuity and apply his past workshop experience to devise something suitable, and submit this for approval in various stages as he proceeds.

Whatever he attempts he must remember that, while originality is always welcome, anything in the nature of a freak design should be avoided, as firms do not relish pet ideas being carried out at their expense.

It should be understood that where accepted methods of machining have given satisfaction, adhere to them, remembering that while your own ideas might be a decided improvement, they may not always be acceptable to those immediately above you.

When the much coveted chief's position has been gained, the time will be ripe to indulge in a judicious riot of ideas.

Detailing.—The "General Arrangement" of the fixture having been completed, and the idea approved, the drawing



FIG. 160.

RECORD FRAMES FOR VARIOUS DRAWINGS.

is passed to the "Detailer," who proceeds to dissect it and make separate drawings of each part.

To do this successfully, the "Detailer" must be able to thoroughly understand a mechanical drawing, and must also see that no part escapes his attention.

The various parts of the jig or fixture on the "General Arrangement" are numbered, and the detail drawings must bear corresponding numbers for purposes of reference.

The reference frames, Fig. 160, or similar, are finally added to the drawing and filled in, the one shown at A being for

the "General Arrangement," and that at B for the detail drawing. To the uninitiated this may seem superfluous, yet, while a drawing is intended to convey the ideas of the designer to the mechanic, it should also bear sufficient details of its past history to enable easy reference to be made. Various offices have their own pattern frames, there being some difference of opinion as to just what should be included in it.

The ones shown in Fig. 160, A and B, are an average type, and taking B first, the spaces require to be filled in as indicated with Reference Number, Scale, Date of Completion, also the Signature of the draughtsman, together with those of persons who approve and check it.

So as to know to which component the drawing refers the Component Number and Name is added, as also is the Operation Number (see Fig. 163), and the machine on which this is to be carried out.

To the left of this is the Number of the Sheet, and also the Total Number of Sheets, these numbers enabling anyone to know whether they are in possession of the complete set of details, and so prevent one item being overlooked.

Again, to the left is the Name and Number of the "General Arrangement" to which the detail belongs.

Above this is a column for Revisions or Alterations, as it is most important that these should be recorded, together with the date of revision.

A being for the "General Arrangement," would not need to carry so much information, and the filling in of this will be followed from what has been said concerning B. In some cases the form can be made less elaborate by including some of the references in the tool number, for example :—

2A, Component or Detail Number.

2A/4/B, Component or Detail Number, and G.A. Number.

2A/4B/10A, Detail Number, G.A. Number, and Tool Number.

On looking at the last number one can tell at once to which "G.A." the component or detail belongs, also the number of the tool used thereon, the letters indicating the particular drawer in which that size drawing is stored.

To maintain uniformity in the office the question of the different "fits" should be carefully watched, as a lot of

time can be wasted, both in the office and the shops, by allowing individuals a free hand.

A system such as that indicated in Chapter IX can be used with advantage, where it is only necessary to quote the fractional size of, say, the diameter of a hole, and then add the letter denoting the class of fit, then the tool room and machine shop, working on the same system, know just what is expected.

The questions of material and heat treatment are extremely important in tool and jig work, and it has been found of great advantage for all parties to mark the drawings for this in a recognized way.

At Fig. 161 is a useful symbol, consisting of a circle in which



FIG. 161

SYMBOLS FOR INDICATING HEAT TREATMENT.

is marked the material, with its grade or maker, and beneath that the necessary heat treatment.

One of those given indicates :—

Allen's Tool Steel. Hardened and ground.

and the other—

Mild Steel.—Pack hardened and ground.

To these symbols can be added, if considered advisable, depths of case hardening, and also scleroscope numbers.

Checking.—The detailing having been completed the drawings are passed to the checker, whose duty is to examine them carefully for faults and errors of all kinds.

Though he is not engaged for the purpose of criticizing, this forms part of his work. On receiving a drawing, then, the checker should also secure a drawing of the component for which the tool or jig was designed, and, better still, if one of the actual components are available.

Armed thus, he will examine the drawing from the point

of view of general construction, the design he will not interfere with, for it is assumed that it has already been approved by the chief of the department.

His line of thought will be as indicated below, though not necessarily in that order, and it will be at once obvious that the position calls for a man of experience.

1. In the case of jigs and fixtures—Can the loading and unloading be carried out quickly ?
2. Are the locating spots arranged at the most important and reliable points ?
3. Are the clamping arrangements satisfactory ?
4. Will they distort the component when in position ?
5. Will they allow the component to move when being machined ?
6. Will they take too long to manipulate ?
7. Will the operator have to think about it ?
8. Can any loose pieces, if they exist, be avoided ?
9. Is the machining thrust against the clamps ?
10. Is there plenty of "chip capacity," i.e. room for the escape of cuttings ?
11. Is there any allowance made for any variation in the shape of the component ?
12. Are all the details of the equipment to standard ?
13. In the case of a cutting tool—In proportioning its cutting edges, has the length of its life been considered ?
14. Has the correct heat treatment been called for ?
15. And generally are the various fits suitable for their duties ?
16. Have the proper methods of the office been followed ?
17. Are the various dimensions correct when totalled and compared with the overall dimension ?
18. Are there any unnecessary dimensions ?
19. Are all the details enumerated drawn ?
20. Is the material called for correct ?
21. Are the filing details correctly filled in ?

If an error is detected anywhere, it is indicated to the draughtsman, who corrects it, and when the checker is satisfied and adds his signature to the drawing to signify this, the drawing is ready for the tracing department.

Tracing.—Tracings which are essential, if blue prints

are wanted, are done on tracing cloth, though occasionally temporary rough tracings are made on paper.

This work is not at all difficult, requiring only common-sense, plus a pair of steady hands. To make a tracing the cloth is laid with the polished side to the drawing, and firmly pinned in position.

The pins should be pressed well home, so that the pinhead also helps to hold the cloth, failure to do this results in the cloth tearing slightly at the pins, thus altering the relation of the tracing to the drawing.

Next, starting at the top left-hand corner of the work, put in all the circular parts, using the ink compasses and bows for this purpose, and working always towards the right-hand lower corner, this will prevent any smearing.

This finished, the tee and set squares are employed to put in all the straight lines. This order of working has been found very satisfactory, for it is easier to make the lines blend in with the curves than vice versa.

Titles and large printed letters can be put in with the aid of stencils, of which a great variety of different sizes exist, so that after a little practice in their use no complaint should be possible on the score of neatness. Dimensions and small lettering must be inserted by hand. The tracer must not be tempted to put in lettering of her own design, but should cultivate the habit of following the drawing in strict detail, the slightest addition or omission sometimes causing serious trouble.

One of the best pens for handwork is the "Gillot" mapping pen, the flexibility of which is amazing, being capable of producing a line as fine as a hair to one so wide as to permit of it being easily measured.

If the surface of the cloth appears greasy, and the ink fails to flow, some french chalk dusted on, and then brushed off, will remedy this.

When a blot occurs it can be removed by immediately absorbing by means of blotting paper, the spot being then wiped with a damped cloth. Other than this, water, rain-spots, etc., must not be allowed to get on the tracings, neither must the latter be folded, because both the crease and the spots will appear on the print.

Filing and Recording.—The importance of keeping correct records cannot be overestimated, and while it is

not intended to deal with the subject here in detail, a few remarks are necessary. The extent to which indexing is carried depends on the class of management existing, some firms simply require a card to indicate that a certain tool or fixture has been made, together with the date, while others may call for minute details, even to the number of the final storage bin in the tool stores.

Fig. 162 shows an index card for location, that is to say, suppose an inquiry was made in the drawing office as to what drill jigs were in existence for component Number 9/B, an examination of the files for this part would perhaps reveal the fact that there were in stock two, Nos. 9/B/4/A and

COMPONENT							
OPERATION	TOOL NOS.						
TURNING							
DRILLING							
MILLING							
BORING							
PLANING							
GRINDING							

FIG. 162.

TOOL INDEX CARD.

9/B/2/A, and on looking in the drawer containing the "General Arrangements" size A, those of the jigs mentioned, should be there, from which, if necessary, the detail drawings could be traced.

It is fairly obvious then that waste time and muddle can be avoided by the judicious use of a filing system.

Alterations or Revisions.—Any alteration should be carefully recorded, and, of course, only the signatures of responsible persons are accepted for this.

The alteration is generally entered into a special book or index, and after the tracing has been corrected and the detail entered in the column under Revisions or Alterations,

the blue prints that may be in circulation are immediately recalled, and replaced by new ones.

Unless this part of the work is carried out efficiently, enormous losses can be sustained by work being machined to old drawings that were supposed to have been recalled.

It is also essential that people directly concerned should be notified of the change, because the habit is easily acquired of remembering dimensions without consulting a drawing, which, though very convenient, is equally dangerous

Operation Sheets.—As a guide to the available equipment for the operations on a component and the order of

OPERATION SHEET.

OP. NO.	DESCRIPTION.	JIG NO.	TOOL NO.	FIXTURE NO.	GAGE NO.	M/C NO.	REMARKS.

BOSTON ENG CO. BOSTON. LINCS. 3/6/21.

FIG. 163.

OPERATION SHEET.

their use, sheets are printed giving this, and are usually fixed to the component drawings issued to the shops.

The sheets are made out according to the "lay out" of the operations, and when the tools, etc., are designed and numbered they are entered on the sheet.

The sheets are made up, traced, blue prints are taken from them, and they are then ready for issue.

It is important that the order of operations should be correct, otherwise great trouble will result when attempts are made to follow the order given, both from the point of view of "progress" and accuracy of work.

Fig. 163 is an illustration of such a sheet.

CHAPTER XIV

STANDARDIZATION

The moment a single component or device is allowed to depart from the original standard, interchangeability commences to break down, and as the latter is the foundation of successful high production it must be prevented at all cost.

Most firms set up a standard of their own productions to assist manufacture and facilitate smooth working, also it enables them to supply new parts to customers without loss of time.

One can imagine the trouble caused by, say, an automobile built up with parts of varying dimensions and fits, which would necessitate the firm keeping a very accurate log book containing the shortcomings of each car, so that when a customer requires a certain part replaced the book would have to be scanned to see what there was peculiar to the part in question, whereas if a standard is maintained, the whole wheels of the business will move with increased freedom and give satisfaction to all concerned. The value of this is clearly demonstrated in the huge sales effected in this country of several types of American cars.

Standards are fixed for certain articles, which remain so throughout the world, such as screw threads, pipes, etc. For this country, however, a body of engineers, known as The British Engineering Standards Association, have fixed standards for a great variety of commodities, varying from tyres and wheel rims to filament lamps and fittings, and from rails and girders to broken stone and chippings. If, then, it is considered advisable to fix a standard for such items as broken stones, surely the tool designer must find it necessary to fix or work to existing standards in the office, and so facilitate not only the passage of designs through the department, but the final manufacture and upkeep of the commodity itself.

The man who introduced the ratchet stop for micrometers

standardized thumb pressure, because previously it was possible for any number of people to set the instrument to read differently.

Drill bushes, clamps, brackets, press bolsters and drawings themselves are, or can be, standardized with advantage, and the beginner is advised to give this his close attention. Fig. 164 shows a drill bush, and Table No. 14 gives a statement of its standard sizes, and it should be the duty of every draughtsman to work to that laid down in his particular office when called upon to design equipment containing bushes, and the far-seeing chief will see that this is done.



Fig. 165. Fig. 164.

Fig. 164.—drill bush.
Fig. 165.—reamer slip bush.

A reamer slip bush is also illustrated in Fig. 165, and Table No. 15 gives its general proportions.

The same holds good for the various fits necessary, and with an office containing a number of designers it is obvious what would happen if each one called for what he considered to be the correct allowance (see Chapter IX).

The walls of some jig and tool offices are hung with charts in large type, of the most important standardized parts, and there are also in existence several handbooks which give numerous other tables, so that it would appear more easy for the draughtsman to do right than wrong.

TABLE NO. 14.

DRILL BUSHES.

A.	B.	C.	D.	E.
In.	In.	In.	In.	In.
1/16	3/8	3/32	3/8	1/4
3/32	1 3/32	—	—	9/32
1/8	7/16	—	—	5/16
5/32	1/2	—	7/16	3/8
3/16	1 7/32	—	7/16	1 3/32
1/4	1 9/32	1/8	1/2	1 5/32
5/16	1 1/16	—	9/16	1/2
3/8	3/4	—	5/8	5/8
7/16	1 3/16	—	5/8	1 1/16
1/2	2 9/32	—	1 1/16	2 5/32
5/8	1 1/16	5/32	3/4	1 5/16
3/4	1 7/32	—	1 3/16	1 3/32
7/8	1 1 3/32	3/16	1	1 9/32
1	1 1/2	3/16	1	1 7/16

TABLE NO. 15.

REAMER BUSHES.

A.	B.	C.	D.	E.
In.	In.	In.	In.	In.
3/16	1 9/32	1/4	7/16	1 3/32
1/4	1 1/16	—	1/2	1 5/32
5/16	3/4	—	9/16	1/2
3/8	1	—	5/8	5/8
7/16	1	5/16	5/8	1 1/16
1/2	1 1/16	—	1 1/16	2 5/32
5/8	1 1/8	—	3/4	1 5/16
3/4	1 1/8	—	1 3/16	1 3/32
7/8	1 1/4	3/8	1	1 9/32
1	1 1/4	3/8	1	1 7/16

MACHINE CAPACITIES. MILLING M/CS.

TABLE No. 16.

TYPE.	FLOOR SPACE.	TABLE SURFACE.	TRAVEL	SPINDLE BORE.
CINCINNATI. Plain High Power. No. 2.	100 × 80⅝	46 × 12	28"	10 B&S.
" " " " 3.	113 × 84	52¾ × 12	34	" "
" " " " 4.	133 × 93⅝	65 × 14	42	11 "
" " " " 5.	152½ × 98½	75 × 16	50	" "
" " M/c. Hor. 12".	48 × 40	20 × 8	12	10 "
" Automatic. "	50 × 47	24 × 9¼	14	11 "
" " 24"	72 × 53	36 × 9¼	26	" "
" " 18"	60 × 53	30 × 9¼	20	" "
" High Power. Vert. No. 2.	94 × 83	47½ × 12	28	" "
" " " " " 3.	108½ × 86½	55¾ × 13½	34	" "
" " " " " 4.	126 × 97¼	64½ × 16½	42	12 "
" Automatic Duplex. Hor. 12"	50 × 53	24 × 9¼	14	11 "
" " " 18"	60 × 53	30 × 9¼	20	" "
" " " 24"	72 × 53	36 × 9¼	26	" "
LE BLOND. Plain. Hor. No. 0. (Ungeared.)	69 × 56	27¾ × 8½	18	9 "
" " " " 1 "	88 × 75	41½ × 10½	22	10 "
" " " " 0 HD. (geared)	69 × 56	27¾ × 8½	18	9 "
" " " " 1 " "	98 × 75	39½ × 11	22	10 "
" " " " 2 DC.	98 × 83	47½ × 12	28	" "
" " " " 2½ Two Ratio Double Friction Geared	98 × 81	47½ × 12	28	" "
" " " " 3	115 × 95	58½ × 13½	34	11 "
" " " " 3H.	115 × 95	58½ × 16	34	" "
" " " " 4	115 × 95	67 × 17½	42	" "
" " " 4H.	138 × 109	67 × 18	42	12 "
" Heavy. " 1½	88 × 72	41½ × 10½	24	10 "
" " " 2.	98 × 73	47½ × 11¾	28	" "
" " " 3	115 × 82	58½ × 13½	34	11 "
" " " 4	138 × 94	67 × 16¾	42	12 "
" " " 5	136 × 120	70 × 20	50	" "
MILWAUKEE. M/c. Hor. No. 1 A	81 × 67½	38⅝ × 9½	25	10 "
" " " " 1½ A	95 × 70¾	45½ × 11½	30	" "
" " " " 2 A	95½ × 79½	47 × 13	30	11 "
" Plain " " 1 B	81 × 67½	38⅝ × 9½	24	10 "
" " " " 1½ B	95 × 71¾	45½ × 11½	30	" "
" " " " 2 B	97½ × 79¼	47 × 13	30	11 "
" " " " 3	115 × 79¼	55 × 15	36	12 "
" Vert. " 1½ B	95 × 70¾	45½ × 11½	30	10 "
" " " 2½ B	84 × 11½	55 × 14	36	11 "
HERBERT. Hor. 16	102 × 96	55 × 13¾	34	" "
" " 22	14¼ × 126	68 × 17	48	12 "
" Vert. 16	102 × 81	55 × 13¾	34	11 "
" " 22	129 × 99	68 × 17	48	12 "

MACHINE CAPACITIES.
MILLING M/CS.

TABLE No. 16. CONTINUED

TYPE.		FLOOR SPACE.	TABLE SURFACE.	TRAVEL	SPINDLE BORE.
" " (Belt Drive)	No. 1.	94×69	39×10¼	30	9 "
" " " "	" 3.	96×78	45×12	36	10 "
" " " "	" 8.	139×144	85×19	62	15 "
GARVIN. (Plain Hor.)	" 11	36×38	21×4	12½	7 "
" " "	" 12.	47×38	30×7	18	10 "
" " "	" 13	60×52	37×7½	22	" "
" (Back Geat)	" "	" "	" "	24	" "
" (Mfg)	" 14	68×53	43½×9	28	" "
" (Plain)	" 15	75×53	42×12	42	" "
" " (60" Feed.)	" "	124×81	60×12	60	" "
" " (Geated.)	" 21	56×53	30×6	18	" "
" Vert	" 20	50×40	30×7	18	7 "
" " (Back Geat)	" 22	55×48	37×7½	24	" "
" " Planer Type,	" V14	72×48	48×20	48	" "
" " " "	" V15	106×75	60×25	60	" "
" DUPLEX.	" 2	74×74	40×8	24	11 "
" " 40"	" 3	92×90	42×12	40	" "
" " 60"	" 3	132×98	64×12	60	" "
BRIGGS. (Lincoln Type)	A	48×39½	24×8	16	" "
" " "	"	60×39½	30×8	22	" "
" " "	"	72×39½	36×8	28	" "
" " "	"	92×39½	46×8	38	" "
COULD EBERHARDT Vert Circular		64×33	23" DIA	360	" "

MACHINE CAPACITIES.

DRILLING MACHINES.

TABLE No. 16A.

TYPE.				TABLE SURFACE	SPINDLE BORE	VERTICAL FEED	SPINDLE TO TABLE	SPINDLE TO COLUMN
BARNES HP. ALL GEAR.			24"	20 DIA,	4 Morse	14"	30"	12¼"
" "			26"	23	5 "	"	40"	13
" "			22"	20 × 14	4 "	"	33	11
AVEY. (PILLAR)			No. 1	15×18	1 "	5	33½	6¼
" "			" 2.	16×20	2 "	6	35½	7½
CORONA. (SENSITIVE.)			12" " 1A	9×9	1 "	4	31½	6⅜
" "			13" " 2A	12 DIA.	1 "	5	36	6⅜
" M/c.			14" " 22A	16×12	2 "	5	35	7⅛
" "			13" " 2B	12 DIA.	2 "	5	36	6⅜
" "			13" " 2C	11×11	2 "	5	36	6⅜
" "			13" " 2D	11×11	1 "	5	36	6⅜
" "			25" " 2E	14×12	1" "	6	36	12⅝
" "			15" " 2P	18×12½	2 "	5	33	7⅜
" "			18" " 3A	15 DIA.	2 "	6	36	9⅜
" "			18" " 3B	15×15	2 "	6	35	9⅜
" (MULTIPLE)	2	SPINDLES	10. 12"	16×8	1 "	4	33½	6½
" "	3	"	10. "	22×8	1 "	4	33	6½
" "	4	"	1E. "	28×8	1 "	4	33	6½
" "	2	"	2G. 13"	20×12½	1 "	5	33	6⅝
" "	3	"	2H. 13"	28×12½	1 "	5	33	6⅝
" "	4	"	2K. 13"	36×12½	1 "	5	33	6⅝
" "	6	"	2L. 13"	52×12½	1 "	5	33	6⅝
" "	2	"	3C 18"	24×15	2 "	6	33	9⅜
" "	3	"	3D. 18"	34½×15	2 "	6	33	9⅜
" "	4	"	3E. 18"	45×15	2 "	6	33	9⅜
" "	6	"	3F. 18"	66×15	2 "	6	33	9⅜
" "	2	"	2R. 12"	16×8.	1 "	4	33½	6½
" (PILLAR)			20"	16½ DIA	1 "	8	32	10½
" (HEAVY)			20"	18 "	4 "	10	31	10¼
"			22"	20 "	4 "	10	32½	11½
"			24"	21½ "	4 "	12	35	12⅛
"			27"	24 "	5 "	12	32	13⅜
CINCINATTI. (PILLAR)			20"	15 "	2 "	4⅜	24¼	10
" "			20"	13×13	2 "	4⅜	"	"
" -BICKFORD.			24 - 36	28 DIA.	4 "	11	35⅜	18½
" " (HS.)			" "	" "	" "	"	"	"
" " (PILLAR)			21"	19 "	3 "	8 15/16	29¾	10¾
" "			24"	22 "	4 "	11	35⅜	12½
" "			23"	25 "	" "	12	37	14½
" "			32"	28 "	" "	13	39¼	16½
" "			36"	32 "	5 "	14½	39½	18½
" "			42"	36 "	" "	16	38¾	21½

MACHINE CAPACITIES.
DRILLING MACHINES.
TABLE No. 16A.
CONTINUED

TYPE.		TABLE SURFACE	SPINDLE BORE	VERTICAL FEED	SPINDLE TO TABLE	SPINDLE TO COLUMN.
HERCULES.	30"	23×23	" "	18	31	15
NATCO. (MULTIPLE SPINDLE)	No.11	20×30	1 TO 3	12	16	9
" " "	" 12	23×23		18¼	19½	12
" " "	" 13	17×25		28	30	15½
" " "	" 14	23×30		40	21	"
" " "	" 30	18×48		42	"	"
" " "	" 22	17×25		31	31	11½
" (STRAIT LINE)	" 39	20×40		16	"	14
BAKER.	" 314	17×23	No. 5	"	32	12¼
"	" 413	24×23	" 6	20	36	18
"	" 513	24×26	" "	18	45	"
HOEFER	21"	15¾ DIA	" 3	9¾	24	10⅝
"	23	18 "	" "	10¾	26½	11½
"	24	20 "	" "	11	24	12
"	26	22 "	" 4	13	25	13
"	28	24 "	" "	15	37	14½
"	32	27 "	" 5	16	45	16¼

The reader will remember that at the beginning of this work mention was made of the extent of the field open to the designer, or would-be designer of jigs, tools and equipment generally, and it is believed that this has been made apparent in the chapters that followed. If, then, this book should be the means of encouraging an enthusiastic one, the writer will feel that his object has been achieved.

INDEX

ABBREVIATIONS, 7
Accuracy, degree of, 17
Adaptable fixtures, 53
Adapters, die, 89
Adjustment of boring tools, 107
,, ,, button dies, 120
,, ,, hollow mills, 101
,, ,, tool posts, 82
Alignment, 86, 156
Allowance when forming shoulders, 92
Alterations, 178, 182
Angle, cutting, 90, 108, 121
Arrangements, general, 7, 8, 175, 177, 182
Automatic feed, value of, 49

BACK slide cam, 167
Balance, importance of, 171
Bending tools, 153
Bits, flat, proportions of, 111
Blank creases, 151
Blanks, formula for area, 152
,, shape of, 152
Blanking tools, 145
,, economy, 144
Blue prints, 175
Bolsters, 144
Bolts, method of drawing, 6
Bores, concentric, threading, 125
Boring bars, 109
,, cutters, special, 109
,, holders, 107, 111
,, tools, 107
,, tool adjustment, 107
,, tools, method of holding, 108
,, tool proportions, 108
Box tool, cutters for, 90
Brass, representation of, 3
Broach, blades, method of fitting, 118
Broaches, 117
,, allowances for wear, 118
Buffers, press, 151
Bushes, 86
,, drill, 45, 184
,, reamer, 45, 185
,, slip, 185
Button dies, 120
,, ,, adjustment of, 120
,, ,, hinged, 121

CALCULATIONS for dovetail tools, 93
Calculations for circular tools, 92
Cam surface, dividing, 162
Cams, Brown & Sharp, 158
,, cross slide, 158, 167
,, "lead" of, 158, 162
,, plotting, 162
,, "rise" of, 164
Capacity of machines, 52
Cards, index, 182
Cast iron, representation of, 3
Centre lines, 4, 8
,, ,, use of, 8
Chasing tools, 125
"Chatter," 90, 101, 104, 112, 127
Checker, duties of, 179
Checking, 179
Choice of machine, 52
Chip breakers, 98, 100, 111,
,, capacity, 38, 96, 180
Chucking reamers, 104
Chucks, magnetic, 35
,, pneumatic, 35
,, thread, 76
Circular tool holders, 82
,, form tools, 90, 172
Clamping, correct, 31
,, Distortion due to, 31
Clamps, screw, 32, 180
,, cam, 33, 180
Clearance, 90, 92, 93, 105, 108, 111, 117, 125, 127, 143, 160
Collets, extra capacity, 74
,, design of, 75
,, positive seating for, 76
,, spring, 74

Collet type tool holders, 85
Colours for representing materials, 4
Compressed air, employment of, 51
Continuous drilling, 49
,, milling, 64
Co-operation, value of, 21
Cored holes, difficulty of, 27
Corners, avoidance or, 98
Cost, considerations of, 16
Countersinks, 114
Counterbores, 112
Combination gauges, 138
,, press tools, 152
Cutters, boring, 109
,, ,, proportion of, 108
,, diameter of, 98
,, for box tools, 90
,, form relieved, 99
,, inserted tooth, 97
,, interlocking, use of, 62
,, roller milling, 95
,, spot-facing, 112
,, thread milling, 125
Cut-off tools, special, 172
Cutting edges, height of, 84, 91

DEPTH gauges, 134
Design, first considerations, 14
Design, over-elaboration of, 20
Detail drawings, 8, 36
Detailers, 175
Detailing, 177
Diameters, drilling, 23
,, effective, adjusting, 125
Die holders, 88
,, adapters, 89
Dies, adjustment of, 120
,, button, 119
,, drawing, 150
,, "follow," 149
,, forming, 154
,, hinged, 121
,, material for, 121
,, press, 143
,, re-drawing, 152
,, special, 154
,, spring, 121
,, taper for, 144
,, tempering of, 121
,, thickness of, 150
Dimensioning, correct method of, 4, 180
Dimension lines, 4
Distortion due to clamping, 31
Dotted lines, use of, 4
Double spindle machine, employing, 38
Dovetail tool holders, 82
,, ,, calculations, 93
"Drawback" motion, 71, 77
Drawbolts, 69
Drawing materials, 1
,, tools, 150
Drawings, tabular, 12
,, numbering of, 178
Draws, number required, 152
Drill bushes, 45
,, heads, multiple, 41
,, jig for pistons, 36
,, jig, indexing, 47
,, jigs, 23
Drilling, continuous, 49
,, horizontal, 37
Drills, necessity for supporting, 48
Duplicates, value of, 11
"Dwell," 167, 168

EBONITE, working in the press, 157
Effective diameter, varying, 125
Elevation, end, 8
,, sectional, 8
Embossing in the press, 153
End-working tool holders, 84
Engine pistons, drill jig for, 36
Equipment, special, 168
Expanding mandrels, 65, 70
Extra capacity collets, 74

FEEDS for Brown & Sharp cams, 158
Feet, for drill jigs, 40
Filing, 181
Fits, 44, 130, 149, 178, 185
Fixture for aluminium cover plate, 57
Fixtures, 14
,, adaptability of, 53
,, correct loading of, 55
,, foolproof, importance of, 58
,, for spot-facing, 116
,, indexing turning, 79
,, revolving precautions, 81
,, turning, 78
,, turning, with lateral movement, 81
,, "string," 55, 59, 62
Flat bits, 111
"Float," 87, 106, 108
"Floating" holders, 86
"Follow" dies, 149
Form relieved cutters, 99
,, tools, circular, 90, 172
,, ,, dovetail, 90
,, ,, diameter of, 92
,, ,, flat, 90
Friction screwdriver, 171
Front slide cam, 167

GANG tools, 144
Gauges, 128
Gauges, plug, 130
,, ,, renewable ends for, 131
,, caliper, 132
,, ,, forgings for, 132
,, combination, 138
,, depth, 134
,, ,, plug, 134
,, gap, 132
,, marking of, 132
,, material for, 140
,, plate depth, 134
,, plate plug, 131
,, ,, ,, proportions for, 132
,, plug pin, 131
,, position, 137
,, profile, 137
,, screw ring, 135
,, ,, thread, 135
,, snap, 132
,, scissor, 132
Gauging by comparison, 136
General arrangements, 7, 8, 175, 177, 182
Girder sections, employment of, 20
Gland, watertight, 172
Grinding in position, 76
Guides for press tools, 151

HEAT treatment, 179, 180
Holders, cross slide tool, 81
Holders, plain, 85
,, boring tool, 107
,, collet type, 85
,, die, 88
,, "floating," 86
Hollow mills, 100
,, ,, adjustment of, 101
,, ,, tempering of, 102
Horizontal drilling machines, 37

INDEXING, 182
Indexing milling fixtures, 65
Indexing drill jigs, 47
,, plungers, 47
,, turning fixtures, 79
Inlet gland, special, 172
Inserted teeth, 98
Interchangeability, 184
Interlocking cutters, use of, 62
Iron, cast, representation of, 3
,, wrought, representation of, 3

JIGS, 14
,, drill, 23
,, feet, 40
Jigs for pistons, 37
,, ,, double spindle machine, 38
,, indexing, 47
,, truck, 169

KEYSLOTS, 97
"Knockouts," press, 146, 153

LABOUR, considerations of, 17
"Land," 96, 104, 118, 120, 132
"Layout," 15, 183
"Lead" cams, 33, 162, 165
Lettering, method of, 6
Leverage, excessive danger of, 38, 57
Limits, 37, 128
Liners, use of, 45
Lines, centre, 4, 8
,, dimension, 4
,, dotted, 4
Location, correct, 24, 27, 180
,, "three point," 27, 68
Loose pieces, avoidance of, 40

MACHINE, choice of, 52
,, capacity, 52, 187, 188, 189, 190
Magnetic chucks, 35
Mandrels, 67
,, for cored work, 68
,, ,, expanding, 65, 70
,, ,, multiple turning, 67
,, ,, gear blanks, 69
,, ,, piston rings, 70
Materials, drawing, 1, 181
,, representation of, 3
,, for gauge making, 140, 179
,, ,, press tools, 157, 179
Milling, semi-continuous, 55
,, continuous, 64
,, cutters, thread, 125
,, fixtures, 52
,, fixture, indexing, 65
,, fixture for cover plate, 57
Mills, hollow, 100
,, ,, adjustment of, 101
,, ,, tempering of, 102
Motion study, 15
Multiple drill heads, 40
,, press tools, 144, 179

NON-ALIGNMENT, overcoming, 87
Numbering of drawings, 178
Nuts, method of drawing, 6

OBLIQUE projection, 12
Office, J. & T., duties of, 176
Operation sheets, 183
Operations for B. & S. cams, 161
Orthographic projection, 12

PADS, sketching, 10
Papers, drawing, 2
Pencils, correct sharpening of, 2
Personnel, office, 175
Pins, pilot, 113
,, ,, avoiding seizure of, 113
Pistons, drill jig for, 36
Plain holders, 85
Planning department, 176
Plate stripper, 144, 146
Plunger, indexing, 47
Plug gauges, 130
Pneumatic chucks, 35
Position gauges, 137, 138
Precautions for revolving fixtures, 81
Press tools, 142
,, ,, multiple, 144
Presses, sub, 155
Pressure rings, 151
Printing, method of, 6
Prints, blue, 174
Profile gauges, 137
,, maintenance of, 99
Progress, 16, 183
Projection, oblique, 12
,, orthographic, 12
Proportion when sketching, 10
,, of boring cutters, 108
Punches, method of holding, 144
,, providing support for, 144, 150
,, piloting, 150
" Push-through " dies, 150
" Push-out " mechanism, 72, 77

RAKE, 90, 100, 118, 121, 122
Reamers, 103
Reamers, expanding, 104
,, bushes, 45
,, fluting of, 103
,, rose, 104
,, special, 103, 105
Recess, gauging, 132
Recording, 181
Re-drawing, 152
References, 177
Releasing tap holders, 88
,, die holders, 88
Relief, 99, 105, 123
Replacement, allowing for, 89
Representation of materials, 3
Revisions, 178, 182
Ring gauges, 135
Rings, pressure, 151, 153
Rods, drilling through diameters of, 23
Running stops, 102

SCALE, useful form of, 2
Screw threads, method of drawing, 6, 184
Screwdriver, friction, 171
Section, part, 8
Sectional elevation, 8
Self-centring mechanisms, 25, 78
Serrations, 84, 92
Setting spots, 50
Shaving tools, 93
,, ,, clearance on, 94
Sheets, operation, 182
Shell taps, 124
Side clearance, 92
Sketching, value of, 10
,, pads, 11
Slots, key, 97
Special press tools, 154, 157
,, equipment, 168
Speeds for B. & S. cams, 158
Spiral teeth, 97
Spot-facing, 47, 59
,, cutters, 112
,, fixtures, 116
Spring collets, 74
,, dies, 121
,, tempering of, 121
Springs, 147
Standardization, 45, 184
Steel, representation of, 3
Stencils, 181
Stop screws for tool holders, 85
Stops, 147
,, running, 102
,, springs, 147
,, trigger, 147
Straddle milling, 53, 60
String fixtures, 55, 59, 62
Stripper plates, 144, 146
Sub presses, 154
Supports, 31
Symbols, heat treatment, 124, 179

TABULAR drawings, 12
Tap holders, releasing, 88
Taper, for dies, 144
Tapered plungers, advantage of, 47
Taps, 122
,, double, 125
,, ,, proportions for, 125
,, groove proportions, 123
,, shell, 124
Teeth cutter, 96

Teeth, spacing, 96
,, broach cutting allowance, 117, 118
,, ,, pitch of, 118
,, countersink, 114
,, hollow mill, 100
,, inserted, 98
,, method of fixing, 98, 99
,, spiral, 97
,, uneven spacing of, 104
Tenons, 59, 60
Thread chucks, 76
,, gauges, 135
,, milling cutters, 125
Threading concentric bores, 125
Threads, modifications of, 122
"Three point" location, 27
Timber, representation of, 3
Tool holders, circular, 82
,, ,, collet type, 85
,, ,, Cross slide, 81
,, ,, dovetail, 82
,, ,, end-working, 85
,, ,, plain, 85
,, steel section, 90, 91
Tools, flat form, 90
,, circular, 90
,, cut-off, special, 172,
,, dovetail, 90
,, shaving, 93
Tools, bending, 153
,, blanking, 145
,, boring, 107
,, chasing, 125
,, combination press, 152
,, drawing, 150
,, gang, 144
,, press, 142
,, press, materials for, 157
,, press multiple, 144
Tolerance, 128, 135
Tracing, 181
Trepanning tools, 116
,, ,, lead of, 116
Truck jigs, 181
Turning fixtures, 78

UNDERCUTS, 97, 111
"U" washer, use of, 40, 60

VEE blocks, 24, 29, 35, 78
Views, arrangement of, 8

WASHERS, "U," use of, 40, 44, 60
Watertight gland, 172
White metal, representation of, 3
Working drawings, method of procedure, 8
Wrought iron, representation of, 3

Printed in Great Britain by
UNWIN BROTHERS, LIMITED, THE GRESHAM PRESS, LONDON AND WOKING

WORKS BY

ERNEST PULL, A.M.I.Mech.E., Etc.

WORKSHOP SUPERINTENDENT LONDON COUNTY COUNCIL SCHOOL OF ENGINEERING, POPLAR, LONDON, E.

JUST PUBLISHED

Sixth Edition, Re-written and Greatly Enlarged. Large Crown 8vo, cloth. 690 *pp.* 542 *illus.* 16s. *net*

MODERN WORKSHOP PRACTICE

A comprehensive and practical book on Engineering Workshop Practice for Engineers, Apprentices and Students in Technical Institutes. Fitting and Turning, General Machining in all its Branches.

Royal 16mo, cloth. 170 *pp., Illustrated,* 3*s. net.*

ENGINEERING WORKSHOP HANDBOOK

An Indispensable Guide for Students in Engineering Classes, containing in simplified form all information necessary to assist them in qualifying as Skilled Workers.

Crown 8vo, cloth. 150 *pp., Illustrated.* 4*s.* 6*d. net*

ENGINEERS' MEASURING TOOLS

The Construction and use of Modern Tool-Room Appliances.

Crown 8vo, cloth. 88 *pp., Illustrated,* 2*s.* 6d. *net*

SCREW CUTTING FOR ENGINEERS

A Handbook for Practical Mechanics and Technical Students.

LONDON: CROSBY LOCKWOOD AND SON

A SHORT-TITLE LIST OF

SCIENTIFIC, TECHNICAL AND INDUSTRIAL BOOKS

(INCLUDING GENERAL EDUCATION)

PUBLISHED BY

CROSBY LOCKWOOD & SON

(C. M. LOCKWOOD)

7 STATIONERS' HALL COURT, LONDON, E.C. 4

Telegrams
CROSBY LOCKWOOD, CENT, LONDON

Telephone
4421 CENTRAL

POST FREE ON APPLICATION

COMPLETE DETAILED CATALOGUE

ALSO

LIST OF BOOKS IN ORIENTAL LANGUAGES

AND

PUBLICATIONS OF THE BRITISH ENGINEERING STANDARDS ASSOCIATION

NOTE.—*The prices herein quoted are subject to revision without notice*

JANUARY 1922

Civil Engineering Types and Devices. Barber. Demy 8vo . . 9s
Clerk of Works. Metson. Crown 8vo 3s 6d
Clock Repairing and Making. Garrard. Crown 8vo 6s
Coal and Iron Industries of the United Kingdom. Meade. 8vo £1 8s
Coal Mining. Glover. Crown 8vo 2s
Coal Mining, Practical. Cockin. Crown 8vo 6s 6d
Coal Mining Notes and Formulæ for Students. Merivale. Small Crown 8vo 3s 6d
Cocoanut Cultivation. Coghlan and Hinchley. Sm. Crown 8vo . 4s
Coffee : Cultivation and Preparation. Ugarte . . *In Preparation*
Coking Practice. Byrom and Christopher—
Volume I. **Raw Materials and Coke.** Demy 8vo . . 10s 6d
Volume II. **By-Products.** Demy 8vo 10s 6d
Colliery Working and Management. Bulman and Redmayne. Medium 8vo . . . . . *New Ed. Preparing*
Commerce, Lessons in. Gambaro. Crown 8vo 5s
Commercial Correspondent, Foreign. Baker. Crown 8vo . . 7s 6d
Compressed Air Work and Diving. Boycott. Medium 8vo . 10s 6d
Concrete : its Nature and Uses. Sutcliffe. Crown 8vo . . 10s 6d
Concrete for House, Farm, and Estate. Ballard. Demy 8vo . 3s 6d
Confectioner, Modern Flour. Wells. Crown 8vo 2s
Confectionery, Ornamental. Wells. Crown 8vo 7s 6d
Continuous Railway Brakes. Reynolds. 8vo 9s
Controllers for Electric Motors. James. Demy 8vo 21s
Creation, The Twin Records of. Le Vaux. 8vo 5s
Curves, Tables of Tangential Angles and Multiples. Beazeley . . 5s
Dairying (British and Colonial). Sutherland Thomson. Demy 8vo 9s
Dairying Industry. Sutherland Thomson. Demy 8vo . . 10s 6d
Dairying : Milk, Cheese and Butter. Oliver. Crown 8vo *New Ed. Preparing*
Dangerous Goods. Phillips. Crown 8vo 10s 6d
Decorator's Assistant. Small Crown 8vo 2s 6d
Deep-Level Mines of the Rand. Denny. Royal 8vo 25s
Dentistry (Mechanical). Hunter. Crown 8vo 6s
Diesel or Slow-Combustion Oil Engine, Wells & Wallis-Tayler. 8vo 10s 6d
Drawing. Pyne. 4to 8s 6d
Dredges and Dredging. Prelini. Royal 8vo 24s
Drilling for Gold and Other Minerals. Denny. Medium 8vo . 12s 6d
Dynamic Electricity and Magnetism. Atkinson. Crown 8vo . . 12s
Dynamics (Notes on). Thomas. Demy 8vo 6s
Dynamo (How to Make). Crofts. Crown 8vo 2s 6d
Dynamo, Motor, and Switchboard Circuits. Bowker. Medium 8vo 9s
Dynamos (Alternating and Direct Current). Sewell. Lge. Cr. 8vo 8s 6d
Dynamos (Management of). Lummis-Paterson. Crown 8vo . . 6s
Earthenware, The Manufacture of. Sandeman. Crown 8vo . . 12s
Earthwork Diagrams. Erskine-Murray and Kirton. 5s ; mounted, 7s 6d
Earthwork Manual. Graham. 18mo 3s 6d

All Published Prices are net.

Earthwork Tables. Broadbent and Campin. Crown 8vo . . . **6s**
Earthwork Tables. Buck. On a sheet **3s 6d**
Electric Light. Urquhart. Crown 8vo **7s 6d**
Electric Light Fitting. Urquhart. Crown 8vo **6s**
Electric Light for Country Houses. Knight. Crown 8vo . . **1s 6d**
Electric Lighting and Starting for Motor Cars. Cross *New Ed. Preparing*
Electric Lighting and Heating. Walker. Fcap. 8vo **5s**
Electric Motors. Crocker and Arendt. Medium 8vo **21s**
Electric Power Stations. Klingenberg. Crown 4to **28s**
Electric Ship-Lighting. Urquhart. Crown 8vo **8s 6d**
Electric Spark Ignition in Internal Combustion Engines. Morgan. Medium 8vo **8s 6d**
Electric Traction and Transmission Engineering. Sheldon and Hausmann. Large Crown 8vo **21s**
Electric Wiring Diagrams and Switchboards. Harrison. Crown 8vo . **15s**
Electrical Calculations (Elementary). Sloane. Crown 8vo . . **15s**
Electrical Dictionary. Sloane. Large Crown 8vo **21s**
Electrical Engineering (Elementary). Alexander. Crown 8vo . . **5s**
Electrical Engineering. Sewell. Large Crown 8vo . . . **8s 6d**
Electrical Installation Work. Havelock. Demy 8vo **15s**
Electrical Transmission of Energy. Abbott. Royal 8vo . . . **30s**
Electrical Transmission of Energy—Three-Phase Transmission. Brew. Demy 8vo **9s**
Electrical and Magnetic Calculations. Atkinson. Crown 8vo . . **12s**
Electricity as Applied to Mining. Lupton. Medium 8vo . . **12s 6d**
Electricity in Factories and Workshops. Haslam. Large Cr. 8vo . **8s 6d**
Electro-Plating. Urquhart. Crown 8vo **7s 6d**
Electro-Plating. Watt. Crown 8vo **5s**
Electro-Plating and Electro-Refining of Metals. Watt and Philip. Large Crown 8vo **15s**
Electro-Typing. Urquhart. Crown 8vo **5s**
Embroiderer's Book of Design. Delamotte. Oblong 8vo . . . **3s**
Engineering Chemistry. Phillips. Crown 8vo . *New Ed. Preparing*
Engineering Drawing. Maxton and Malden. Crown 8vo . **8s 6d**
Engineering Estimates, Costs, & Accounts. A General Manager. 8vo **9s**
Engineering Progress (1863–6). Humber. Imperial 4to, half morocco . . . . Price **£12 12s**; each volume, **£3 3s**
Engineering Workshop Handbook. Pull. Royal 16mo . . . **3s**
Engineer's Handbook (Practical). Hutton. Medium 8vo . . . **21s**
Engineer's Measuring Tools. Pull. Crown 8vo **4s 6d**
Engineer's, Mechanic's, Architect's, Builder's, &c., Tables and Memoranda. Smith. Waistcoat-pocket size *New Ed. Preparing*
Engineer's and Millwright's Assistant. Templeton. 18mo . . **3s**
Engineer's Year-Book. Kempe. Crown 8vo . . *Annually* **30s**
Engineering Standards Association's Reports and Specifications.
Separate List on Application

All Published Prices are net.

Engineman's Pocket Companion. Reynolds. Royal 18mo . **3s 6d**
English Literature, A Handbook of. Dobson. Crown 8vo . . **5s**
Entropy as a Tangible Conception. Wheeler. Demy 8vo . **8s 6d**
Excavation (Earth and Rock). Prelini. Royal 8vo **21s**
Explosives—High Explosives. Colver. Royal 8vo . . . **£3 3s**
Explosives—Nitro-Explosives. Sanford. Demy 8vo **12s**
Factory Accounts. Garcké and Fells. Demy 8vo . *Nearly Ready*
Farm Account Book. Woodman. Folio **10s 6d**
Farm Gas Engines. Brate. Crown 8vo. **6s 6d**
Farmers' Tables and Memoranda. Francis. Waistcoat-pocket size **2s 6d**
Farmers' Labour and Account Book. Saxby. Fcap. Folio . . **6s**
Farming, Practical. Shepherd. Demy 8vo **5s**
Fertilisers and Feeding Stuffs. Dyer. . . . *New Ed. Preparing*
Fertilizing Materials, Mining and Manufacture. Lloyd. Crown 8vo **12s**
Fire Protection in Buildings. Holt. Demy 8vo **9s**
Forcing Garden. Wood. Crown 8vo **4s**
Foreshores. Latham. Crown 8vo **2s 6d**
Forestry, Practical. Curtis. Crown 8vo **6s**
Forestry : Complete Yield Tables for. Maw. Oblong . . **7s 6d**
French Conversation, Guide to. De Fivas. 32mo . . . **2s 6d**
French Grammar : De Fivas' New Grammar of French Grammars **2s 6d**
Key to the Above **3s 6d**
French Grammar, Elementary. De Fivas. Crown 8vo . . **1s 6d**
French Language : Introduction. De Fivas. Crown 8vo . . **2s 6d**
Fretcutting, The Art of Modern. Makinson. Crown 8vo . . **2s 6d**
Founders' Manual. Payne. Crown 8vo. **24s**
Gas Engine, A Handbook on the. Haeder and Huskisson. 4to . **30s**
Gas Engine Handbook. Roberts. Crown 8vo **12s 6d**
Gas Engineers' Pocket-Book. O'Connor. Crown 8vo. . . **12s 6d**
Gas Manufacture, Chemistry of. Royle. Demy 8vo . . . **16s**
Gas and Oil Engine Management. Bale. Crown 8vo . . **3s 6d**
Gasfitting and Appliances. Briggs and Henwood. Crown 8vo . **6s**
Geometry of Compasses. Byrne. Crown 8vo **3s 6d**
Geometry for Technical Students. Sprague. Crown 8vo . . . **2s**
Gold Extraction, Cyanide Process of. Eissler. 8vo . . . **8s 6d**
Gold, Metallurgy of. Eissler. Medium 8vo **25s**
Gold Mining Machinery. Tinney. Medium 8vo **12s 6d**
Gold Working : Jeweller's Assistant. Gee. Crown 8vo . . **8s 6d**
Goldsmith's Handbook. Gee. Crown 8vo . . . . *Nearly Ready*
Granites and our Granite Industries. Harris. Crown 8vo. . . **3s**
Grazing. The Complete Grazier, and Farmer's and Cattle Breeder's Assistant. Youatt, Fream and Bear. Royal 8vo . . . **36s**
Hand Sketching for Mining Students. Lodge and Harwood. Oblong Demy 4to **10s 6d**

All Published Prices are net.

Handybooks for Handicrafts. Hasluck. Crown 8vo.
- **Metal Turner's Handybook** **1s 6d**
- **Wood Turner's Handybook** **1s 6d**
- **Watch Jobber's Handybook** **1s 6d**
- **Pattern Maker's Handybook** **1s 6d**
- **Mechanic's Workshop Handybook** **1s 6d**
- **Model Engineer's Handybook** **1s 6d**
- **Clock Jobber's Handybook** **1s 6d**
- **Cabinet Worker's Handybook** **1s 6d**
- **Woodworker's Handybook** **1s 6d**

Heat, Expansion of Structures by. Keily. Crown 8vo . . . **4s**

History : Mediæval Heresy and the Inquisition. Turberville. Demy 8vo **10s 6d**

History : The Influence of the French Revolution in English History. Brown. Demy 8vo **8s 6d**

History : The Wars of the Roses, 1377–1471. Mowat. Demy 8vo **7s 6d**

Hoisting Machinery. Horner. Crown 8vo **8s 6d**

Horticultural Note-Book. Newsham. Fcap. 8vo **7s 6d**

Hot Water and Steam Heating and Ventilation. King. Med. 8vo . **21s**

House Owner's Estimator. Simon. Crown 8vo **4s**

House Painting. Davidson. Crown 8vo **7s 6d**

House Planning—How to Plan a House. Samson. Crown 8vo . **6s**

House Property. Tarbuck. 12mo **7s 6d**

Houses, Villas, Cottages, and Bungalows for Britishers and Americans Abroad. Samson. Demy 8vo **7s 6d**

Hydraulic Power Engineering. Croydon Marks. 8vo . . . **12s 6d**

Hydrostatics and Pneumatics, Handbook of. Lardner. Post 8vo . **5s**

Illuminating and Missal Painting. Whithard. Crown 8vo . . **6s**

Illumination, Art of. Delamotte. Small 4to **7s 6d**

Inflammable Gas and Vapour in the Air. Clowes. Crown 8vo . **6s**

Interest Calculator. Campbell. Crown 8vo **3s**

Internal Combustion Engines. Carpenter. Medium 8vo . . . **38s**

Inwood's Tables for Purchasing Estates. Schooling. Demy 8vo . **9s**

Iron and Metal Trades Companion. Downie **9s**

Iron and Steel Girders (Graphic Table for Computation of Weights). Watson Buck. On a sheet **2s 6d**

Iron Ores of Great Britain and Ireland. Kendall. Crown 8vo . **18s**

Iron-Plate Weight Tables. Burlinson and Simpson. 4to . . . **25s**

Irrigation (Pioneer). Mawson. Demy 8vo **12s 6d**

Jigs and Tools (Drawing and Design). Gates . . . *Nearly Ready*

Journalism. Mackie. Crown 8vo **2s 6d**

Labour Disputes, Conciliation and Arbitration in. Jeans. Crown 8vo **2s 6d**

Land Valuer's Assistant. Hudson. Royal 32mo **4s 6d**

Lathe Design, Construction, and Operation. Perrigo. Med. 8vo . **18s**

Lathe Work. Hasluck. Crown 8vo **6s**

Law : Every Man's Own Lawyer. Barrister. Large Crown 8vo . **15s**

All Published Prices are net.

Lead, Metallurgy of. Eissler. Crown 8vo **15s**
Leather Chemistry. Harvey. Demy 8vo **15s**
Leather Manufacture. Watt. 8vo **15s**
Letter Painting. Badenock and Prior. Crown 8vo **2s**
Levelling, Principles and Practice of. Simms. 8vo **9s**
Lightning Conductors, Modern. Hedges. Medium 8vo . . . **8s**
Limes and Cements. Dancaster. Large Crown 8vo . . . **7s 6s**
Liquid Fuels for Internal Combustion Engines. Moore. Demy 8vo **15s**
Lockwood's Builder's Price Book. Crown 8vo . . *Annually* **7s 6d**
Locomotive Engine. Weatherburn. Crown 8vo **3s 6d**
Locomotive Engine Development. Stretton. Crown 8vo . . . **5s**
Machine Shop Tools. Van Dervoort. Medium 8vo **28s**
Magnetos for Automobilists. Bottone. Crown 8vo . . . **2s 6d**
Marble and Marble Working. Renwick. Medium 8vo . . . **16s**
Marble Decoration. Blagrove. Crown 8vo **4s**
Marine Engineer's Guide. Wannan and Lindsay. Lge. Crown 8vo. In 2 vols.
Arithmetic . . . . . *New Ed. Preparing*
Elementary's, Verbals, and Drawings . . *New Ed. Preparing*
Marine Engineer's Pocket-Book. Wannan. 18mo . . . **7s 6d**
Marine Engines and Boilers. Bauer. Medium 8vo **25s**
Marine Gas Engines. Clark. Crown 8vo **10s 6d**
Marine Steam Turbines. Bauer. Medium 8vo **12s 6d**
Masonry. Purchase. Royal 8vo **9s**
Masonry Dams from Inception to Completion. Courtney. 8vo **10s 6d**
Measures (British and American). Foley. Folio . . . **8s 6d**
Measuring and Valuing Artificer's Work. Dobson and Tarn. Crown 8vo **8s 6d**
Mechanical Engineering Terms (Lockwood's Dictionary of). Horner. Crown 8vo **9s**
Mechanical Engineer's Pocket-Book. Clark and Powles. Small 8vo **7s 6d**
Mechanical Handling and Storing of Material. Zimmer. Royal 8vo . . . . . *New Ed. Nearly Ready*
Mechanics Condensed. Hughes. Crown 8vo. **2s 6d**
Mechanics of Air Machinery. Weisbach. Royal 8vo. . . . **25s**
Mechanics' Workshop Companion. Templeton & Hutton. Fcp. 8vo **7s 6d**
Mensuration and Gauging. Mant. 18mo **4s**
Metal Plate Work (Principles and Processes). Barrett. Crown 8vo **3s 6d**
Metal-Turning. Horner. Large Crown 8vo **12s 6d**
Metrology, Modern. Jackson. Large Crown 8vo . . . **12s 6d**
Military Observation Balloons. Widmer. Crown 8vo . . . **16s**
Milk and Cream Testing. Thomson and Lowe . *New Ed. Preparing*
Milling Machines. Horner. Medium 8vo **15s**
Mine Drainage. Michell. Royal 8vo **25s**
Mine Rescue Work and Organization. Bulman and Mills. Demy 8vo **12s**
Mine Wagon and its Lubrication. Pamely. Medium 8vo. . **7s 6d**

All Published Prices are net.

Mineral Property, The Valuation of. O'Donahue. Demy 8vo **8s 6d**
Minerals and Mining (Earthy). Davies. Crown 8vo . . . **12s 6d**
Minerals and Mining (Metalliferous). Davies. Large Crown 8vo **12s 6d**
Miners and Metallurgists, Pocket-Book for. Power. Fcap. 8vo . **7s 6d**
Miner's Handbook. Milne. Fcap. 8vo **7s 6d**
Mining, British. Hunt. Super Royal 8vo **42s**
Mining Calculations. O'Donahue. Crown 8vo **4s 6d**
Mining Examination Questions (1,200), Kerr. Demy 8vo . **2s 6d**
Mining, Physics and Chemistry of. Byrom. Crown 8vo . . . **6s**
Mining : Machinery for Metalliferous Mines. Davies. Medium 8vo **25s**
Motor Car Catechism. Knight. Crown 8vo **3s 6d**
Motor Car Construction. Brewer. Demy 8vo **9s**
Motor Cycle Overhauling. Shepherd. Crown 8vo . . . **2s 6d**
Motor Lorry Design Construction. Schaefer. Medium 8vo . . **18s**
Motor Vehicles. Fraser and Jones. Medium 8vo **16s**
Museum of Science and Art. Lardner **21s**
Naval Architect's and Shipbuilder's Pocket-Book. Mackrow and Woollard. Fcap. 8vo **16s**
Oils and Allied Substances. Wright. Demy 8vo *New Ed. Preparing*
Oil-Field Development and Petroleum Mining. Thompson do.
Oil Palm Cultivation. Milligan. Small Crown 8vo **3s**
Ore Deposits of South Africa. Johnson.
Part II.—The Witwatersrand and Pilgrimsrest Goldfields and Similar Occurrences. Demy 8vo **5s**
Packing-Case Tables. Richardson. Oblong 4to **5s**
Paints : Their Chemistry and Technology. Toch. Royal 8vo . . **30s**
Paper and its Uses. Dawe. Crown 8vo **8s 6d**
Paper-Making. Clapperton. Crown 8vo **7s 6d**
Paper-Making. Watt. Crown 8vo **8s 6d**
Paper-Making, Chapters on. Beadle. 5 vols. Crown 8vo. Per vol. **6s**
Pastrycook and Confectioner's Guide. Wells. Crown 8vo . . . **2s**
Patent-Rights. Hardingham. Demy 8vo . . *New Ed. Preparing*
Pattern Making. Barrows. Crown 8vo **14s**
Pattern Making. Horner. Large Crown 8vo **9s**
Petrol Air Gas. O'Connor. Crown 8vo **2s 6d**
Petroleum and its Substitutes, Chemistry of. Tinkler and Challenger. Medium 8vo **15s**
Petroleum, Oil Fields of Russia and the Russian Petroleum Industry. Beeby Thompson. Royal 8vo **21s**
Pigments. An Artists' Manual. Standage. Crown 8vo . . . **3s**
Portland Cement Industry. Brown. Medium 8vo *New Ed. Preparing*
Portland Cement, The Modern Manufacture of. West. Royal 8vo. In 2 volumes . . . . . *New Ed. Preparing*
Poultry Farming : Commercial. Toovey. Crown 8vo *New Ed. Preparing*
Producer Gas Practice (American) and Industrial Gas Engineering. Latta. Demy 4to **30s**

All Published Prices are net.

Propagation and Pruning. Newsham. Demy 8vo . . . **7s 6d**
Prospecting. Merritt. Fcap. 8vo **6s**
Prospecting for Gold. Rankin. Fcap. 8vo **7s 6d**
Prospector's Handbook. Anderson. Small Crown 8vo . . . **5s**
Pumps and Pumping. Bale. Crown 8vo **5s**
Punches, Dies, and Tools. Woodworth. Medium 8vo . . . **28s**
Radiodynamics. Miessner. Crown 8vo **12s**
Radiotelegraphy, Elements of, Stone. Crown 8vo . . . **16s 6d**
Rating and Assessment. Webb. Demy 8vo. **8s 6d**
Receipts, Formulas, and Processes. Hiscox. Medium 8vo . . **21s**
Recoil of Guns. Rausenberger. Translated by Slater. Demy 8vo **12s 6d**
Refrigerating and Ice-Making Pocket-Book. Wallis-Tayler. Cr. 8vo **5s**
Refrigeration, Cold Storage, and Ice-Making. Wallis-Tayler. Med. 8vo **15s**
Reinforced Concrete Design Simplified. Gammon & Dyson. Crown 4to **15s**
Road Construction and Maintenance. Goldsmith. Medium 8vo . **21s**
Roads : The Making of Highroads. Carey. Crown 8vo . . **3s 6d**
Rothamsted Experiments. Tipper. Crown 8vo **4s**
Rubber : its Cultivation and Preparation. Johnson. *New Ed. Preparing*
Rubber Hand Stamps. Sloane. Square 8vo **7s 6d**
Rubber Planter's Note-Book. Braham. Fcap. 8vo **5s**
Safe Railway Working. Stretton. Crown 8vo **4s 6d**
Safe Use of Steam. By an Engineer **6d**
Sailmaking. Sadler. 4to **12s 6d**
Sanitation, Water Supply, and Sewage Disposal of Country Houses. Gerhard. Crown 8vo **15s**
Savouries and Sweets. Miss Allen. Fcap. 8vo **1s 6d**
Saw Mills. Bale. Crown 8vo **10s 6d**
Screw Cutting for Engineers. Pull. Crown 8vo **2s 6d**
Screw Threads. Hasluck. Waistcoat-pocket size **2s**
Sea Terms, Phrases, and Words. Pirrie. Fcap. 8vo . . . **7s 6d**
Sewage, Purification of. Barwise. Demy 8vo **12s 6d**
Sewerage of Sea Coast Towns. Adams. Demy 8vo **6s**
Sewerage Systems. Watson and Herbert. Royal 8vo . . **12s 6d**
Sheet Metal Worker's Instructor. Warn and Horner. Crown 8vo **8s 6d**
Shipbuilding Industry of Germany. Felskowski. Super Royal 4to **10s 6d**
Silver. The Metallurgy of. Eissler. Crown 8vo **12s 6d**
Slide Rule. Hoare. Sm. Crown 8vo **4s**
Smoley's Tables—1. Logarithms and Squares. **27s**
2. Slopes and Rises **24s**
3. Logarithmic-Trigonometric Tables . . . **6s**
Soap : The Modern Soap Industry. Martin . . . *In Preparation*
Soap-Making. Watt. Crown 8vo **9s**
Soaps, Candles, and Glycerine. Lamborn. Medium 8vo . . . **54s**
Solubilities of Inorganic and Organic Substances. Seidell. Med. 8vo **45s**
Spanish Grammar and Reader. Korth. Fcap. 8vo . . . **2s 6d**
Specification in Detail. Macey and Allen. Royal 8vo *Nearly Ready*

All Published Prices are net.

Specification, A Short. Cubitt. Oblong Demy 4to . . . **2s 6d**
Specifications for Practical Architecture. Bartholomew. Revised by Rogers. 8vo **16s**
Stanley, William Ford : His Life and Work. Inwards. Demy 8vo **2s 6d**
Stationary Engines. Hurst. Crown 8vo **2s**
Steam : The Application of Highly Superheated Steam to Locomotives. Garbe. Edited by Robertson. Medium 8vo . . **9s**
Steam Engine. Haeder and Powles. Crown 8vo . . . **10s 6d**
Steam Engine. Goodeve. Crown 8vo **6s 6d**
Steam Engine (Portable). Wansbrough. Demy 8vo **6s**
Steam Engineering in Theory and Practice. Hiscox and Harrison. Medium 8vo **21s**
Steel Research Committee's Report. Fcap. Folio . . . **31s 6d**
Steel : Elliott's Weights of Steel. Medium 8vo **£5 5s**
Stockowner's Veterinary Aid. Archer. Crown 8vo . . . **7s 6d**
Stone Quarrying—Practical. Greenwell and Elsden. Med. 8vo . **15s**
Stone Working Machinery. Bale. Crown 8vo **10s 6d**
Strains, Handy Book for the Calculation of. Humber. Crown 8vo **7s 6d**
Strains on Structures of Ironwork. Shields. 8vo **5s**
Streamline Kite Balloons. Sumner. Medium 8vo . . . **10s 6d**
Submarine Telegraphs. Bright. Super Royal 8vo . . . **£3 3s**
Submarine Torpedo Boat. Hoar. Crown 8vo **12s**
Survey Practice. Jackson. 8vo **12s 6d**
Surveying. Whitelaw. Demy 8vo **12s 6d**
Surveying for Settlers. Crosley. Small Crown 8vo . *Nearly Ready*
Surveying Sheets for Professional and Educational Use. Oblong Royal 8vo **1s 6d**
Surveying, Land and Marine. Haskoll. Large Crown 8vo . . **9s**
Surveying, Land and Mining. Leston. Large Crown 8vo . . **9s**
Surveying, Practical. Usill and Leston. Large Crown 8vo . **8s 6d**
Surveying with the Tacheometer. Kennedy. Demy 8vo . . **12s 6d**
Surveyor's Field Book for Engineers and Mining Surveyors. Haskole. Crown 8vo **12s 6d**
Tanning Materials & Extract Manufacture. Harvey. Demy 8vo . **15s**
Tanning (Practical). Rogers and Flemming . . . *Nearly Ready*
Tannins (Synthetic). Grasser and Enna. Demy 8vo . . . **12s**
Tea Machinery and Tea Factories. Wallis-Tayler. Medium 8vo . **28s**
Technical Guide, Measurer, and Estimator. Beaton. Waistcoat-pocket size **2s**
Technical Terms : English-French, French-English, Fletcher. Waistcoat-pocket size **2s**
Technical Terms : English-German, German-English. Horner and Holtzmann. Waistcoat-pocket size **3s 6d**
Technical Terms : English-Spanish, Spanish-English. Monteverde. Waistcoat-pocket size **3s**
Telephones : their Construction, Installation, Wiring, Operation, and Maintenance. Radcliffe and Cushing. Fcap. 8vo . . **9s**

All Published Prices are net.

Telephones : Field Telephones and Telegraphs for Army Use. Stevens. Crown 8vo **3s**
Timber Merchant. Richardson. Fcap. 8vo **4s**
Timber Merchant's Companion. Dowsing. Crown 8vo . . **3s 6d**
Tools for Engineers and Woodworkers. Horner. Demy 8vo . **10s 6d**
Toothed Gearing. Horner. Crown 8vo . . . *New Ed. Preparing*
Traverse Tables. Lintern. Small Crown 8vo **3s 6d**
Tropical Agriculture. Johnson. Demy 8vo **5s**
Tunnelling. Prelini and Hill. Royal 8vo **18s**
Tunnelling, Practical. Simms and Clark. Imp. 8vo **21s**
Tunnel Shafts. Buck. 8vo **12s 6d**
Upholstering. Bitmead. Crown 8vo **2s 6d**
Urban Traffic, Principles of. Stone. Crown 8vo **3s 6d**
Valuation of Real Property. Webb and Hunnings. Demy 8vo **8s 6d**
Valuation of Real Property. Lamputt. Crown 8vo . . . **2s 6d**
Valuation, Tabular Aids to. M'Caw and Lyons. Crown 8vo . . **5s**
Wages Tables. Garbutt. Square Crown 8vo **6s**
Watchmaker's Handbook. Saunier. Crown 8vo **12s 6d**
Watch Repairing. Garrard. Crown 8vo **6s**
Water Engineering. Slagg. Crown 8vo **7s 6d**
Water, Flow of. Schmeer. Medium 8vo **18s**
Water Supplies. Rideal. Demy 8vo **8s 6d**
Water Supply of Cities and Towns. Humber. Imp. 4to . . **£6 6s**
Water Supply (Rural). Greenwell and Curry. Crown 8vo . . **6s**
Water Supply of Towns and the Construction of Waterworks, Burton. Super Royal 8vo **28s**
Weight Calculator. Harben. Royal 8vo **25s**
Wire Ropes for Hoisting. Crown 4to **20s**
Wireless Telegraphy. Erskine-Murray. Demy 8vo *New Ed. Preparing*
Wireless Telegraphy (Framework of). Cadilhac. Demy 8vo . **3s 6d**
Wireless Telephones. Erskine-Murray. Crown 8vo *New Ed. Preparing*
Wireless Telephony. Ruhmer. Demy 8vo **10s 6d**
Wood, The Seasoning of. Wagner. Royal 8vo **21s**
Wood-Carving for Amateurs. By a Lady. Crown 8vo . . **2s 6d**
Woodworking Machinery. Bale. Large Crown 8vo . . . **10s 6d**
Workshop Practice, Modern. Pull. Large Crown 8vo *Nearly Ready*
Works' Manager's Handbook. Hutton. Medium 8vo . . . **18s**

All Published Prices are net.

PRACTICAL HANDBOOKS FOR HOME STUDY.

Issued by THE AMERICAN TECHNICAL SOCIETY.

Agents: CROSBY LOCKWOOD & SON.

NOTE.—The Prices herein quoted are based on American Prices, and therefore subject to revision without notice.

Air Brake. Ludy	12s
Alternating-Current Machinery. Esty	18s
Architectural Drawing and Lettering. Bourne	12s
Armature Winding. Moreton	15s
Automobile Construction and Repair. Hall	21s
Automobile Ignition, Starting and Lighting. Hayward	24s
Bank Bookkeeping. Sweetland	9s
Blueprint Reading. Fairfield and Kenison	15s
Boiler Accessories. Leland	7s 6d
Bridge Engineering—Roof Trusses. Dufour	18s
Building and Flying an Aeroplane. Hayward	9s
Building Code. Fitzpatrick	9s
Building Superintendence. Nichols	12s
Building Superintendence for Reinforced Concrete Structures. Post	9s
Building Superintendence for Steel Structures. Belden	9s
Business English and Correspondence. Barrett	12s
Carpentry. Townsend	12s
Civil Engineering Specifications and Contracts. Ashbridge	12s
Commercial Law. Chamberlain	18s
Compressed Air. Wightman	12s
Contracts and Specifications. Nichols	9s
Corporation Accounts and Voucher System. Griffith	9s
Corporation Law. Abbott, Springer, and Gilmore	21s
Cotton Spinning. Hedrick	15s
Dams and Weirs. Bligh	12s
Department Store Accounts. Sweetland	7s 6d
Descriptive Astronomy. Moulton	15s
Electric Railways. Craveth	7s 6d
Electric Lighting. Harrison	15s
Electric and Gas Welding. Cravens	9s
Electrochemistry and Welding. Burgess	15s
Elements of Electricity. Millikan	12s
Elevators. Jallings	18s
Estimating. Nichols	7s 6d
Fire Insurance Law. Hardy	15s
Fireproof Construction. Fitzpatrick	18s
Ford Car. Bayston	12s
Forging. Jernberg	9s
Foundry Work. Gray	12s
Freehand and Perspective Drawing. Everett	12s
Gas and Oil Engines and Gas Producers. Marks	18s

All Published Prices are net.

Gasoline Automobile. Lougheed 10s
Gasoline Tractors. Hayward 12s
Getting a Good Job. Barrett 7s 6d
Heating and Ventilation. Hubbard 12s
Hydraulic Engineering. Turneaure and Black 18s
Interior Electric Wiring. Nelson 18s
Locomotive Boilers and Engines. Ludy 12s
Machine Design. Wallace 12s
Machine Drawing. Griffin and Adams 14s
Machine-Shop Work. Turner and Perrigo 15s
Mechanical Drawing. Kenison 9s
Meter Testing and Electrical Measurements. Bushnell and Turnbull. 12s
Modern American Homes. Von Holst 15s
Modern Land and Submarine Telegraphy. Macomber . . . 6s
Modern Road Construction. Byrne 9s
Orders of Architecture. Bourne, Brown and Holst 18s
Oxy-Acetylene Welding Practice. Kell 9s
Pattern Making. Ritchey and Monroe 12s
Plumbing. Gray and Ball 12s
Portfolio of the Orders. Bourne, Brown, and Holst . . . 12s
Power Stations and Transmissions. Shaad 12s
Practical Aviation. Chas. B. Hayward. 24s
Practical Bookkeeping. Griffith 12s
Practical Mathematics. Nobbs and Waite 9s
Railroad Engineering. Webb 18s
Real Property Law. Kales 15s
Refrigeration. Arrowood 15s
Reinforced Concrete. Webb and Gibson 12s
Sewers and Drains. Marston and Fleming 12s
Sheet Metal Work. Neubecker 15s
Small Motors, Transformers and Electromagnets 18s
Stair Building and Steel Square. Hodgson 9s
Standard Legal Forms. Lee 15s
Steam Boilers, Care and Operation. Kuss 12s
Steam Boilers, Construction and Design. Kuss 12s
Steam Engines. Ludy 15s
Steam Engine Indicators and Valve Gears. Ludy 9s
Steam Turbines. Leland 9s
Steel Construction. Burt 18s
Storage Batteries. Crocker and Arendt 12s
Strength of Materials. Maurer 9s
Structural Drafting. Dufour 6s
Surveying. Finch 15s
Switchboards. Adams 9s
Telephony. Miller and M'Meen . . . . . *New Ed. Preparing*
Tool and Die Design for Beginners. Shailor 9s
Tool Making. Markham 15s
Trigonometry, Plane. McCarty 6s
Underwriters' Requirements or Safe Electrical Installations. Pierce 9s
Wireless : How to Become a Wireless Operator. Hayward . . 12s
Woollen and Worsted Finishing. Zimmerman 15s
Woollen and Worsted Spinning. Collins 15s

All Published Prices are net.

. A SELECTED LIST OF .

WEALE'S SCIENTIFIC AND TECHNICAL SERIES.

Arranged according to Subjects. ***All these Prices are net.***

Acoustics, *Smith* (116) . . . 2/6
Agricultural Surveying, *Scott* (245). 2/6
Animal Physics, *Lardner*—
Part I (183) 4/6
Part II (184) 3/6
Arches, Piers, &c., *Bland* (111). . 2/-
Architecture, Ancient (128, 130) . 6/-
Design, *Garbett* (18) . . . 3/-
Grecian, *Aberdeen* (130) . . . 1/6
of Vitruvius, *Gwilt* (128) . . 5/-
Orders, *Leeds* (16) 2/6
Orders and Styles (16, 17) . . 5/-
Styles, *Bury* (17) 2/6
Architectural Modelling, *Richardson* (127) 2/-
Arithmetic, *Young* (84) . . . 3/-
Do. do Key (84*) . . 2/6
Equational, *Hipsley* (58) . . 2/-
Blasting and Quarrying, *Burgoyne* (35). 2/-
Boilermakers' Assistant, *Courtney* (211) 3/-
Ready Reckoner, *Courtney* (254) . 6/-
Bookkeeping (83) 1/6
for Farmers, *Woodman* (266) . 3/-
Boot and Shoe Making, *Leno* (262) . 3/-
Brass Founding, *Graham* (162) . . 3/6
Brick-Cutting & Setting, *Hammond* (265) 2/6
Bricklaying, *Hammond* (189) . . 2/6
Brickwork, *Walker* (252) . . . 2/6
Bridges (Iron), *Pendred* (260) . . 2/6
(Tubular and Girder), *Dempsey* (43) 2/6
Building, *Beckett* (206) . . . 5/6
Estates, *Maitland* (247) . . . 2/6
Science of, *Tarn* (267) . . . 4/-
Calculus, Differential, *Woolhouse* (101) 2/-
Carpentry and Joinery, *Tredgold*, Plates, 4to (182*). 7/6
Cattle, Sheep, & Horses, *Burn* (142). 3/6
Cements, Pastes, Glues, *Standage* (276) 3/6
Circular Work in Carpentry, *Collings* (258) 3/6
Coach-Building, *Burgess* (224) . . 3/6
Coal Mining, *Smyth* (180) . . . 4/-
Colouring, Grammar of, *Field* (186) . 3/6
Compound Interest and Annuities, *Thoman* (196) 4/6
Cottage Building, *Allen* (42) . . 2/6
Gardening, *Hobday* (232) . . 2/-
Dairy, Pigs and Poultry, *Burn* (145) 2/6
Decoration, Elementary House, *Facey* (229) 2/6
Decoration, Practical House, *Facey* (257) 3/6
Draining & Embanking, *Scott* (239) 2/-
Drawing and Measuring Instruments, *Heather* (168) . . . 3/-
Dwelling Houses, *Brooks* (132) . . 3/-
Electric Lighting, *Swinton* (282) . 2/-
Farm Roads and Fences, *Scott* (241). 2/6
Farming Economy, *Burn* (141) . 3/6
Foundations, &c., *Dobson* (44) . . 2/-
French Polishing, *Bitmead* (281) . 2/6
Fruit Trees, *Du Breuil* (177) . . 4/6
Garden Receipts, *Quin* (233) . . 2/-
Gas Works, *Hughes & O'Connor* (212) 6/6
Geology, Historical, *Tate* (173) . . 2/6
Physical, *Tate* (174). . . . 2/-
Geometry, Analytical, *Hann* (90) . 2/6
Descriptive, *Heather* (76) . . 2/6
Plane, *Heather* (178) . . . 2/-
Grafting and Budding, *Baltet* (231) . 3/6
Hall-Marking of Jewellery, *Gee* (249) 3/6
Handrailing and Staircasing, *Collings* (230) 3/6
Health, Management of, *Baird* (112*) 1/6
House Book (112, 112*, 194) . . 6/-
Decoration, *Facey* (229, 257) . 6/-
Manager (194) 3/6
Human Understanding, *Locke* (153). 2/-
Irrigation and Water Supply, *Scott* (240) 2/6
Joints Used by Builders, *Christy* (226) 3/6
Kitchen Gardening, *Glenny* (201) . 3/-
Land, Ready Reckoner, *Arman* (61) . 3/-
Landed Estates Management, *Burn* (208) 3/-
Light, *Tarn* (269). 2/-
Locomotive Engine Driving, *Reynolds* (255) 5/-
Engineer, Model, *Reynolds* (278) . 5/-
Logarithms, *Law* (204*) . . . 4/-
Logic, *Emmens* (150) 2/-
Machinery, Details of, *Campin* (236) 3/6
Marine Engineering Elementary, *Brewer* (275) 3/-
Masonry and Stone-Cutting (25) . 3/-
Masting and Rigging, *Kipping* (54) . 3/-
Materials & Construction, *Campin* (216) 3/6
Mathematical Instruments, *Heather* (168-9-70) 7/6
Mathematical Tables, *Law and Young* (204) 5/-
Mathematics, *Campin* (227) . . 3/6

All Published Prices are net.

Measures, Weights, and Moneys, *Woolhouse* (221) 3/-
Meat Production, *Ewart* (250) . . 3/-
Mechanical Engineering, *Campin* (223) 3/6
Medicine, Domestic, *Gooding* (112) . 2/-
Mensuration and Measuring, *Baker* (93). 2/6
Mineral Surveyors' Guide, *Lintern* (195) 4/-
Mining Tools, *Morgans* (172) . . 3/-
Morgans, Plates, 4to (172*) . . 5/-
Music, *Spencer* (69) 2/6
Natural Philosophy, *Tomlinson* (2) . 2/-
Navigation & Nautical Astronomy, *Young* (99) 3/-
Greenwood and Rosser (55) . . 3/-
Optical Instruments, *Heather* (169) . 3/-
Organ Building, *Dickson* (235) . . 3/6
Painting, Fine Art, *Gullick and Timbs* (181) 5/6
Perspective, *Pyne* (20) 2/6
Pianoforte, *Spencer* (71) . . . 1/6
Pioneer Engineering, *Dobson* (213) . 5/-
Plastering, *Kemp* (273) 2/6
Plumbing, *Buchan* (191) . . . 4/6
Pneumatics, *Tomlinson* (12) . . 2/-
Portland Cement, *Faija* (248) . . 3/6
Quantities & Measurements, *Beaton* (156) 2/-
Roads and Streets, *Law, Clark, and Tayler* (197) 6/6
Roof Carpentry, *Collings* (272) . . 2/6
Sailmaking, *Kipping* (149) . . 3/6
Sanitary Work, *Slagg* (203) . . 3/6
Sewage, Irrigation, &c., *Burn* (146). 3/-
Sheet-Metal Workers' Guide, *Crane* (238) 2/6
Shoring, *Blagrove* (261) 2/-
Silversmiths' Handbook, *Gee* (225) . 5/-
Slate and Slate Quarrying, *Davies* (214) 3/6
Smithy and Forge, *Crane* (237). . 3/6
Soils, Manures, and Crops, *Burn* (140) 3/-
Stationery Engine Driving, *Reynolds* (256) 5/-
Steam Engine, *Lardner* (34) . . 2/-
Superficial Measurement, *Hawkings* (285) 4/-
Surveying, *Baker and Dixon* (60) . 3/-
Instruments, *Heather* (170) . . 3/-
Subterraneous, *Fenwick* (117) . 3/-
Tree Planter and Propagator, *Wood* (209) 3/-
Pruner, *Wood* (210) 2/-
Ventilation of Buildings, *Buchan* (271) 4/-
Water, Power of, *Glynn* (82) . . 2/6
Well Sinking, *Swindell & Burnell* (31) 3/6

WEALE'S EDUCATIONAL SERIES.

English Grammar, *Clarke* (11) . . 2/-
Greek Grammar, *Hamilton* (14). . 2/-
Lexicon, *Hamilton* -
Greek and English (15) . . . 3/-
English and Greek (17) . . . 2/6
Complete in 1 vol. 6/-
Latin Grammar, *Goodwin* (19) . . 2/-
Dictionary, *Goodwin*—
Latin and English (20) . . . 2/6
English and Latin (22) . . . 2/-
Complete in 1 vol. 5/-
Italian Grammar, *Elwes* (27) . . 2/-
Triglot Dictionary, *Elwes*, English-French-Italian (30) . . . 3/-
French-Italian-English (32) . . 3/-
Spanish Grammar, *Elwes* (34) . . 2/6
Dictionary, *Elwes* (35) . . . 8/6
French Grammar, *Strauss* (24) . . 2/-
German Reader, *Strauss* (40) . . 1/-
Hebrew Dictionary, *Bresslau*—
Hebrew and English (44) . . 7/6
English and Hebrew (46) . . 3/6
Hebrew Grammar, *Bresslau* (46*) . 2/-
French and English Phrase Book (47). 1/6
Composition and Punctuation, *Brenan* (48) 2/-
Derivative English Spelling, *Rowbotham* (49) 2/-
Extempore Speaking, *Bautain* (51) . 3/-
Portuguese Grammar, *Elwes* (55) . 2/6
Dictionary, *Elwes* (56) . . . 8/6
Cæsar's Commentaries on the Gallic War, *Young*. 2/6

All Published Prices are net.

LONDON: CROSBY LOCKWOOD & SON,
7 STATIONERS' HALL COURT, LUDGATE HILL, E.C.4.

Printed in Great Britain by UNWIN BROTHERS, LIMITED, WOKING AND LONDON.